


JOB SITE PLANS

This set of plans must be kept on the job site of work at all times per Sarasota County Ordinance Sarasota County Planning & Development Services



Bay Street Village 7-Unit Condominium

148 Navigation Circle Osprey, Florida 34229



Client:

DR Horton 13880 Treeline Ave., Suite 3 Fort Myers, FL 33913 239-225-2633

Architect:

BSB Design, Inc. 11512 Lake Mead Ave. Unit 301 Jacksonville, FL 33618 Phone: 904-732-7335 Fax: 877-283-0404

Structural Engineer:

Integral Engineering, Inc. 16704 Tobacco Rd. Lutz, Florida 33558 Phone: 813-908-0402

Mechanical Engineer:

Stepanek-Lewis and Associates 22557 Twelve Oaks Way Wesley Chapel, Florida 33544 Phone: 813-991-1248

Electrical Engineer:

Emerald Engineering 4048 Cox Drive Land O' Lakes, Florida 34639 Phone: 813-995-0300


Plumbing Engineer:

Stepanek-Lewis and Associates 22557 Twelve Oaks Way Wesley Chapel, Florida 33544 Phone: 813-991-1248

Safety Harbor, Florida 34695

7-30-1

G1



TO THE BEST OF MY KNOWLEDGE SAID PLANS AND SPECIFICATIONS COMPLY

553 AND 633, FLORIDA STATUTES.

WITH THE APPLICABLE MINIMUM BUILDING CODES AND THE APPLICABLE MINIMUM FIRE SAFETY STANDARDS AS DETERMINED IN ACCORDANCE WITH CHAPTERS

GENERAL NOTES

- These documents are the property of the architect and shall not be copied duplicated, altered, modified or revised in any way without the expressed written approval of the architect.
- 2. To the best of the architects' knowledge these construction documents are in conformance with the requirements of the building authorities having jurisdiction over this tupe of construction and occupancy.
- 3. It is the intent of the architect to delineate these documents as accurate as possible for the purpose of graphic representation. Do not "scale" these documents. The dimensions shown are to take precedence over scaling the documents. The general contractor shall take full responsibility for any incorrect work and any repair of said work as a result of scaling
- 4. All work performed by the general contractor shall comply and conform with local and state building codes, ordinances and regulations, along with all other authorities having jurisdiction. The general contractor is responsible to be aware of these requirements and governing regulations.
- The general contractor shall thoroughly review and become familiar with these documents. Upon review, the general contractor shall document and notify the architect of any errors, omissions, discrepancies and / or inconsistencies prior to the start of any portion of the proposed work. The architect shall review the proposed corrections after the receipt of notification. The discovery of discrepancies and / or conflicts after the start of work shall be the full responsibility of the general contractor to
- 6. The general contractor shall be responsible for the correction of any errors, omissions, discrepancies and / or inconsistencies which have not been brought to the architects' attention.
- The general contractor shall accept the premises as is, in its current state. The owner shall assume no responsibility for the condition of the existing site, and its contents, at the time of bidding or thereafter.
- 8. The general contractor shall field verify all existing site conditions, along with dimensions, prior to the start of any portion of the work. All findings discrepancies and concerns shall be brought to the owners' attention in
- 9. The general contractor shall be responsible for all work and materials represented on these documents including the work and materials furnished by subcontractors and vendors.
- 10. Deviations from these documents in the construction phase shall be reviewed by the architect and the owner prior to the start of work in question. Any deviations from these documents without prior review, shall be the sole responsibility of the general contractor.
- II. It is the sole responsibility of the general contractor to determine erection procedure, means and methods and sequence of construction.
- 12. The general contractor is responsible to produce and comply with an approved construction schedule acceptable to the owner's expectations.
- 13. The owner shall furnish any and all reports received from the geotechnical engineer (soil reports), on the study of the proposed site, to the architect, structural engineer and general contractor. In the event the geotechnical reports do not exist, the soil condition shall be assumed to be a minimum design soil pressure stated by the structural engineer of record for the purpose of structural design. General contractor shall assure the soil conditions meet or exceed this criteria.
- 14. Shop drawing review and distribution, along with product submittals, requested in the construction documents, shall be the sole responsibility of the general contractor, unless directed otherwise under a separate
- 15. The architect shall not accept, or review any request for shop drawing review and / or stamp without the review and stamp of the general contractor clearly shown on the documents.

WALL LEGEND

2x4 INTERIOR PARTITION WALL

	2x6 INTERIOR PLUMBING WALL
	2X8 P.T. EXTERIOR FURRED WALL W EXTERIOR SHEATHING PER STRUCTURAL
	6" CMU WALL PER STRUCTURAL DWGS
	6" CMU WALL W/ 2X P.T. FURRING AT INTERIOR FINISH SIDE OF UNITS
1	INDICATES LINE OF I HOUR RATED TENANT SEPARATION. SEE BUILDING SECTIONS FOR TESTED ASSEMBLIES.

DIMENSION NOTE

INTERIOR DIMENSIONS ARE TAKEN FROM FACE OF STUD TO FACE OF STUD, UNLESS NOTED OTHERWISE.	EXTERIOR DIMENSIONS ARE TAKEN FROM FACE OF SHEATHING TO INTERIOR FACE OF STUD, UNLESS NOTED OTHERWISE.
VARIES ,	VARIES
MASONRY DIMENSIONS ARE TAKEN FROM FACE TO FACE OF MASONRY UNIT OR FACE OF MASONRY UNIT TO FACE OF STUD UNLESS NOTED OTHERWISE.	
NARIES NARIES	

PROJECT INFORMATION

	PROJECT NAME:	BAY STREET VIL	LAGE				
	PROJECT NUMBER:	O2TI2O34					
	PROJECT LOCATION:	SARASOTA, FLOI	RIDA				
	PROJECT JURISDICTION:		SARASOTA COUN	ITY, FLORID	A		
	APPLICABLE CODES: BUILDING		2014- FLORIDA 1	BUILDING CO	DDE		
	FIRE SAFETY		2014- FLORIDA 1	BUILDING CO	DDE / NFPA IOI		
	ACCESSIBILITY		2014- FLORIDA 1	BUILDING CO	ODE		
	FAIR HOUSING		1998- FAIR HOU	ISING ACT D	ZESIGN MANUAL		
	PLUMBING		2014- FLORIDA I	BUILDING CO	DDE - PLUMBING		
	MECHANICAL		2014- FLORIDA BUILDING CODE - MECHANICAL				
	ELECTRICAL		2008- NATIONAL ELECTRICAL CODE				
•	LIFE SAFETY		2012- LIFE SAFETY CODE (NFPA 101)				
	PROJECT DESCRIPTION:		TWO STORY STA	CKED FLAT	CONDOMINIUM BUILDING		
			• •				
	OCCUPANCY CLASSIFICA	TION:	R2				
	CONSTRUCTION TYPE:		IIIB				
	AUTOMATIC FIRE SPRINK				E : NFPA I3R		
	FIRE ALARM SYSTEM CLASSIFI		CATION:	MANUAL			
	ALLOWABLE HEIGHT & BUILDING AREAS		ALLOWED		PROVIDED (WORST CASE)		
	HEIGHT IN FEET:		55'-0"		30'-0"		
	MAX. NO. OF STORIES:		4		2		
	BUILDING AREA:						

IST FLOOR:	16,000	6 <i>8</i> 28
2ND FLOOR:	16,000	10,963
FIRE RESISTANCE RATIN	65: (FBC2014/ BUILDING TABLE 601)	
EXTERIOR LOAD	BEARING WALLS	2 HOUR
EXTERIOR NON-L	OAD BEARING WALLS	SEE BELOW
STRUCTURAL FRA GIRDERS, TRUSSE	ME - INCLUDING COLUMNS,	— O HOUR
NONBEARING INTE PARTITIONS	ERIOR WALLS AND	O HOUR
	CTION - INCLUDING MS AND JOISTS	O HOUR

SUPPORTING BEAMS AND JOISTS FIRE RESISTANCE RATING REQUIREMENTS FOR EXTERIOR WALLS BASED ON FIRE SEPARATION DISTANCE (FBC 2014 Table 602)

ROOF CONSTRUCTION - INCLUDING

	•
exterior bearing #	Oft to 5 ft 3-hour
non-bearing walls	5 ft to 10 ft 2-hour
(horizontal separation from common property	10 ft to 20 ft 2-hour
line or assumed	20 ft to 30 ft I-hour
property line)	over 30 ft O-hour

MAXIMUM	AREA C	F EXTER	OR WALL	. OPENING	55 (FBC 2	014 Table	705.8)	
CLASSIFICATION		FIRE SEPARATION DISTANCE (feet)						
OF OPENING	0-3	3-5	5 - 10	10 - 15	15 - 20	20 - 25	25 - 30	OVER 30
UNPROTECTED	N/A*	N/A*	10%*	15%*	25%*	45%*	70%*	UL
PROTECTED	N/A	15%	25%	45%	75%	UL	UL	UL
N/A = NOT ALLOWED UL = UNLIMITED								

*Buildings whose exterior bearing wall, exterior nonbearing wall and exterior structural frame are not required to be fire-resistance rated shall be permitted to have unlimited unprotected openings.

704.8.1 Automatic sprinkler system. In buildings equipped throughout with an automatic sprinkler system in accordance with Section 903.3.1.1, the maximum allowable area of unprotected openings in occupancies other than Groups H-1, H-2 and H-3 shall be the same as the tabulated limitations for protected openings.

SECTION 1207-SOUN	ND TRANSMISS	510N		l
OUND TRANSMISSION SUMMARY				
BUILDING ELEMENT	CLASS (STC.	ANSMISSION) RATING FOR) ASSEMBLIES	FIELD TESTED (STC) REQUIREMENTS	 F
	REQUIRED	PROVIDED	REQUIRED	
TENANT SEPARATION WALLS -VERTICAL	50	54	4 5	
TENANT SEPARATION WALLS- HORIZONTAL	50	53	45	
	CLASS (IIC)	NSULATION RATING FOR ASSEMBLIES		
	REQUIRED	PROVIDED	REQUIRED	
TENANT SEPARATION HORIZONTAL	50	50	45	

SHEET INDEX

GENERAL

COVER SHEET

ARCHITECTURAL

INDEX, PROJECT INFO, AND GENERAL NOTES

A-0.2 **FAIR HOUSING GUIDELINES**

A-2.1 FIRST AND SECOND FLOOR BUILDING PLANS

A-2.2 **ROOF PLAN PLAN AND TRIM PROFILES**

A-2.3 **UNIT "A" AND "B" FLOOR PLANS**

A-2.4 **UNIT "C" AND "D" FLOOR PLANS**

A-3.1 **EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS**

A-3.2 A-4.1 **BUILDING SECTIONS**

A-4.2 **BUILDING AND WALL SECTIONS**

A-4.3 WALL SECTIONS

A-5.1 **ROOF AND STAIR DETAILS**

A-5.2 WINDOW AND DOOR DETAILS

RATED ASSEMBLY DETAILS

STRUCTURAL

FOUNDATION PLANS AND DETAILS **S2.0**

1ST FLOOR STRUCTURAL PLAN LOWER ROOF PLAN AND 2ND FLOOR FRAMING **S3.0**

2ND FLOOR STRUCTURAL PLAN

S5.0 UPPER ROOF FRAMING PLAN

S6.0 STRUCTURAL WALL SECTIONS

SD1 STRUCTURAL DETAILS

SD2 STRUCTURAL DETAILS SD3 STRUCTURAL DETAILS

STRUCTURAL DETAILS

ELECTRICAL

E0.1 **ELECTRIC NOTES AND LEGEND**

E0.2 **ELECTRIC PANEL DIAGRAMS AND SCHEDULES**

E1.1 **BUILDING ELECTRICAL PLANS**

E2.1 UNIT 'A' AND 'B' ELECTRIC PLANS

E3.1 UNIT 'C' AND 'D' ELECTRIC PLANS

MECHANICAL

BUILDING MECHANICAL PLAN AND NOTES

UNIT 'A' AND 'B' MECHANICAL PLANS

UNIT 'C' AND 'D' MECHANICAL PLANS

PLUMBING


PLUMBING NOTES AND SCHEDULES


SANITARY PLANS AND RISERS

P2.1 P3.1 **UNIT 'A' AND 'B' PLUMBING PLANS**

UNIT 'C' AND 'D' PLUMBING PLANS

SITE LOCATION MAP





3880 Treeline Ave, Fort Myers, Florida

Street Village
Condominium Building

Circle 34229 Navigation or Prey, Florida 3 Bay 7 Unit

www.bsbdesign.com 100 Main St. Suite 209 Safety Harbor, Florida 34695 813 265 4808

JOB NO: 02T12034 PROJ MGR: JD DRAWN: JD, AM CHECKED: CODE DATA, GENERAL NOTES,

SYMBOLS & ABBREVIATIONS

A0.1

9

GENERAL REQUIREMENTS & PORTIONS OF FAIR HOUSING ACT GUIDELINES

GENERAL NOTE

INFORMATION PROVIDED ON THIS PAGE APPLY TO ALL FHA COVERED UNITS, REFER TO THE CURRENT FHA MANUAL FOR EXACT DETAILS & DIRECTION, NOTIFY ARCHITECT OF ANY DISCREPANCIES.

DEFINITIONS

"COVERED MULTIFAMILY DWELLINGS" ARE:

(1) ALL DWELLING UNITS IN BUILDINGS CONTAINING FOUR OR MORE DWELLING UNITS IF SUCH BUILDINGS HAVE ONE OR MORE ELEVATORS, AND

(2) ALL GROUND FLOOR DWELLING UNITS IN OTHER BUILDINGS CONTAINING FOUR OR MORE DWELLING UNITS "ADAPTABLE DWELLING UNITS" ARE:

DWELLING UNITS IN BUILDINGS CONTAINING FOUR OR MORE DWELLING UNITS THAT INCLUDE THE FEATURES OF ADAPTABLE DESIGN AS SPECIFIED IN 24 CFR 100.205(c) (2)-(3)

GENERAL REQUIREMENTS

(1) TO BE A "COVERED" MULTIFAMILY DWELLING UNIT, ALL OF THE FINISHED LIVING SPACE MUST BE ON THE SAME LEVEL. (EX. SINGLE STORY) (2) MULTI STORY DWELLING UNITS ARE NOT COVERED BY THESE GUIDELINES UNLESS LOCATED WITHIN A BUILDING THAT IS EQUIPPED WITH ONE OR MORE ELEVATORS, IN WHICH CASE, THE PRIMARY ENTRY LEVEL IS COVERED. (3) "COVERED" MULTIFAMILY DWELLINGS, AS DEFINED HEREIN, WHICH ARE INTENDED FOR FIRST OCCUPANCY AFTER MARCH 13, 1991, SHALL BE DESIGNED AND CONSTRUCTED TO HAVE AT LEAST ONE BUILDING ENTRANCE ON AN ACCESSIBLE ROUTE UNLESS IT IS IMPRACTICAL TO DO SO BECAUSE OF THE TERRAIN OR UNUSUAL CHARACTERISTICS OF THE SITE, AS DETERMINED BY COMMISSION RULE. (4) "COVERED" MULTIFAMILY DWELLINGS, AS DEFINED HEREIN, SHALL

COMPLY WITH THE FOLLOWING SEVEN REQUIREMENTS: I. "COVERED MULTIFAMILY DWELLING UNITS MUST HAVE AT LEAST ONE BUILDING ENTRANCE ON AN ACCESSIBLE ROUTE

ACCESSIBLE TO AND BE USABLE BY PEOPLE WITH DISABILITIES 3. ALL DOORS SHALL BE DESIGNED AS "USABLE" TO ALLOW PASSAGE INTO AND WITHIN ALL PREMISES. DOORS SHALL BE DESIGNED TO ALLOW PASSAGE OF A WHEEL CHAIR 4. THERE SHALL BE AN ACCESSIBLE ROUTE INTO AND THROUGH

THE "COVERED" DWELLING UNITS 5. ALL PREMISES WITHIN THE "COVERED" DWELLING UNITS SHALL

CONTAIN LIGHTS SWITCHES, ELECTRICAL OUTLETS, THERMOSTATS AND OTHER ENVIROMENTAL CONTROLS IN ACCESSIBLE LOCATIONS 6. ALL PREMISES WITHIN THE "COVERED" DWELLING UNITS SHALL CONTAIN REINFORCEMENTS IN BATHROOM WALLS TO ALLOW FOR FUTURE INSTALLATIONS OF REQUIRED GRAB BARS.

7. ALL "COVERED" DWELLING UNITS SHALL BE DESIGNED WITH USABLE KITCHENS AND BATHROOMS TO ALLOW FOR THE NECESSARY MANUEVERING SPACE FOR INDIVIDUALS WITH DISABILITIES. (5) CLEAR FLOOR SPACE FOR A STATIONARY WHEELCHAIR SHALL BE

(6) CLEAR FLOOR SPACE FOR A WHEELCHAIR TO MANUEVER OR TURN AROUND SHALL BE 60" DIAMETER MINIMUM (CLEAR OF ALL OBSTRUCTIONS)-ALTERNATIVELY, A "T"-TURN SPACE CAN BE PROVIDED IF CONDITIONS

(7) ALTHOUGH THE AMERICANS WITH DISABILITIES ACT(ADA) GENERALLY DOES NOT COVER DWELLING UNITS, PUBLIC AND COMMON USE AREAS OF DEVELOPMENTS MAY BE REQUIRED TO COMPLY WITH THE REQUIREMENTS OF ADA, SUCH AS SITE ACCESSIBILITY, COMMON ENTRANCES, COMMUNITY ROOMS/AREAS, ETC. THESE AREAS SHALL COMPLY WITH THE REQUIREMENTS OF ADA AND ANSI AII7.I-1998

(8) ALL DOORS INSTALLED WITHIN A "COVERED" MULTIFAMILY DWELLING UNIT, THAT ARE REQ'D. FOR PASSAGE, SHALL COMPLY WITH ANSI AIIT.I-1998 SECTION 4.13. A MINIMUM OF 32" CLEAR, UNOBSTRUCTED WIDTH, WHEN THE DOOR IS IN THE 40 DEG. OPEN POSITION, MEASURED FROM THE FACE OF THE DOOR TO THE NEAREST PROJECTION (DOOR STOP)

(9) OPENING DEPTHS OF GREATER THAN 24" SHALL BE A MINIMUM OF 36" WIDE, CLEAR OF ANY OBSTRUCTIONS

(10) THE GUIDELINES ALLOWS THE OPTION OF SPECIFICATION "A" OR SPECIFICATION "B" FOR BATHROOMS WHEN DESIGNING FOR COMPLIANCE. THE MAIN DIFFERENCE BETWEEN SPEC "A" AND "B" IS THE PARALLEL APPROACH TO THE BATH TUB., REQUIRED FOR SPECIFICATION "B" BATHS. IF ONE BATHROOM IS SELECTED TO MEET SPECIFICATION "B", ALL OTHER BATHROOMS WITHIN THE DWELLING UNIT NEED ONLY MEET THE ACCESSIBILITY REQUIREMENTS AND NOT THE CLEAR FLOOR SPACE REQUIREMENTS. IF SPECIFICATION "A" IS SELECTED THEN ALL BATHROOMS WITHIN THE DWELLING UNIT SHALL COMPLY WITH SPECIFICATION "A"

(II) THE INFORMATION CONTAINED IN THESE DOCUMENTS SHALL BE UTILIZED AS A GUIDE TO COMPLY WITH THE "FAIR HOUSING ACT". THE FULL PRINTED DOCUMENT OF THE FAIR HOUSING GUIDE LINE MANUAL IS AVAILABLE THROUGH THE OFFICE OF DCA. THE CONTRACTOR SHALL BE AWARE OF THE REQUIREMENTS OF THE FHA. INFORMATION NOT SHOWN ON THESE DOCUMENTS DOES NOT NEGATE THE REQUIREMENT TO COMPLY. (12) IF A POWDER ROOM IS LOCATED ON THE ACCESSIBLE LEVEL OF A

MULTI-STORY DWELLING UNIT, IT SHALL BE DESIGNED AND CONSTRUCTED TO MEET THE CLEAR FLOOR SPACE FOR FIXTURES AND THE REINFORCED WALLS FOR INSTALLATION OF GRAB BARS (13) TOTAL NUMBER OF PARKING SPACES PROVIDED SHALL INCLUDE 2% OF

THE TOTAL NUMBER TO BE MADE ACCESSIBLE AND BE ON AN ACCESSIBLE ROUTE. IF MORE THAN ONE TYPE OF PARKING SPACE IS PROVIDED THEN EACH OF THE TYPES OF PARKING SHALL COMPLY. (14) THRESHOLDS AT PRIMARY ENTRANCE DOORWAYS SHALL NOT EXCEED 3/4

IN (IAMM), INCLUDING THE THRESHOLD HIEGHT. MAXIMUM OF 1/2" DIFFERENCE IN FLOOR LEVELS. SECONDARY EXTERIOR DOORS MAY HAVE A 4" STEP TO THE OUTSIDE. RAISED THRESHOLDS AND FLOOR LEVEL CHANGES AT ACCESSIBLE

DOORWAYS SHALL BE BEVELED WITH A SLOPE NO GREATER THAN 1:2 (15) A MINIMUM OF 30" X 48" CLEAR FLOOR SPACE SHALL BE PROVIDED AND CENTERED ON ALL KITCHEN APPLIANCES, SEE LATEST EDITION OF THE FHA DESIGN MANUAL FOR APPLICABLE FORWARD & PARALLEL APPROACHES ALLOWED.


(16) A MINIMUM OF 40" CLEARANCE SHALL BE PROVIDED BETWEEN ALL CABINET COUNTER TOP EDGES. A MINIMUM OF 40" SHALL BE PROVIDED BETWEEN ALL FACES OF APPLIANCES AND CABINETS COUNTER TOPS.

(IT) ALTHOUGH THESE GUIDELINES DO NOT REQUIRE CLEAR FLOOR SPACE AT THE WASHER AND DRYER EQUIPMENT, IT IS RECOMMENDED THAT SUFFICIENT CLEAR FLOOR SPACE BE PROVIDED FOR THE USE BY PERSONS

(18) REFER TO THE "FAIR HOUSING ACT GUIDELINES MANUAL" FOR CONDITIONS THAT MAY NOT BE COVERED BY THESE DRAWINGS AND INFORMATION

(14) WALK-IN TYPE PANTRIES THAT ALLOW A PERSON TO PASS THROUGH THE DOOR OPENING SHALL COMPLY WITH THESES GUIDELINES. PANTRIES AND OTHER SHALLOW TYPE CLOSETS ARE NOT COVERED BY THESE GUIDELINES SINCE PASSAGE ISN'T REQUIRED.

(20) THE DIAGRAMS SHOWING THE SPECIFICATIONS FOR AN "A" AND "B" BATHROOM ARE INTENDED AS GUIDES FOR THE DESIGN. THEY ARE NOT INTENDED TO LIMIT THE DESIGN POSSIBILITIES. THIER INTENT IS TO SHOW THE MINIMUM REQUIREMENTS NECESSARY TO COMPLY WITH THE FAIR HOUSING ACT GUIDELINES.



reeline yers, Flo 3880 Fort N

Village nium Building 34 24 /igation Florida Ze


DESIGN www.bsbdesign.com 10000MaMai6t8ateSuStait20209 Safety Harbor, Florida 34695


0

3

813 265 4808 JOB NO: 02T12034 PROJ MGR: JD DRAWN: JD, AM CHECKED: JD

ACCESSIBILITY







Bay Street Village
7 Unit Condominium Building

148 Navigation Circle Osprey, Florida 34229



100 Main St. Suite 209 Safety Harbor, Florida 34695 813 265 4808

JOB NO: 02T12034 PROJ MGR: JD DRAWN: JID),AAM CHECKED: 7-UNIT FIRST FLOOR BUILDING PLAN

A2.1

987

ATTIC VENT CALCULATION

MAIN FLOOR NOTES

- ALL INTERIOR PARTITIONS (首首) ARE 3 I/2" ROUGH, UNLESS OTHERWISE NOTED.
 ALL ANGLED PARTITIONS ARE 45
- DEGREES UNLESS OTHERWISE NOTED.

 3. ALL DIMENSIONS ARE TO FACE OF MASONRY, FRAME, OR SHEATHING UNLESS OTHERWISE NOTED.
- 4. WINDOW SUPPLIER TO VERIFY AT LEAST ONE WINDOW IN ALL BEDROOMS TO HAVE A CLEAR EGRESS OPENING OF 5.71 SQ. FT. WITH MIN. NET CLEAR OPENING OF 24" IN HEIGHT AND NET CLEAR
- OPENING OF 20" IN WIDTH; SILL HEIGHT NOT GREATER THAN 44" ABOVE FLOOR. 5. ALL ELECTRICAL AND MECHANICAL EQUIPMENT & METERS ARE SUBJECT TO
- RELOCATION DUE TO FIELD CONDITIONS CONTRACTOR TO VERIFY. 6. EXTERIOR DOORS AND WINDOWS TO BE
- IMPACT RESISTANT. BUILDER TO SUBMIT APPLICABLE DATA TO BUILDING DEPT. 7. SHOWER GLASS AND SHOWER DOORS TO
- BE TEMPERED GLAZING.

 8. ALL INTERIOR DOORS TO BE FRAMED 4" MINIMUM FROM CORNERS.

Bay Street Village
7 Unit Condominium Building

148 Navigation Circle Osprey, Florida 34229

ら

E

98

100 Main St. Suite 209

Safety Harbor, Florida 34695 813 265 4808 JOB NO: 02T12034 PROJ MGR: JD CHECKED: 7-UNIT BUILDING ROOF PLAN, WALL SECTION, AND TRIM PROFILES

A2.2

ELEVATION

1 BALCONY EDGE FOAM TRIM PROFILE

SCALE: 3"=1'-0"


FOAM EAVE TRIM PROFILE

SCALE: 3"=1"-0"

2 CATILEVER FOAM BRACKET DETAIL

SCALE: 3"=1'-0"

PROFILE





- ALL INTERIOR PARTITIONS (首首) ARE 3 I/2" ROUGH, UNLESS OTHERWISE NOTED.
 ALL ANGLED PARTITIONS ARE 45 DEGREES UNLESS OTHERWISE NOTED.
 ALL DIMENSIONS ARE TO FACE OF MASONRY, FRAME, OR SHEATHING UNLESS OTHERWISE NOTED.
- OTHERWISE NOTED.

 4. WINDOW SUPPLIER TO VERIFY AT LEAST ONE WINDOW IN ALL BEDROOMS TO HAVE A CLEAR EGRESS OPENING OF 5.7
- HAVE A CLEAR EGRESS OPENING OF 5.7
 SQ. FT. WITH MIN. NET CLEAR OPENING
 OF 24" IN HEIGHT AND NET CLEAR
 OPENING OF 20" IN WIDTH; SILL HEIGHT
 NOT GREATER THAN 44" ABOVE FLOOR.

 5. ALL ELECTRICAL AND MECHANICAL
 EQUIPMENT & METERS ARE SUBJECT TO
 RELOCATION DUE TO FIELD CONDITIONS;
 CONTRACTOR TO VERIFY.

 6. EXTERIOR DOORS AND WINDOWS TO BE
 IMPACT RESISTANT. BUILDER TO SUBMIT
 APPLICABLE DATA TO BUILDING DEPT.

 7. SHOWER GLASS AND SHOWER DOORS TO
 BE TEMPERED GLAZING.

 8. ALL INTERIOR DOORS TO BE FRAMED 4"
 MINIMUM FROM CORNERS.

			ı	8
ON				
· · · · · · · · · · · · · · · · · · ·	1528	SQ.FT.		
	1528	SQ.FT.		
	259	SQ.FT. SQ.FT. SQ.FT.		

13880 Treeline Ave, S Fort Myers, Florida

UNIT B **AREA TABULATI** MAIN FLOOR PLAN TOTAL A/C AREA ENTRY PORCH GARAGE LANAI TOTAL AREA 1889 SQ.FT.

7	9'-43%"	12'-7%"	8'-3 ³ / ₄ "		6'-10 ³ / ₄ " 6'-9/ ₄ "	
	25 5 H		(2) 3 55H		(2) 35 5H	
				0.50.75.1		
4'-2"	Bedroom 2	8'-0' G.6.	2680 FULL LITE	Tanai Concrete		
255H	5'-03/4" 2'-3"	3'-10"	Family Room CARPET 9'-4" CLG 15'-5"	II'-2"	Master Bedroom CARPET q'-4" CLG 12'-q"	
6-83/4"	32" x 60" TUB / SHMR			Den 54 CLG 5		
34'-0" 5'-1/4" 1/2 3594	Bath 2 TILE 8'-6' CLG FHA - SPEC B' WC		Dining CARPET 8'-6" CLG	8'-6" CLG 3'-6" q", 2'-5" 4'-7/2" m	TEMP. GLASS SHWR ENCLOSURE—FMB TEMP. GLASS SHWR ENCLOSURE—FMB 36'X6 SHWR	34.0"
21-53/4" -113/4"	3'-1/4" 484		FMB FMB		3'-0" Master Bath TILE 8'-6' CL6	42" HALF WALL W
	· •	COMPLIANT DWELLING UNIT 0.2 FOR FAIR HOUSING	REF. RANGE	2468 2468 2468	Laundry WIC CARPET 8'-6" CL6 6'-94"	GLASS ENCLOSURE ABV.
			O.H. CAB O O.H.	Pantry (4) SH. HC THRESHOL	21068 R/5 R/5 LD 15'-3/4"	

54'-0**"**

54'-0**"**

10'-0"

13'-8"

Unit A Floor Plan

FHA COMPLIANT

SCALE: 1/4"=1'-0"

30'-4"

UNIT A AREA TABULATION		
MAIN FLOOR PLAN	1574	SQ.FT.
TOTAL A/C AREA	1574	SQ.FT.
ENTRY PORCH		SQ.FT.
GARAGE		SQ.FT.
LANAI		SQ.FT.
TOTAL AREA		

JOB SITE PLANS

This set of plans must be kept on the job site of work at all times per Sarasota County Ordinance Sarasota County Planning & Development Services

Bay Street Village
7 Unit Condominium Building 148 Navigation (Osprey, Florida 3

S S


LO I


138-1

www.bsbdesign.com 100 Main St. Suite 209 Safety Harbor, Florida 34695 813 265 4808

JOB NO: 02T12034 PROJ MGR: JD DRAWN: JID, AMM CHECKED: UNIT A AND UNIT B FLOOR PLANS

A2.3






10'-0"

Unit D 1st Floor Plan

SCALE: 1/4"=1'-0"

SCALE: 1/4"=1'-0"



MAIN FLOOR NOTES NOTE_FLOOR

- ALL INTERIOR PARTITIONS (十十) ARE 3 I/2" ROUGH, UNLESS OTHERWISE NOTED.
 ALL ANGLED PARTITIONS ARE 45
- DEGREES UNLESS OTHERWISE NOTED. 3. ALL DIMENSIONS ARE TO FACE OF MASONRY, FRAME, OR SHEATHING UNLES:
- OTHERWISE NOTED. 4. WINDOW SUPPLIER TO VERIFY AT LEAST ONE WINDOW IN ALL BEDROOMS TO HAVE A CLEAR EGRESS OPENING OF 5.7 SQ. FT. WITH MIN. NET CLEAR OPENING OF 24" IN HEIGHT AND NET CLEAR
- OPENING OF 20" IN WIDTH; SILL HEIGHT NOT GREATER THAN 44" ABOVE FLOOR 5. ALL ELECTRICAL AND MECHANICAL
- EQUIPMENT & METERS ARE SUBJECT T RELOCATION DUE TO FIELD CONDITION CONTRACTOR TO VERIFY. 6. EXTERIOR DOORS AND WINDOWS TO E
- IMPACT RESISTANT. BUILDER TO SUBMI APPLICABLE DATA TO BUILDING DEPT.

 7. SHOWER GLASS AND SHOWER DOORS
- BE TEMPERED GLAZING. 8. ALL INTERIOR DOORS TO BE FRAMED MINIMUM FROM CORNERS.

OR. TO NS; BE	TE:	REVISIONS		PECIFICATIONS ARE PROTEIL LAWS. (C) BSS BSS DESIGN
BE IIT T. TO	ISSUE DATE:	REVISI		THESE PLANS AND SPECIFICATIONS ARE PROTE FEDERAL COPPUREDT LAWS. (C) BSS DESIGN COMPUTED AND ALL COMPUTED AN
	ı			



UNIT D		
AREA TABULATION		
MAIN FLOOR PLAN	806	SQ.FT.
UPPER FLOOR PLAN	849	SQ.FT.
TOTAL A/C AREA	1655	SQ.FT.
ENTRY PORCH		SQ.FT.
GARAGES LANAI		SQ.FT.
TOTAL AREA		SQ.FT.

UNIT C AREA TABULATION MAIN FLOOR PLAN 1244 SQ.FT. TOTAL A/C AREA 1244 SQ.FT. 230 SQ.FT. 86 SQ.FT. GARAGE LANAI 1560 SQ.FT. TOTAL AREA

JOB SITE PLANS

This set of plans must be kept on the job site of work at all times per Sarasota County Ordinance Sarasota County Planning & Development Services

street Village ondominium Building

148 Navigation Circle Osprey, Florida 34229


BSB www.bsbdesign.com 100 Main St. Suite 209 Safety Harbor, Florida 34695 813 265 4808


UNIT C AND UNIT D FLOOR PLANS


A2.4

7-38-1

SCALE: 3"=1'-0"







EXTERIOR ELEVATION NOTES [NOTE_EXTELEY]

GRADE CONDITIONS MAY VARY FOR INDIVIDUAL SITE FROM THAT SHOWN. BUILDER SHALL VERIFY AND COORDINATE PER ACTUAL SITE CONDITIONS.
 EXTERIOR DOORS AND WINDOWS ARE TO

BE PROTECTED WITH METAL STORM PANELS. CONTRACTOR TO SUBMIT APPLICABLE DATA TO BUILDING

DEPARTMENT AS NECESSARY. 3. ALL EXTERIOR COMPONENTS MUST BE FLORIDA APPROVED PRODUCTS. BUILDER TO SUBMIT APPLICABLE DATA TO

BUILDING DEPT.

4. PROVIDE ROOF AND SOFFIT VENTS AS REQUIRED BY CODE AND MANUFACTURERS SPECIFICATIONS. SEE SHEET A2.2 FOR VENTILATION REQUIREMENTS.

Bay Street Village
7 Unit Condominium Building **Circle 34229**

148 Navigation Osprey, Florida

www.bsbdesign.com 100 Main St. Suite 209 Safety Harbor, Florida 34695 813 265 4808


JOB NO: 02T12034 PROJ MGR: PRAWN: JID), AAM CHECKED: BUILDING ELEVATION



EXTERIOR ELEVATION NOTES [NOTE_EXTELEY]

- I. GRADE CONDITIONS MAY VARY FOR INDIVIDUAL SITE FROM THAT SHOWN.
 BUILDER SHALL VERIFY AND COORDINATE PER ACTUAL SITE CONDITIONS.
- 2. EXTERIOR DOORS AND WINDOWS ARE TO BE PROTECTED WITH METAL STORM PANELS. CONTRACTOR TO SUBMIT APPLICABLE DATA TO BUILDING
- DEPARTMENT AS NECESSARY. 3. ALL EXTERIOR COMPONENTS MUST BE FLORIDA APPROVED PRODUCTS. BUILDER TO SUBMIT APPLICABLE DATA TO
- BUILDING DEPT.

 4. PROVIDE ROOF AND SOFFIT VENTS AS REQUIRED BY CODE AND MANUFACTURERS SPECIFICATIONS. SEE SHEET A2.2 FOR VENTILATION REQUIREMENTS.




Bay Street Village
7 Unit Condominium Building


148 Navigation (Osprey, Florida 3




DESIGN 100 Main St. Suite 209 Safety Harbor, Florida 34695 813 265 4808


JOB NO: 02T12034 PROJ MGR: JD DRAWN: JID), AAM CHECKED: SIDES AND REAR ELEVATIONS







SCALE: 3/16"=1'-0"







Circle 34229

148 Navigation Osprey, Florida




Safety Harbor, Florida 34695 813 265 4808 DRAWN: JED, AAM CHECKED: BUILDING SECTIONS





Building Section D-D SCALE: 3/16"=1'-0"



WALL SECTION THRU UNIT C ENTRY

SCALE: 3/4"=1"-0"

WALL SECTION THRU UNIT D PORCH

Street Village Condominium Building Circle 34229

Suite 3 33913

148 Navigation (Osprey, Florida 3


DESIGN www.bsbdesign.com 100 Main St. Suite 209 Safety Harbor, Florida 34695 813 265 4808


JOB NO: 02T12034 PROJ MGR: JD CHECKED:


BUILDING SECTIONS

987

A4.2







TENANT SEPARATION WALL

5 9

A4.3

| Circle | 34229

148 Navigation (Osprey, Florida 3


2-STORY WALL SECTION - EXT. WALL

SCALE: 3/4"=|'-O"


TENANT SEPARATION WALL - UNIT D 2 | I EINAIN 9CALE: 3/4"=1'-0"

STRINGER/LANDING DETAIL


SCALE: 1 1/2" = 1'-0"




9 PIPE PENETRATION - TILE



LANDING/STRINGER DETAIL



10 FLOOR/STRINGER DETAIL



8 HANDRAIL


NOTE: HEIGHTS REFERENCED IN THIS DETAIL ARE FOR INTERIOR OF DWELLING UNITS ONLY. EXTERIOR GUARDRAILS ARE 42" HIGH PER EXTERIOR ELEVATIONS.

HANDRAILS SHALL NOT BE LESS THAN 34" OR MORE THAN 38" IN HEIGHT ABOVE THE STAIR NOSING. HANDRAILS SHALL BE CONTINUOUS PER FLIGHT OF STAIRS. HANDRAILS SHALL BE I 1/2" CLEAR OF ALL ADJACENT FINISH MATERIALS AND ENDS SHALL RETURN TO WALL OR TERMINATE I 1/4"-2" IN CROSS SECTIONAL DIMENSION, OR APPROVED EQUIVALENT, IN NEWEL POSTS OR SAFE TERMINALS. HANDRAILS SHALL BE AND BE SMOOTH WITH NO SHARP EDGES/CORNERS.


STAIR AND RAILING SUPPLIER INSTALLER SHALL SATISFY ALL BUILDING DEPARTMENT APPROVAL REQUIREMENTS FOR THE PRODUCTS THEY PROVIDE OR INSTALL. THE HANDRAIL CONSTRUCTION SHALL BE ABLE TO RESIST A LOAD OF 200 LBS APPLIED IN ANY DIRECTION AT ANY POINT ALONG THE TOP RAIL. GUARDRAILS SHALL NOT BE LESS THAN 36" IN HEIGHT. OPEN RAILS SHALL HAVE INTERMEDIATE RAILS OF 4" SPHERE AN ORNAMENTAL PATTERN SUCH THAT A MAY NOT PASS 4" DIAMETER SPHERE CANNOT PASS THROUGH. THROUGH THE GUARDRAIL CONSTRUCTION SHALL BI ABLE TO RESIST A CONCENTRATED MAY NOT PASS THROUGH LOAD OF 200 LBS IN ANY DIRECTION THIS DIAGRAM ILLUSTRATES THE SPECIFIC THE TRIANGULAR OPENINGS REQUIREMENTS OF THE AT STAIR TREAD, RISER, & BUILDING CODE AND IS BOTTOM SHALL BE SUCH ONLY AN AID FOR THAT A 6" DIAMETER BUILDING DESIGN AND SPHERE CANNOT PASS THROUGH.

HANDRAIL/GUARDRAIL CODE DATA


CONSTRUCTION.




DRIP SCREED - PLASTER





800F TO WALL-TILE





RIDGE AND HIP RIDGE





TYPICAL EAVE - PLASTER

5/8"THK CEMENT-BASED PLASTER FINISH (PER ASTM

C-926) ON CONCRETE MASONRY UNIT CONSTRUCTION.

PROVIDE CONTROL JOINTS AT

LOCATIONS INDICATED ON EXTERIOR

Village nium Building Street VIII: Bay 7 Unit


34 2


lavigation y, Florida


DESIGN www.bsbdesign.com 100 Main St. Suite 209 Safety Harbor, Florida 34695 813 265 4808

JOB NO: 02T12034 PROJ MGR: RAWN: JD, AM **ROOF DETAILS**

Ġ









JAMB AT MASONRY WALL






OVERHEAD GARAGE DOOR HEAD




OVERHEAD GARAGE DOOR JAMB




NOTE: INSTALL GARAGE DOOR ASSEMBLY PER MANUFACTURER'S RECOMMENDATIONS


OVERHEAD GARAGE DOOR RAIN CUT SCALE: 3"=1"-0" SLIDING GLASS DOOR SILL SCALE: 3"=1"-0"




SLIDING GLASS DOOR HEAD



5 SLIDING GLASS DOOR JAMB



NOTE: DOOR TO BE FASTENED TO STRUCTURE PER DOOR MANUFACTURERS INSTALLATION REQUIREMENTS AND RECOMMENDATIONS







EXTERIOR

JOB SITE PLANS ' This set of plans must be kept

on the job site of work at all times per Sarasota County Ordinance Sarasota County Planning & Development Services



RECOMMENDATIONS JAMB AT CMU WALL



NOTE: WINDOW ASSEMBLY TO BE FASTENED TO STRUCTURE PER WINDOW MANUFACTURERS INSTALLATION REQUIREMENTS AND RECOMMENDATIONS

SILL AT CMU WALL

Bay Street Village
7 Unit Condominium Building 148 Navigation (Osprey, Florida 3

Circle 34229

DESIGN www.bsbdesign.com 100 Main St. Suite 209 Safety Harbor, Florida 34695

813 265 4808

السياد دست د

9

JOB NO: 02T12034 PROJ MGR: JD Drawn:JD, am CHECKED: DETAILS


A5.2

- ① CONCRETE BLOCKS*--VARIOUS DESIGNS. CLASSIFICATION D-2 (2 HR.). SEE CONCRETE BLOCK CATEGORY FOR LIST OF ELIGIBLE MANUFACTURERS.
- 2 MORTAR--BLOCKS LAID IN FULL BED OF MORTAR NOM. 3/8 IN. THICK, OF NOT LESS THAN 2-1/4 AND NOT MORE THAN 3-1/2 PARTS OF CLEAN SHARP SAND TO I PART PORTLAND CEMENT (PROPORTIONED BY VOLUME) AND NOT MORE THEN 50 PERCENT HYDRATED LIME (BY CEMENT VOLUME). VERTICAL JOINTS STAGGERED.
- 3 PORTLAND CEMENT STUCCO OR GYPSUM PLASTER-- ADD 1/2 HR TO CLASSIFICATION IF USED. WHERE COMBUSTIBLE MEMBERS ARE FRAMED IN WALL, PLASTER OR STUCCO MUST BE APPLIED ON THE FACE OPPOSITE FRAMING TO ACHIEVE A MAX. CLASSIFICATION OF I-I/2 HR. ATTACHED TO CONCRETE BLOCK
- (4) LOOSE MASONRY FILL--IF ALL CORE SPACES ARE FILLED WITH LOOSE DRY EXPANDED SLAG, EXPANDED CLAY OR SHALE (ROTARY KILN PROCESS), WATER REPELLANT VERMICULITE MASONRY FILL INSULATION, OR SILICONE TREATED PERLITE LOOSE FILL INSULATION ADD 2 HR TO CLASSIFICATION.
- 5 FOAMED PLASTIC* --(OPTIONAL-NOT SHOWN)-- 1-1/2 IN. THICK MAX. 4 FT. WIDE SHEATHING ATTACHED TO CONCRETE BLOCKS (ITEM I) CELOTEX CORP.---TYPE THERMAX

(SEE ITEMS 2 AND 2A)

2 HR. MASONRY WALL

SCALE: NOT TO SCALE




NONBEARING OR BEARING WALL RATING -- I HR.

- MOOD STUDS --- NOM. 2x3 OR 2x4 IN., FLAT WISE, SPACED 24 IN. O.C. MAX, EFFECTIVELY FIRESTOPPED.
- 2 WALLBOARD, GYPSUM* --- FOR NONBEARING WALL RATING --- ONE LAYER OF 5/8 IN. THICK, 4 FT. WIDE WALLBOARD EACH SIDE OF STUDS. WALLBOARD OR LATH APPLIED HORIZONTALLY OR VERTICALLY WITH VERTICAL JOINTS CENTERD ON STUDS, AND NAILED TO STUDS AND BEARING PLATES 7 IN. O.C. WITH 6d CEMENT COATED NAILS, I 7/8 IN. LONG, O.0915 IN. SHANK DIA. AND 1/4 IN. DIA. HEAD. AS AN ALTERNATE, NO. 6 BUGLE HEAD DRYWALL SCREWS, I 7/8 IN. LONG, MAY BE SUBSTITUTED FOR THE 6d CEMENT COATED
- SEE WALLBOARD, GYPSUM* (CKNX) CATEGORY FOR NAMES OF CLASSIFIED COMPANIES. A. WALLBOARD, GYPSUM* --- SAME AS ITEM 2. FOR BEARING WALL RATING --- ADDITIONAL LAYER OF 5/8 IN. THICK, 4 FT. WIDE WALLBOARD EACH SIDE OF STUDS. ATTACHED TO STUDS OVER INNER LAYER 8 IN. O.C. MAX, WITH 8d CEMENT COATED NAILS, 2-3/8 IN. LONG, O.113 IN. SHANK DIA. AND 9/32 IN. DIA.
- 3 JOINTS AND NAIL HEADS --- WALLBOARD JOINTS OF OUTER LAYER COVERED WITH TAPE AND JOINT COMPOUND. NAIL HEADS OF OUTER LAYER COVERED WITH JOINT COMPOUND. AS AN ALTERNATE, NOM 3/32 IN. THICK GYPSUM VENEER PLASTER MAY BE APPLIED TO THE ENTIRE SURFACE OF CLASSIFIED
- 4 BATTS AND BLANKETS* --- (OPTIONAL) --- MAX I IN. THICKNESS GLASS OR MINERAL FIBER BATT
- SEE BATTS AND BLANKETS* (BZJZ) CATEGORY FOR NAMES OF CLASSIFIED COMPANIES. * BEARING THE UL CLASSIFICATION MARKING

1 HR. RATED WALL (BEARING OR NONBEARING)

SCALE: NOT TO SCALE



1. Roofing System* Any UL Class A, B or C Roofing System (TGFU) or Prepared Roof Covering (TFWZ) acceptable for use over nom 15/32 in. thick wood structural panels, min. grade "C-D" or "Sheathing". Nom 15/32 in. thick wood structural panels secured to trusses with No. 6d ringed shank nails spaced 12 in. OC along each truss. Staples having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails. Construction adhesive may be used with either the nails or staples

2. Trusses Pitched or parallel chord wood trusses, spaced a max of 24 in. OC, fabricated from nom 2 by 4 lumber, with lumber oriented vertically or horizontally. Truss members secured together with min. 0.0356 in. thick galv steel plates. Plates have 5/16 in. long teeth projecting perpendicular to the plane of the plate. The teeth are in pairs facing each other (made by the same punch), forming a split tooth type plate. Each tooth has a chisel point on its outside edge. These points are diagonally opposite each other for each pair. The top half of each tooth has a twist for stiffness. The pairs are repeated on approximately 7/8 in. centers with four rows of teeth per inch of plate width. Where the truss intersects with the interior face of the exterior walls, the min truss depth shall be 5-1/4 in. with a min roof slope of 3/12 and a min. area in the plane of the truss of 21 sq/ft. Where the truss intersects with the interior face of the exterior walls, the min truss depth may be reduced to 3 in. if the batts and blankets (Item 3) are used as shown in the above illustration (Alternate Insulation Placement) and are firmly packed against the intersection of the bottom chords and the

3. Batts and Blankets* (Optional) - Required when Item 6B is used Glass fiber insulation, secured to the wood structural panels with staples spaced 12 in. OC or to the trusses with 0.090 in. diam galv steel wires spaced 12 in. OC. Any glass fiber insulation bearing the UL Classification Marking as to Surface Burning Characteristics and/or Fire Resistance, having a min density of 0.5 pcf. As an option, the insulation may be fitted in the concealed space, draped over the resilient channel/gypsum board ceiling membrane when resilient channels and gypsum board attachment is modified as specified in Items 6 and 7. When Steel Framing Members (Item 6B) are used, max 3-1/2 in. thick insulation shall be draped over the furring channels (Item 6Ba) and gypsum board ceiling membrane, and friction-fitted between trusses and Steel Framing Members (Item 6Bd). The finished rating has only been determined when the

3A. Fiber,Sprayed* As an alternate to Item 3 (not evaluated for use with Item 6B) Any thickness of spray-applied cellulose insulation material, having a min density of 0.5 pcf, applied within the concealed space, over the resilient channel/gypsum board ceiling membrane when resilient channels and gypsum board attachment is modified as specified in Items 6 and 7. The finished rating when Fiber, Sprayed is used has not been determined. The fiber is applied with water within the concealed space, over the resilient channel/gypsum board ceiling membrane, in accordance with the application instructions supplied with the product Alternate application method: The fiber is applied with U.S. Greenfiber LLC Type AD100 hot melt adhesive at a nominal ratio of one part adhesive to 6.6 parts fiber in accordance with the application instructions supplied with the product. Alternate application method: The fiber is applied without water or adhesive in accordance with the application instructions supplied with the product.

US GREENFIBER LLC Cocoon2 Stabilized or Cocoon-FRM (Fire Rated Material).

4. Air Duct* Any UL Class 0 or Class 1 flexible air duct installed in accordance with the instructions provided by the damper

5. Ceiling Damper* Max nom area, 324 sq in. Max square size, 18 in. by 18 in. rectangular sizes not to exceed 324 sq in. with a max width of 18 in. Max damper height is 14 in. Installed in accordance with manufacturers installation instructions provided with the damper. Max damper openings not to exceed 162 sq in. per 100 sq ft of ceiling area.

POTTORFF Model CFD-521

5A. Alternate Ceiling Damper* Max nom area, 196 sq in. Max square size, 14 in. by 14 in. Rectangular sizes not to exceed 196 sq in. with a max width of 24 in. Max overall damper height is 7 in. Installed in accordance with the manufacturers installation instructions provided with the damper. Max damper openings not to exceed 98 sq in. per 100 sq ft of ceiling area.

C&S AIR PRODUCTS Model RD-521-BT

POTTORFF Model CFD-521-BT.

6. Furring Channels Resilient channels, nom. 1/2 in. deep by 2-3/8 in. wide at the base and 1-3/8 in. wide at the face, formed from 0.020 in. thick galv steel. Installed perpendicular to the trusses (Item 2), spaced a max of 16 in. OC when no insulation (Item 3 or 3A) is fitted in the concealed spaced, or a max of 12 in. OC when insulation (Item 3 or 3A) is fitted in the concealed space, draped over the resilient channel/gypsum board ceiling membrane. Two courses of resilient channel positioned 6 in. OC at wallboard butt-joints (3 in. from each end of wallboard). Channels oriented opposite at wallboard butt-joints. Channel splices overlapped 4 in. beneath wood trusses. Channels secured to each truss with 1-1/4 in. long Type S screws.

6A. Steel Framing Members (Not Shown)* As an alternate to Item 6, furring channels and Steel Framing Members as described

a. Furring Channels Formed of No. 25 MSG galv steel. 2-3/8 in. wide by 7/8 in. deep, spaced 24 in. OC perpendicular to trusses when no insulation (Items 3 or 3A) is fitted in the concealed space or 12 in. OC when insulation (Items 3 or 3A) is fitted in the concealed space, draped over the furring channel/gypsum board ceiling membrane or 24 in, OC when insulation (tlems 3 or 3A) is fitted in the concealed space, draped over the furring channel/gypsum board ceiling membrane and a second layer of gypsum board is attached as described in Item 7 for steel framing members. Channels secured to joists as described in Item b. Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 SWG galv steel wire near each end of overlap.

b. Steel Framing Members Used to attach furring channels (Item a) to trusses (Item 2). Clips spaced 48 in. OC and secured to alternating trusses with No. 8 x 2-1/2 in. coarse drywall screw through the center grommet. Furring channels are friction fitted into clips. Adjoining channels are overlapped as described in Item a. As an alternate, ends of adjoining channels may be overlapped 6 in. and secured together with two self-tapping #6 framing screws, min. 7/16 in. long at the midpoint of the overlap, with one screw on each flange of the channel. Additional clips required to hold furring channel that supports the gypsum board butt joints, as described

PAC INTERNATIONAL INC Type RSIC-1.

6B. Steel Framing Members* (Not Shown) - As an alternate to Items 6 and 6A.

a. Furring Channels Hat-shaped furring channels, 7/8 in. deep by 2-5/8 in. wide at the base and 1-1/4 in. wide at the face, formed from No. 25 ga. galv steel, spaced max. 16 in. OC perpendicular to trusses and Cold Rolled Channels (Item 6Bb). Furring channels secured to Cold Rolled Channels at every intersection with a 1/2 in. pan head self-drilling screw through each furring channel leg. Ends of adjoining channels overlapped 4 in. and tied together with two double strand No. 18 SWG galv steel wire ties, one at each end of overlap. Supplemental furring channels at base layer and outer layer gypsum board butt joints are not required. Batts and Blankets draped over furring channels as described in Item 3. Two layers of gypsum board attached to furring channels as described

b. Cold Rolled Channels 1-1/2 in. by 1/2 in., formed from No. 16 ga. galv steel, positioned vertically and parallel to trusses, friction-fitted into the channel caddy on the Steel Framing Members (Item 6Bd). Adjoining lengths of cold rolled channels lapped min. 6 in. and wire-tied together with two double strand 18 SWG galv steel wire ties, one at each end of overlap.

c. Blocking Where truss design does not permit direct, full contact of the hanger bracket, a piece of nominal 2 by 4 in. lumber (blocking), min. 6 in. long to permit full contact of the hanger bracket, to be secured vertically to the side of the truss (Item 2) at the top and bottom of the blocking at each Steel Framing Member (Item 6Bd) location.


d. Steel Framing Members* Hangers spaced 48 in. OC. max along truss, and secured to the Blocking (Item 6Bc) on alternating trusses with a single 5/16 in. by 2 in. hex head lag bolt or four #6 1-1/4 in. drywall screws through mounting hole(s) on the hanger bracket. The two 1/4 in. long steel teeth on the hanger are embedded in the side of the blocking. Hanger positioned on blocking and leveling bolt height adjusted such that furring channels are flush with bottom of trusses before gypsum board installation. Spring gauge of hanger chosen per manufacturer\'s instructions.

KINETICS NOISE CONTROL INC Type ICW.

1 HOUR RATED - UNRESTRAINED CEILING

NO SCALE

Copyright ©2007 Underwriters Laboratories Inc.®



7. Gypsum Board* One layer of nom 5/8 in. thick by 48 in. wide boards, installed with long dimension parallel to trusses. Attached to the resilient channels using 1 in. long Type S bugle-head screws. Screws spaced a max of 12 in. OC along butted end-joints and in the field when no insulation (Item 3 or 3A) is fitted in the concealed spaced, or a max of 8 in. OC along butted end-joints and in the field when insulation (Item 3 or 3A) is fitted in the concealed space, draped over the resilient channel/gypsum board ceiling

ALTERNATE INSULATION PLACEMENT

When Steel Framing Members* (Item 6A) are used, sheets installed with long dimension perpendicular to turring channels and side joints of sheet located beneath trusses. Gypsum board screws are driven through channel spaced 12 in. OC in the field when no insulation (Item 3 or 3A) is fitted in the concealed space, or 8 in. OC in the field when insulation (Item 3 or 3A) is fitted in the concealed space, draped over the furring channel/gypsum board ceiling membrane. Gypsum board butt joints shall be staggered min. 2 ft. within the assembly, and occur between the main furring channels. At the gypsum board butt joints, each end of the gypsum board shall be supported by a single length of furring channel equal to the width of the wallboard plus 6 in. on each end. The furring channels shall be spaced approximately 3-1/2 in. OC, and be attached to the trusses with one RSIC-1 clip at each end of the channel. Screw spacing along the butt joint to attach the gypsum board to the furring channels shall be 8 in. OC. Second (outer) layer of gypsum board required when furring channels (Item 6A, a) are spaced 24 in. OC and insulation is fitted in the concealed space, draped over the furring channel/gypsum board ceiling membrane. Outer layer of gypsum board attached to the furring channels using 1-5/8 in. long Type S bugle-head screws spaced 8 in. OC at butted joints and 12 in. OC in the field. Butted end joints of outer layer to be offset a minimum of 8 in. from base layer end joints. Butted side joints of outer layer to be offset minimum 18 in. from

When Steel Framing Members (Item 6B) are used, two layers of nom 5/8 in. thick, 4 ft wide gypsum board are installed with long dimensions perpendicular to furring channels (Item 6Ba). Base layer attached to the furring channels using 1 in. long Type S bugle head steel screws spaced 8 in. OC along butted end joints and 12 in. OC in the field of the board. Butted end joints centered on the continuous furring channels. Butted base layer end joints to be offset a min of 16 in. in adjacent courses. Outer layer attached to the furring channels using 1-5/8 in. long Type S bugle head steel screws spaced 8 in. OC at butted end joints and 12 in. OC in the field. Butted end joints centered on the continuous furring channels and offset a min of 16 in. from butted end joints of base layer. Butted side joints of outer layer to be offset min 16 in. from butted side joints of base layer.

CANADIAN GYPSUM COMPANY Types C, IP-X2, IPC-AR.

UNITED STATES GYPSUM CO Types C, IP-X2, IPC-AR.

USG MEXICO S A DE C V Types C, IP-X2, IPC-AR.

8. Finishing System (Not Shown) Vinyl, dry or premixed joint compound, applied in two coats to joints and screw-heads; paper tape, 2 in. wide, embedded in first layer of compound over all joints. As an alternate, nom 3/32 in. thick veneer plaster may be applied to the entire surface of gypsum board. Alternate Ceiling Membrane Not Shown.

a. Main runners Installed perpendicular to trusses Nom 10 or 12 ft long, 15/16 in. or 1-1/2 in. wide face, spaced 4 ft OC. Main runners hung a min of 2 in. from bottom chord of trusses with 12 SWG galv steel wire. Wires located a max of 48 in. OC.

b. Cross tees or channels Nom 4 ft long, 15/16 in. or 1-1/2 in. wide face or cross channels, nom 4 ft long, 1-1/2 wide face, installed perpendicular to the main runners, spaced 16 in. OC. Additional cross tees or channels used at 8 in. from each side of butted gypsum board end joints. The cross tees or channels may be riveted or screw-attached to the wall angle or channel to facilitate the ceiling

c. Wall angles or channels Used to support steel framing member ends and for screw-attachment of the gypsum wallboard Min 0.016 in. thick painted or galvanized steel angle with 1 in. legs or min. 0.016 in. thick painted or galvanized steel channel with a 1 by 1-1/2 by 1 in. profile, attached to walls at perimeter of ceiling with fasteners 16 in. OC.

CGC INC Type DGL or RX.

USG INTERIORS INC Type DGL or RX.

10. Gypsum Board* For use with Steel Framing Members (Item 9) when Batts and Blankets* (Item 6) are not used - One layer of nom 5/8 in. thick by 48 in. wide boards, installed with long dimension parallel to the main runners. Gypsum board fastened to each cross tee or channel with five wallboard screws, with one screw located at the midspan of the cross tee or channel, one screw located 12 in. from and on each side of the cross tee or channel mid span and one screw located 1-1/2 in. from each gypsum board side joint. Except at wallboard end joints, wallboard screws shall be located on alternating sides of cross tee flange. At ovosum board end joints, gypsum board screws shall be located 1/2 in. from the joint. Gypsum board fastened to main runners with wallboard screws 1/2 in. from side joints, midway between intersections with cross tees or channels (16 in. OC). End joints of adjacent gypsum board sheets shall be staggered not less than 32 in. Gypsum board sheets screw attached to leg of wall angle with wallboard screws spaced 12 in. OC. Joints treated as described in Item 7. For use with Steel Framing Members* (Item 9) when Batts and Blankets* (Item 6) are used - Ratings limited to 1 Hour - 5/8 in. thick, 4 ft wide; installed with long dimension perpendicular to cross tees with side joints centered along main runners and end joints centered along cross tees. Fastened to cross tees with 1 in. long steel gypsum board screws spaced 8 in. OC in the field and 8 in. OC along end joints. Fastened to main runners with 1 in. long gypsum board screws spaced midway between cross tees. Screws along sides and ends of boards spaced 3/8 to 1/2 in. from board edge. End joints of the sheets shall be staggered with spacing between joints on adjacent boards not less than 4 ft OC.

CANADIAN GYPSUM COMPANY Type C or IP-X2.

UNITED STATES GYPSUM CO Type C or IP-X2.

USG MEXICO S A DE C V Type C or IP-X2.

JOB SITE PLANS This set of plans must be kept on the job site of work at all times per Sarasota County Ordinance Sarasota County Planning & Development Services

ng

00

/illage Im Buildi

www.bsbdesign.com 100 Main St. Suite 209 Safety Harbor, Florida 34695

*Bearing the UL Classification Mark

MALL SECTIONS & ASSEMBLIES P Rated\1 Hour\P522.dwg September 11, 2007

813 265 4808 JOB NO: 02T12034 PROJ MGR: JD

DRAWN: JD, AM CHECKED:

1. THE ELECTRICAL CONTRACTOR REFERRED TO HEREAFTER, AS THE "CONTRACTOR" SHALL PROVIDE COMPLETE ELECTRICAL SYSTEMS AS INDICATED ON THE DRAWINGS AND SPECIFIED HEREIN.

2. CONTRACTOR SHALL PROVIDE PROTECTIVE DEVICES, CONDUCTORS SUPPORTS, RACEWAYS, AND MISCELLANEOUS MATERIALS TO SERVE ALL DEVICES REQUIRING ELECTRICAL POWER.

3. CONTRACTOR SHALL OBTAIN AND PAY FOR ALL PERMITS, FEES. AND

4. CONTRACTOR SHALL CONDUCT A THOROUGH SITE INSPECTION TO FAMILIARIZE HIMSELF WITH EXISTING CONDITIONS AND ALL ASPECTS OF HIS SCOPE OF WORK. SUCH AN INSPECTION SHALL BE CONDUCTED PRIOR TO

INSPECTIONS REQUIRED TO COMMENCE AND COMPLETE ELECTRICAL WORK.

5. CONTRACTOR SHALL REFER TO INTERIOR ARCHITECTURAL CASE WORK ELEVATIONS FOR EXACT MOUNTING HEIGHTS AND/OR LOCATIONS OF SWITCHES, OUTLETS, AND WIRING DEVICES.

6. CONTRACTOR SHALL MAINTAIN A COMPLETE TEMPORARY POWER AND LIGHTING SYSTEM DURING CONSTRUCTION.

7. THE CONTRACTOR SHALL PROVIDE, DROP CLOTH, RUBBER MATS AND, PLYWOOD COVERS FOR OWNERS EQUIPMENT SUSCEPTIBLE TO DAMAGE DURING CONSTRUCTION. VERIFY SPECIFIC LOCATIONS WITH OWNER'S REPRESENTATIVE.

8. AT PROJECT COMPLETION, THE CONTRACTOR SHALL INSURE THAT ALL ELECTRICAL SYSTEMS OPERATE PROPERLY. CONTRACTOR SHALL DEMONSTRATE OPERATION OF EACH SYSTEM WITH THE OWNER'S

9. CONTRACTOR SHALL COORDINATE AND VERIFY WITH LOCAL POWER COMPANY THE FOLLOWING:

- EXACT LOCATION OF SERVICE CONNECTION.
- ELECTRICAL CHARACTERISTICS (VOLTAGE AND PHASING)
- AVAILABLE FAULT CURRENT METERING REQUIREMENTS

CODES AND STANDARDS

- 1. ELECTRICAL WORK SHALL COMPLY WITH THE LATEST EDITION OF:
- NFPA 70 (NATIONAL ELECTRICAL CODE)
- NFPA 101 (LIFE SAFETY CODE) CODES SPECIFIC TO OTHER SÉCTIONS HEREIN

2. ELECTRICAL WORK SHALL COMPLY WITH ALL LOCAL AND STATE ELECTRICAL CODES AND IN ACCORDANCE WITH REQUIREMENTS OF THE AUTHORITY HAVING JURISDICTION (AHJ).

 WORKMANSHIP SHALL BE HIGH QUALITY AND FOLLOW INDUSTRY STANDARDS. SUBSTANDARD WORK WILL BE REJECTED. THE CONTRACTOR IS RESPONSIBLE FOR REPAIR AND REWORK TO RECTIFY SUBSTANDARD WORK. QUALITY OF WORK SHALL BE DETERMINED BY THE OWNER'S REPRESENTATIVE AND/OR ENGINEER OF RECORD.

1. PLANS ARE GENERALLY DIAGRAMMATIC. THE CONTRACTOR SHALL COORDINATE WITH THE OTHER TRADES SO THAT INTERFERENCES BETWEEN CONDUITS, PIPING, EQUIPMENT, DUCTS, AND STRUCTURAL WORK WILL BE AVOIDED. IN SUCH CASE, IF THE CONTRACTOR FAILS TO COORDINATE WITH OTHER TRADES AND INTERFERENCES ARE ALLOWED TO DEVELOP, THE OWNER'S AUTHORIZED REPRESENTATIVE WILL DECIDE WHICH EQUIPMENT, DUCT CONDUIT, ETC., MUST BE RELOCATED. REGARDLESS OF WHICH WAS INSTALLED FIRST. ELECTRICAL REWORK REQUIRED TO CORRECT INTERFERENCES WILL BE AT THE CONTRACTORS EXPENSE.

MATERIALS

1. ALL ELECTRICAL EQUIPMENT AND MATERIALS SHALL BE APPROVED BY UNDERWRITERS LABORATORY FOR THE APPLICATION AND SHALL BEAR A UL

2. ELECTRICAL ENCLOSURES SHALL BE NEMA RATED. UNLESS OTHERWISE NOTED, ENCLOSURE RATINGS SHALL ADHERE TO THE FOLLOWING:

- NEMA 1 NEMA 3R
- OUTDOOR CORROSIVE ENVIRONMENT - NEMA 4

GUARANTEE

1. CONTRACTOR SHALL GUARANTEE ALL WORK FOR A PERIOD OF ONE YEAR FROM DATE OF OWNER'S ACCEPTANCE. THE CONTRACTOR SHALL RECTIFY ANY DEFECTS DUE TO FAULTY MATERIALS OR WORKMANSHIP AND PAY FOR DAMAGE CAUSED BY FAILURE AND REWORK. THE OWNER WILL GIVE NOTICE OF DEFECTS WITH REASONABLE PROMPTNESS AFTER DISCOVERY. THE CONTRACTOR SHALL START REWORK WITHIN TEN (10) WORKING DAYS OF NOTIFICATION AND COMPLETE REPAIRS IN A TIMELY MANNER.

FIXTURE SCHEDULE SYMBOL DESCRIPTION / MODEL NUMBER VOLTAGE LAMP(S) MOUNTING NOTES OWNER SELECTED - INTERIOR CEILING MOUNTED SURFACE FIXTURE 120 **MAX 100W** SURFACE FURNISHED AND INSTALLED BY CONTRACTOR OWNER SELECTED - GARAGE CEILING MOUNTED SURFACE FIXTURE 120 **MAX 150W** SURFACE FURNISHED AND INSTALLED BY CONTRACTOR OWNER SELECTED - CLOSET WALL MOUNTED SURFACE FIXTURE 120 **MAX 100W** SURFACE FURNISHED AND INSTALLED BY CONTRACTOR OWNER SELECTED - RESTROOM VANITY SCONCE 120 **MAX 250W** SURFACE FURNISHED AND INSTALLED BY CONTRACTOR OWNER SELECTED PENDANT FIXTURE **HANGING** 120 **MAX 150W PENDANT** FURNISHED AND INSTALLED BY CONTRACTOR FAN RATED J-BOX FOR FUTURE FAN WITH BLANK COVER PLATE **MAX 400W** 120 SURFACE **INCL MOTOR** FURNISHED AND INSTALLED BY CONTRACTOR OWNER SELECTED EXTERIOR SCONCE WITH PHOTOCELL - WET LISTED 120 MAX 150W SURFACE FURNISHED AND INSTALLED BY CONTRACTOR OWNER SELECTED EXTERIOR SCONCE - WET LISTED 120 **MAX 150W** SURFACE FURNISHED AND INSTALLED BY CONTRACTOR OWNER SELECTED PENDANT FIXTURE HANGING 120 MAX 75W PENDANT FURNISHED AND INSTALLED BY CONTRACTOR OWNER SELECTED - RECESSED CAN 120 MAX 75W RECESSED FURNISHED AND INSTALLED BY CONTRACTOR OWNER SELECTED - RECESSED CAN WITH SHOWER LENS MAX 75W RECESSED FURNISHED AND INSTALLED BY CONTRACTOR I. ALL FIXTURES SHALL BE SELECTED BY OWNER AND/OR INTERIOR DECORATOR. ADDITIONAL FIXTURES AND/OR VARIATIONS OF THE FIXTURES LISTED HEREIN MAY OCCUR. THE CONTRACTOR SHALL BE RESPONSIBLE TO VERIFY THE REQUIREMENTS OF ALL FIXTURES PRIOR TO ROUGH-IN.

SUBMITTAL DATA AND RECORD DRAWINGS

1. THE ELECTRICAL DESIGN IS BASED ON A SINGLE MANUFACTURE. WHEREAS SUBSTITUTIONS ARE PROVIDED IN LIEU OF THAT WHICH IS SPECIFIED, THE CONTRACTOR ASSUMES FULL RESPONSIBILITY FOR ANY IMPACT TO THE INSTALLATION. CONTRACTOR SHALL VERIFY THAT SUBSTITUTIONS CAN FUNCTION SATISFACTORILY IN THEIR DESIGNATED SPACE AND CHANGES IN OPERATING CHARACTERISTICS DO NOT DEGRADE THE INSTALLATION.

2. SUBMIT MANUFACTURER'S DATA (MINIMUM 5 COPIES) FOR ELECTRICAL GEAR, LIGHT FIXTURES, WIRING DEVICES AND OTHER EQUIPMENT SPECIFIED HEREIN. SUBMIT SHOP DRAWINGS IN BOOKLET FORM WITH SEPARATE SHEET FOR EACH DEVICE. PROVIDE EQUIPMENT IDENTIFICATION AS DESIGNATED ON PLANS FOR EACH SHOP DRAWING CUT SHEET SUBMITTED.

3. AT PROJECT COMPLETION THE CONTRACTOR SHALL COMPILE TWO (2) COMPLETE SETS OF RECORD DRAWINGS INDICATING ALL DEVIATIONS FROM CONSTRUCTION DOCUMENTS. ONE SET SHALL BE ISSUED TO THE ARCHITECT AND ONE SET SHALL BE ISSUED TO OWNER'S REPRESENTATIVE.

IDENTIFICATION OF EQUIPMENT

1. LABEL ALL ELECTRICAL EQUIPMENT WITH ENGRAVED LAMINATED PLASTIC NAMEPLATE THAT CLEARLY DESCRIBES THE EQUIPMENT NAME, VOLTAGE, AMPERAGE RATING, AND FUNCTION. NAMEPLATES SHALL BE RED BACKGROUND WITH WHITE STENCILED UPPER CASE LETTERING A MINIMUM OF

2. INSTALL VINYL CLOTH SELF-ADHESIVE CIRCUIT LABELS ON ALL WIRE AND CABLE IN JUNCTION BOXES, WIRE TROUGHS, AND PANELBOARD WIRING

3. IDENTIFY JUNCTION BOXES WITH PERMANENT MARKER INDICATING PANELBOARD AND CIRCUIT NUMBERS OF WIRING CONTAINED WITHIN.

4. PROVIDE TYPEWRITTEN PANELBOARD DIRECTORIES WITH ACCURATE AS BUILT INFORMATION. DIRECTORIES SHALL REFLECT TYPE OF LOAD AND AREA SERVED FOR EACH BREAKER.

RACEWAYS AND FITTINGS

1. WHERE USED, CONDUIT SHALL BE PROPERLY ALIGNED, GROUPED AND SUPPORTED. EXPOSED CONDUIT SHALL BE INSTALLED AT RIGHT ANGLES TO OR PARALLEL TO THE PRINCIPAL STRUCTURAL MEMBERS. CONDUIT SHALL BE SUPPORTED AT INTERVALS NOT EXCEEDING 8 FEET. CONDUIT SHALL BE SUPPORTED FROM STRUCTURE AND NOT FROM CEILING SUPPORT SYSTEM.

2. PROVIDE NYLON PULL CORD IN ALL EMPTY CONDUITS.

3. FLEXIBLE METALLIC CONDUIT; IN DAMP OR WET LOCATIONS SHALL BE UL GALVANIZED STEEL WITH MOISTURE PROOF PVC JACKET. IN DRY LOCATIONS SHALL BE UL ZINC COATED STEEL. FITTINGS SHALL HAVE INSULATED THROATS. FITTINGS SHALL BE LIQUID TIGHT FOR DAMP OR WET

4. GALVANIZED RIGID STEEL (GRS) CONDUIT SHALL BE UL APPROVED HOT DIPPED GALVANIZED. GRS CONDUIT COUPLINGS SHALL BE THREADED HEAVY WALL GALVANIZED STEEL. USE GRS CONDUIT FOR FEEDER EXPOSED RISERS BETWEEN ELECTRICAL PANEL BOARDS, JUNCTION BOXES, OR METERS. USE 90 DEGREE GRS SWEEPS IN UNDERGROUND PVC CONDUIT RUNS LARGER THAT 2" IN DIAMETER. PAINT ALL GALVANIZED RIGID CONDUITS INSTALLED BELOW GRADE WITH RUST INHIBITING PAINT.

1. BOXES SHALL BE RIGIDLY MOUNTED AND COVERED WITH MATCHING PLATE. OPEN KNOCK-OUTS OR HOLES IN BOXES SHALL BE PLUGGED WITH A SUITABLE BLANKING DEVICE.

2. SURFACE MOUNT EXTERIOR OUTLET BOXES SHALL BE CAST ALUMINUM WITH WEATHERPROOF ALUMINUM GASKETED COVER.

3. FLUSH MOUNT EXTERIOR OUTLET BOXES SHALL 4" SQUARE STEEL WITH MASONRY RING AND WEATHERPROOF GASKETED CAST ALUMINUM COVER.

1. UNLESS OTHERWISE INDICATED, BRANCH CIRCUIT CONDUCTORS SHALL BE SOLID NO. 14 AWG COPPER ON 15 AMP CIRCUITS AND SOLID NO. 12 AWG ON 20 AMP CIRCUITS. BRANCH CIRCUITS RUN OVER 75 FEET IN LENGTH, MEASURING ONE WAY FROM THE FIRST OUTLET OF THE CIRCUIT TO THE PANEL, SHALL BE INCREASED ONE TRADE SIZE AWG COPPER FOR THE

2. SPLICES AND TAPS SHALL UTILIZE SOLDERLESS LUGS FOR #8 AWG AND LARGER. SPLICES AND TAPS SHALL FORM A ELECTRICAL AND MECHANICALLY SECURE CONNECTION. LUGS SHALL BE CORRECTLY SIZED FOR THE CONDUCTORS. TAPE JOINTS WITH VINYL PLASTIC ELECTRICAL TAPE.

3. ALLOW SUFFICIENT CABLE SLACK IN BOXES, OUTLETS AND CABINETS TO MAKE CONNECTION AND INSURE THERE IS NO BINDING AT THE SPLICE/TAP.

4. CONDUCTORS SHALL BE COPPER. UNLESS OTHERWISE NOTED, INSULATION SHALL BE NM (ROMEX) WITH IN EACH RESIDENCE AND DUAL TYPE THHN/THWN 75°C ELSEWHERE, SERVICE CONDUCTORS SHALL BE THHN/THWN 75°C IN CONDUIT FROM UTILITY TRANSFORMER TO UNIT PANELS. CONDUCTORS SHALL BE COLOR CODED IN ACCORDANCE WITH NFC 70. COLOR CODING SHALL BE BY MEANS OF COLORED INSULATING MATERIAL, COLORED BRAID OR JACKET OVER THE INSULATION OR BY MEANS OF SUITABLE COLORED, PERMANENT, NON-AGING, INSULATING TAPE APPLIED TO CONDUCTORS AT EACH CABINET OR JUNCTION POINT. THE FOLLOWING SYSTEM OF COLOR CODING SHALL BE ADHERED TO:

- GROUND LEADS: GREEN
- 120/240 NEUTRAL CONDUCTOR: WHITE - 120/240 VOLT, PHASE CONDUCTORS: BLACK, RED

1. ALL INTERIOR ELECTRICAL SYSTEMS SHALL BE COMPLETELY AND EFFECTIVELY GROUNDED AS REQUIRED BY NFPA 70 AND AS SPECIFIED

2. METALLIC RACEWAYS SHALL BE MECHANICALLY AND ELECTRICALLY SECURE AT ALL JOINTS AND AT ALL BOXES, CABINETS, FITTINGS, AND EQUIPMENT. METALLIC RACEWAYS SHALL BE CONNECTED TO A DIRECT GROUND AT POINT OF ELECTRICAL SERVICE ENTRANCE AND SHALL BE ELECTRICALLY CONTINUOUS THROUGHOUT THE ENTIRE SYSTEM.

3. ALL GROUND CONDUCTORS SHALL BE INSULATED COPPER UNLESS OTHERWISE NOTED.

4. RACEWAYS WITH NO. 10 OR 12 AWG PHASE CONDUCTORS FOR RECEPTACLES, LIGHT FIXTURES AND SIMILAR CIRCUITS (NEW BRANCH CIRCUITS) SHALL BE PROVIDED WITH A PARITY SIZED GREEN EQUIPMENT GROUND CONDUCTOR. GROUND CONDUCTOR SHALL BE INSTALLED IN ENTIRE RACEWAY SYSTEM INCLUDING WALL SWITCHES AND FLEXIBLE CONDUIT TO LIGHT FIXTURES. EQUIPMENT GROUND CONDUCTOR SIZES FOR CIRCUITS WITH PHASE CONDUCTORS LARGER THAN NO. 12 AWG ARE INDICATED ON DRAWINGS.

PANEL BOARDS AND SAFETY SWITCHES

1. ELECTRICAL PANELS AND DISCONNECTS SHALL BE PLUMB AND SECURELY SUPPORTED. IF SUITABLE SUPPORT DOES NOT EXIST, PROVIDE SUPPORTING STRUCTURE WITH PROPERLY SIZED "U" CHANNEL.

2. CIRCUIT BREAKERS SHALL BE MOLDED PLASTIC CASE WITH QUICK-MAKE. QUICK-BREAK CONTACTS. BREAKERS SHALL HAVE THERMAL MAGNETIC TRIP UNITS. MULTI-POLE BREAKERS SHALL HAVE A FACTORY INSTALLED COMMON TRIP. TIE BARS INSTALLED IN THE FIELD ARE NOT ACCEPTABLE.

3. SAFETY SWITCH MECHANISMS SHALL BE GENERAL DUTY QUICK-MAKE, QUICK-BREAK. COVER SHALL BE INTERLOCKED WITH MECHANISM TO PREVENT OPENING WITH HANDLE IN THE "ON" POSITION. ALL ENCLOSURES SHALL BE PRIMED AND FINISHED TO RESIST RUSTING AND CORROSION. SWITCHES SHALL BE GENERAL ELECTRIC, OR SQUARE-D (MATCH BUILDING STANDARD WHERE

4. FUSES SHALL BE DUAL ELEMENT, CARTRIDGE TYPE. FUSES SHALL BE BUSMAN "FUSETRON" OR CHASE SHAWMUT "TRIONIC". THE CONTRACTOR SHALL PROVIDE SIZES BASED ON EQUIPMENT NAMEPLATE DATA. CONTRACTOR SHALL FURNISH AS SPARE, A DUPLICATE CARTRIDGE FOR EACH

5. PANELBOARDS SHALL BE DEADFRONT TYPE, COPPER BUS BARS, AND BOLT-ON TYPE BRANCH CIRCUIT BREAKERS.

1. CONTRACTOR SHALL PROVIDE ALL MOUNTING HARDWARE AND LIGHTING OPTIONS TO PROVIDE A PROPER LIGHTING INSTALLATION.

2. BALLASTS FOR FLUORESCENT LAMPS SHALL BE HIGH POWER FACTOR TYPE AND SHALL BEAR THE CBM, AND UL LABELS, ALL BALLASTS SHALL BE UNDERWRITERS CLASS P. BALLASTS SHALL BE MAGNETEK TRIAD 'HP' OCTIC OR EQUAL BY MOTOROLA.

3. FIXTURES SHALL BE PROPERLY SUPPORTED AND ALIGNED. LIGHTING FIXTURES SHALL BE CLEANED AND LAMPED IMMEDIATELY PRIOR TO FINAL

4. USE STEEL 4" SQUARE BACK BOXES FOR SURFACE MOUNT FIXTURES. RECEPTACLES AND SWITCHES

1. ALL RECEPTACLE, SWITCH AND WALL PLATE COLOR AND STYLE SHALL BE SELECTED BY OWNER.

2. PROVIDE WALLPLATES FOR SINGLE AND COMBINATION WIRING DEVICES. OF TYPES, SIZES, AND GANGING TO MATCH INSTALLATION. SELECT PLATES WHICH MATE AND MATCH WIRING DEVICES. SECURE WALL PLATES WITH METAL SCREWS. SCREW HEADS SHALL BE COLORED TO MATCH FINISH OF PLATE.

3. GENERAL PURPOSE RECEPTACLES SHALL BE 125V, 20A, NEMA 5-20R,

4. GROUND FAULT CIRCUIT INTERRUPTER (GFI) RECEPTACLES SHALL BE 125V, 20A, NEMA 5-20R, WHITE TEST AND RESET BUTTONS ON FRONT FACE.


5. RECEPTACLES DEDICATED TO A SINGLE PIECE OF EQUIPMENT SHALL MATCH SAID EQUIPMENT REQUIREMENTS. CONTRACTOR SHALL MAKE RECEPTACLE SELECTION BASED EQUIPMENT VOLTAGE, AMPERAGE, AND PLUG CONFIGURATION. INCLUDE THIS INFORMATION IN SHOP DRAWING SUBMITTALS. ADVISE ENGINEER OF DISCREPANCIES.

6. SWITCHES SHALL BE WHITE, AC QUIET, SNAP TYPE, RATED 120/277V, 20A. SWITCH TYPE SHALL BE AS INDICATED ON DRAWINGS.

7. APPROVED MANUFACTURERS: HUBBLE, LEVITON, OR GENERAL ELECTRIC. COMMUNICATIONS:

1. FURNISH SINGLE GANG BOX CONNECTOR AND CABLING FOR EACH TELEPHONE/CABLE TV DEVICE LOCATION. EXTEND CABLE CONCEALED IN WALLS AND CEILING SPACE TO SERVING UTILITIES POINT OF CONNECTION COORDINATE REQUIREMENTS WITH SERVING UTILITY. CABLING AND DEVICES TO BE INSTALLED BY TELEPHONE/CABLE TV CONTRACTOR.





လဗ္ဗ eline rs, Fl e e

 $\mathbf{Q}\mathbf{Q}$ et Vill Stre

Dg

JOB SITE PLANS

This set of plans must be kept

on the job site of work at all times

per Sarasota County Ordinance

Sarasota County Planning &

Development Services

0

DESIGN www.bsbdesign.com 11512 Lake Mead Ave., #301 Jacksonville, Florida 32256 904 732 7335

JOB NO: 02T12034 PROJ MGR: JE CHECKED: SPECIFICATIONS LEGEND

	CULATION - U 008 EDITION							
TOTAL LIVIN		1,269 S						
GENERAL LIGHTING 3 VA	X	1,269 S	Q. FEET	- 144 () - = (3,807 V	Ą		
SMALL APPLIANCE 2 CKT		1,500 V		= '	3,000 V			
LAUNDRY 1 CKT	X	1,500 V		=	1,500 V			
TOTAL CONNECTED GENERAL LOA					=	8,307	VA	•
WATER HEATER				=	6,000 V	A		
REFRIGERATOR				=	800 V	A		
GARBAGE DISPOSER			• .	· = ·	1,200 V	A		
DISHWASHER				• =	900 V	Α		
RANGE				= " .	8,000 V	Ą		· · · .
DRYER				=	5,000 V	A į		
MICROWAVE				= .	1,200 V		<u>.</u>	
TOTAL CONNECTED SENERAL CON		D ADDI IANG				23,100		
TOTAL CONNECTED GENERAL LOA	ND AND FIXE	DAPPLIANC	SE LOAD		· · · · = ·	31,407	VA	
SUB-TOTAL GENERAL LOAD - 1st 10	_						10,000	VA
SUB-TOTAL GENERAL LOAD - Rema	inder @ 40%	•				: =	8,563	VA
TOTAL GENERAL LOAD	: F						18,563	VA
A/C and CENTRAL HEAT LOAD - (100								
AHU-3 2-1/2 TON V		JX HEAT	X 65%	=	9,126 V	Α	- 1	
CU-3 (heat pump) 2-1/2 TONS			X 100%	=	5,064 V	4		
TOTAL HEAT LOAD (heat pump and a	ux heat do no	t run concurre	ent)				9,126	VA
			TOTAL D	EMAN	D LOAD	= · · ·	27,689	VA
	ΔΙ	MPS AT 240						AMPS


LOAD CALCULATION - UNIT TYPE "D"			
PER NEC 2008 EDITION ARTICLE 220.82			
TOTAL LIVING 1,655 SQ. FEE	T		
GENERAL LIGHTING 3 VA X 1,655 SQ. FEE	T =	4,965 VA	
SMALL APPLIANCE 2 CKT X 1,500 VA	=	3,000 VA	
LAUNDRY 1 CKT X 1,500 VA	= .	1,500 VA	
TOTAL CONNECTED GENERAL LOAD			5 VA
WATER HEATER	=	6,000 VA	
REFRIGERATOR	=	800 VA	
GARBAGE DISPOSER	· · · _ · ·	1,200 VA	
DISHWASHER	. =	900 VA	
RANGE	=	8,000 VA	
DRYER	=	5,000 VA	
MICROWAVE	=	1,200 VA	
TOTAL CONNECTED FIXED APPLIANCE LOAD	` , 	= 23,10	
TOTAL CONNECTED GENERAL LOAD AND FIXED APPLIANCE LOAD	\D	= 32,56	5 VA
SUB-TOTAL GENERAL LOAD - 1st 10kVA @ 100%			10,000 VA
SUB-TOTAL GENERAL LOAD - Remainder @ 40%			9,026 VA
TOTAL GENERAL LOAD			19,026 VA
A/C and CENTRAL HEAT LOAD - (100% of the larger load)			
· · · · · · · · · · · · · · · · · · ·	% =	9,126 VA	
CU-4 (heat pump) 3 TONS X 100		5,280 VA	
A 100	/0 –	0,200 VA	
TOTAL HEAT LOAD (heat pump and aux heat do not run concurrent)			9,126 VA
TOTAL	DEMAN	ID I OAD =	00.450.1/4
IOIAL	. UEMAN	ID LOAD =	28,152 VA

	PER NEC 2008 I	EDITION ARTICLI	E 220.82				
	TOTAL LIVING	1,574	4 SQ. FEET				
GENERAL LIGHTING	3 VA	X 1,574	4 SQ. FEET	=	4,722 VA		
SMALL APPLIANCE	2 CKT	X 1,500	O VA	= 1	3,000 VA	***	
LAUNDRY	1 CKT		AV C	=	1,500 VA		
TOTAL CONNECTED G	ENERAL LOAD				=	9,222 V	/A
WATER HEATER				=	6,000 VA		
REFRIGERATOR				= .	AV 008		
GARBAGE DISPOSER				= .	1,200 VA		
DISHWASHER				= '	900 VA	*	
RANGE				=	8,000 VA		
DRYER				= 1	5,000 VA	1 P. 1	
MICROWAVE				=	1,200 VA	·	
TOTAL CONNECTED F	IXED APPLIANCE	LOAD			= 2	3,100 V	/ A
			****		•	2,322 V	/ A
TOTAL CONNECTED G	ENERAL LOAD AI	ND FIXED APPLI	ANCE LOAD		= 3	2,322 V	/A
			ANCE LOAD		= 3		7A 10,000 VA
SUB-TOTAL GENERAL SUB-TOTAL GENERAL	LOAD - 1st 10kVA LOAD - Remainde	@ 100%	ANCE LOAD				
SUB-TOTAL GENERAL	LOAD - 1st 10kVA LOAD - Remainde	@ 100%	ANCE LOAD			= = _	10,000 VA
SUB-TOTAL GENERAL SUB-TOTAL GENERAL TOTAL GENERAL LOAI	LOAD - 1st 10kVA LOAD - Remainde D	. @ 100% r @ 40%	ANCE LOAD			= = _	10,000 VA 8,929 VA
TOTAL CONNECTED G SUB-TOTAL GENERAL SUB-TOTAL GENERAL TOTAL GENERAL LOAD A/C and CENTRAL HEA AHU-1	LOAD - 1st 10kVA LOAD - Remainde D	@ 100% r @ 40% f the larger load)				= = _	10,000 VA 8,929 VA
SUB-TOTAL GENERAL SUB-TOTAL GENERAL TOTAL GENERAL LOAI A/C and CENTRAL HEA AHU-1	LOAD - 1st 10kVA LOAD - Remainder D AT LOAD - (100% o 2-1/2 TON W/ 10	@ 100% r @ 40% f the larger load)			9,126 VA	= = _	10,000 VA 8,929 VA
SUB-TOTAL GENERAL SUB-TOTAL GENERAL TOTAL GENERAL LOAI A/C and CENTRAL HEA	LOAD - 1st 10kVA LOAD - Remainder D AT LOAD - (100% of 2-1/2 TON W/ 10, 2-1/2 TONS	@ 100% r @ 40% f the larger load) .0KW AUX HEAT	X 65% X 100%		9,126 VA	= = _	10,000 VA 8,929 VA

	RISER DIAGRAM - WIRE TAG LEGEND
A	2 SETS: (2) 500 MCM AL, 500 MCM AL N, 3" C.
 В	(2) #3/0 AL, #3/0 AL N, #4 AL EGC, 2" C.
С	(2) #6 AL, #6 AL N, #8 AL EGC, 1" C.
٥	#1/0 CU GRD AND 5/8" DRIVEN RODS PER NEC AND LOCAL CODE. BOND TO BUILDING STEEL AND/OR COLD WATER WHERE APPLICABLE.

○ KEYED DRAWING NOTES ○

- 1. UTILITY OWNED TRANSFORMER. EXACT LOCATION, SIZE AND CHARACTERISTICS DETERMINED BY FLORIDA POWER AND LIGHT. CONTRACTOR SHALL VERIFY EXACT LOCATION PRIOR TO ROUGH—IN.
- 2. 120/240V, 10 METER CENTER WITH 800 AMP MLO BUS CAPACITY AND (6) TENANT METERS WITH BREAKERS AS INDICATED. METER CENTER SHALL CONFORM TO ALL UTILITY COMPANY REQUIREMENTS. DESIGN BASIS IS SQUARE D "MP" SERIES MP METER-PAK. SEE PLAN VIEW FOR LOCATION.



FEEDER AND SERVICE CALCULATION

PER NEC 2008 EDITION ARTICLE 220.84

4,722

9,126

9,126

9,126

9,126

DEMAND FACTOR PER TABLE 220-84 0.44

SUBTOTAL CONNECTED LOAD 288,645

SUBTOTAL DEMAND LOAD 127,004

TOTAL DEMAND LOAD 128,429 VA SERVICE VOLTAGE 240 V

SERVICE AMPS REQUIRED 600 AMPS

UNIT B PANEL "B" 150A MLO 120/240V.1¢ NEMA-1

DEMAND AMPS 535 AMPS

UNIT "A"

HVAC LOAD

HVAC LOAD

HVAC LOAD

HVAC LOAD

HOUSE PANEL

UNIT "D"

GENERAL LIGHTING

GENERAL LIGHTING

GENERAL LIGHTING

GENERAL LIGHTING

SMALL APPLIANCE & LAUNDRY 4,500

FIXED APPLIANCES AT 100% 23,100

SMALL APPLIANCE & LAUNDRY 4,500

FIXED APPLIANCES AT 100% 23,100

SMALL APPLIANCE & LAUNDRY 4,500

FIXED APPLIANCES AT 100% 23,100

SMALL APPLIANCE & LAUNDRY 4,500

FIXED APPLIANCES AT 100% 23,100

LOAD NUMBER

(VA) OF UNITS

TOTAL

LOAD

(VA)

2 9,444

2 9,000

2 46,200

2 18,252

2 9,540

2 9,000

2 46,200

2 18,252

2 7,614

2 9,000

2 46,200

2 18,252

1 4,965

1 4,500

1 23,100

1 9,126

1,425


UNIT C PANEL "C" 150A MLO 120/240V.16 NEMA-1

1 PHASE

UNIT D PANEL "D" 150A MLO 120/240V.1ø NEMA-1

UNIT B PANEL "B" 150A MLO 120/240V.1¢ NEMA-1


UNIT C PANEL "C" 150A MLO 120/240V.16 NEMA-1



JOB SITE PLANS

This set of plans must be kept on the job site of work at all times per Sarasota County Ordinance Sarasota County Planning S

Sarasota County Planning & Development Services



America's Bu 13880 Treeline Ave, S Fort Myers, Florida 3

Bay Street Village
7 Unit Condominium Building

160 East Bay Street Osprey, Florida 3422

Jacksonville, Florida 32256 904 732 7335

JOB NO: 02T12034 PROJ MGR: JD RISER DIAGRAM

LOAD CALCULATIONS

E1.1

30 07


JOB NO: 02T12034 PROJ MGR: JI

ELECTRICAL

Permit

E2.1

ENGINEERING INC.





PA	NEL "	HP"	120/240V. 1PH, 3W	60A MI	LO	N	EMA-	3R	22,000 AIC		
SQU	IARE D	: QO	VOLTAGE/PHASE	60A BU	IS	S	URFAC	Έ	SERIES RATED	ОРТК	ONS:
CKT	AMPS	POLE	DESCRIPTION	NOTES	LOAD VA	СКТ	AMPS	POLE	DESCRIPTION	NOTES	LOAD VA
1	20	1	SPARE		0	2	20	1	LIGHTING	1	900
3	20	1	SPARE		0	4	20	1	SPRINKLER CONTROL	1	300
5	20	1	SPARE		0	6	20	1	SPARE		0
7	20	1	SPARE		0	8	20	1	SPARE		0
9	20	1	SPARE		0	10	20	1	SPARE		0
11	20	1	SPARE		0	12	20	1	SPARE		0
OTES:					LOAD DESCRIP	ΠΟΝ		IECTED	DEMAND FACTOR	DEMAND LOAD (VA)	
	(2) #10 (CU, #10 C	CU GRD - 1/2"C		LIGHTING			900	1.25	1125	
2.					HVAC - CO			0	0.00	0	
3.		-			HVAC - HE			0	0.00	0	
4.					RECEPTA	CLE		0	0.00	0	
5.	- 1				MISC			300	1.00	300	
6.	· · · · · · · · · · · · · · · · · · ·					TOTAL		1200		1425	
7.					TOTAL DE	MAND C	URREN	T @ 120/	240V, 1PH		5.9 AMPS

JOB SITE PLANS This set of plans must be kept on the job site of work at all times per Sarasota County Ordinance Sarasota County Planning & Development Services

KEYED DRAWING NOTES


- 1. FIXTURE PROVIDED SHALL BE EQUIPPED WITH A PHOTOCELL. PROVIDE UNSWITCHED CIRCUIT AS REQUIRED.
- 2. SEE EQUIPMENT SCHEDULE THIS SHEET FOR DISCONNECT SIZES, FUSING (WHERE REQUIRED) AND CONDUCTOR SIZES. CONDENSING UNIT DISCONNECT SWITCHES SHALL BE PROVIDED WITH BUILT—IN GFI/WP RECEPTACLES







2nd Floor Electrical Plan

Unit A Electrical Plan



Unit B Electrical Plan





Suite 3 33913 13880 Treeline Ave, S Fort Myers, Florida 3

KEYED DRAWING NOTES

1. PROVIDE COMBINATION CARBON MONOXIDE AND SMOKE DETECTORS PER ALL APPLICABLE CODES. DETECTORS SHALL BE 120V. WITH BATTERY BACK-UP AND INTERCONNECTED SO THAT THE INITIATION OF ANY GIVEN DETECTOR SHALL SOUND ALL DETECTORS.

2. SEE EQUIPMENT SCHEDULE THIS SHEET FOR DISCONNECT SIZES, FUSING (WHERE REQUIRED) AND CONDUCTOR SIZES. CONDENSING UNIT DISCONNECT SWITCHES SHALL BE PROVIDED WITH BUILT—IN GFI/WP RECEPTACLES.

3. PROVIDE FAN RATED J-BOX TO SUPPORT THE WEIGHT OF THE FIXTURE/FAN SELECTED AT ALL FAN AND FUTURE FAN LOCATIONS. ALL FANS SHALL BE PRE-WIRED FOR SEPARATE LIGHTING CONTROL REGARDLESS IF LIGHT KIT IS BEING PROVIDED. WHERE SWITCHING IS NOT REQUIRED AT THIS TIME PROVIDE BLANK COVER PLATE AND TAG CONDUCTORS FOR FUTURE IDENTIFICATION.

4. PROVIDE DEDICATED 120V CIRCUIT AND 20A RECEPTACLE FOR UNDER COUNTER DISHWASHER. COORDINATE EXACT LOCATION AND RECEPTACLE CONFIGURATION WITH MANUFACTURER SPECIFICATIONS PRIOR TO ROUGH—IN AND PROVIDE AS REQUIRED.

5. PROVIDE DEDICATED 120V CIRCUIT AND 20A RECEPTACLE FOR REFRIGERATOR/FREEZER. COORDINATE EXACT LOCATION AND RECEPTACLE CONFIGURATION WITH MANUFACTURER SPECIFICATIONS PRIOR TO ROUGH—IN AND PROVIDE AS REQUIRED.

6. PROVIDE DEDICATED 120V CIRCUIT AND 20A RECEPTACLE FOR GARBAGE DISPOSAL. COORDINATE EXACT LOCATION AND RECEPTACLE CONFIGURATION WITH MANUFACTURER SPECIFICATIONS PRIOR TO ROUGH—IN AND PROVIDE AS REQUIRED.

7. PROVIDE 120V CIRCUIT AS INDICATED FOR LOW VOLTAGE PANEL. TOP OF PANEL MOUNTED AT 12" BELOW CEILING. COORDINATE EXACT LOCATION AND MOUNTING REQUIREMENTS FOR RECEPTACLE PRIOR TO ROUGH-IN AND PROVIDE AS REQUIRED. LOW VOLTAGE PANEL SHALL BE UTILIZED FOR CATV/DATA/COMM DISTRIBUTION ONLY AND SHALL NOT CONTAIN OVERCURRENT DEVICES.

8. CONNECT EXHAUST FAN FOR DRYER VENT TO CIRCUIT SHOWN. COORDINATE WITH DIV. 15 FOR EXACT LOCATION PRIOR TO ROUGH-IN. PROVIDE 20A/1P MOTOR RATED SNAP SWITCH IF FAN IS NOT PROVIDED WITH FACTORY DISCONNECT.

9. CONTRACTOR SHALL INSTALL PANEL AS INDICATED AND MAINTAIN ALL WORKING SPACES PER NEC ART. 110.26. CONTRACTOR SHALL FIELD COORDINATE WITH OTHER TRADES AS REQUIRED TO MAINTAIN REQUIRED DEDICATED ELECTRICAL SPACE.

		E	QUIPM	ENT SC	HEDULE	
TAG	VOLTAGE	PHASE	PHASE	NUETRAL	GROUND	DISCONNECT MEANS
CU-1 & 3	240	1	(2) # 10	N/A	# 10	30A/2P/NF/N-3R
AHU-1,2,3 & 4	240	1	(2)#6	N/A	# 10	60A/2P/NF/N-1
CU-2 & 4	240	1	(2) # 8	N/A	#10	60A/2P/NF/N-3R
WH	240	1	(2) # 10	N/A	# 10	30A/2P/NF/N-1
DRYER	240	1	(2) # 10	#10	#10	RECEPTACLE
RANGE	240	• 1	(2) # 8	#10	#10	RECEPTACLE

JOB SITE PLANS

This set of plans must be kept on the job site of work at all times per Sarasota County Ordinance Sarasota County Planning &

Development Services

PA	ANEL	"A"	120/240V. 1PH, 3W	N	IEMA-	-1	150A MLO
SQL	JARE D	: QO	VOLTAGE/PHASE		FLUSH		150A BUS
СКТ	AMPS	POLE	DESCIPTION	СКТ	AMPS	POLE	DESCIPTION
1	30	2	CU-1	2	15	1	LV PNL/BOOSTER FAN - AFCI
3				4	20	1	MASTER BATH GFI RECEPT
5	60	2	AHU-1	6	20	1	BATHROOM 2 GFI RECEPT
7				8	15	1	BATHROOMS - GENERAL
9	35	2	WATER HEATER	10	15	1	MASTER BEDROOM - AFCI
11			6 KW	12	15	1	BEDROOM 2 - AFCI
13	30	2	DRYER	14	15	1	LIVING RM - AFCI
15				16	15	1	GENERAL - AFCI
17	40	2	RANGE	18	15	1	DEN - AFCI
19				20			SPACE
21	20	1	DISPOSAL	22			SPACE
23	20	1	SMALL APPLIANCE	24			SPACE
25	20	1	REFRIGERATOR	26		11 N.	SPACE
27	20	1	DISHWASHER	28			SPACE
29	20	1	SMALL APPLIANCE	30			SPACE
31	20	1	SMALL APPLIANCE	32	,		SPACE
33	20	1	LAUNDRY	34			SPACE
35			SPACE	36			SPACE
37			SPACE	38	15	1	LANAI
39			SPACE	40	15	1	GARAGE

PA	NEL '	"B"	120/240V. 1PH, 3W	N	IEMA-	-1	150A MLO
SQL	JARE D	: QO	VOLTAGE/PHASE		FLUSH		150A BUS
CKT	AMPS	POLE	DESCIPTION	CKT	AMPS	POLE	DESCIPTION
1	35	2	CU-2	2	15	1	LV PANEL - AFCI
3				4	20	1	MASTER BATH GFI RECEPT
5	60	2	AHU-2	6	20	1	BATHROOM 2 GFI RECEPT
7				8	15	1	BATHROOMS - GENERAL
9	35	2	WATER HEATER	10	15	1	MASTER BEDROOM - AFCI
11			6 KW	12	15	1	BEDROOM 2 - AFCI
13	30	2	DRYER	14	15	1	LIVING RM - AFCI
15				16	15	1	GENERAL - AFCI
17	40	2	RANGE	18	15	1	BEDROOM 3 - AFCI
19				20			SPACE
21	20	1	DISPOSAL	22			SPACE
23	20	1	SMALL APPLIANCE	24			SPACE
25	20	1	REFRIGERATOR	26			SPACE
27	20	1	DISHWASHER	28			SPACE
29	20	1	SMALL APPLIANCE	30			SPACE
31	20	1	SMALL APPLIANCE	32			SPACE
33	20	1	LAUNDRY	34			SPACE
35			SPACE	36			SPACE
37			SPACE	38	15	1	LANAI
39			SPACE	40	15	1	GARAGE


-30-1 **Permit**

Bay Street Village
7 Unit Condominium Building

11512 Lake Mead Ave., #301 Jacksonville, Florida 32256 904 732 7335 JOB NO: 02T12034 PROJ MGR: JD

E3.1

JOB NO: 02T12034 PROJ MGR: JD




Unit C	E	lectrica	I Plan
SCALE: 1/4"=1"			

D.4		10"	400/040/4 45/4 014	Γ .			
	NEL'		120/240V. 1PH, 3W	N	IEMA-	·1	150A MLO
SQL	JARE D	: QO	VOLTAGE/PHASE		FLUSH		150A BUS
CKT	AMPS	POLE	DESCIPTION	СКТ	AMPS	POLE	DESCIPTION
1	30	2	CU-3	2	15	-1	LV PANEL - AFCI
3				4	20	1	MASTER BATH GFI RECEPT
5	60	2	AHU-3	6	20	1	BATHROOM 2 GFI RECEPT
7				8	15	1	BATHROOMS - GENERAL
9	35	2	WATER HEATER	10	15	1	MASTER BEDROOM - AFCI
11			6 KW	12	15	1	BEDROOM 2 - AFCI
13	30	2	DRYER	14	15	1	LIVING RM - AFCI
15				16	15	1	GENERAL - AFCI
17	40	2	RANGE	18			SPACE
19				20			SPACE
21	20	1	DISPOSAL	22			SPACE
23	20	1	SMALL APPLIANCE	24			SPACE
25	20	1	REFRIGERATOR	26			SPACE
27	20	1	DISHWASHER	28			SPACE
29	20	1	SMALL APPLIANCE	30			SPACE
31	20	1	SMALL APPLIANCE	32			SPACE
33	20	1	LAUNDRY	34			SPACE
35			SPACE	36		/* -	SPACE
37			SPACE	38	15	1	LANAI
39			SPACE	40	15	1	GARAGE

			Y				
PA	NEL'	"D"	120/240V. 1PH, 3W	N	IEMA-	-1	150A MLO
SQL	JARE D	: QO	VOLTAGE/PHASE	:	FLUSH	<u> </u>	150A BUS
СКТ	AMPS	POLE	DESCIPTION	СКТ	AMPS	POLE	DESCIPTION
1	35	2	CU-4	2	15	1	LV PANEL - AFCI
3				4	20	1	MASTER BATH GFI RECEPT
5	60	2	AHU-4	6	20	1	BATHROOM 2 GFI RECEPT
7				8	15	1	BATHROOMS - GENERAL
9	35	2	WATER HEATER	10	15	1	MASTER BEDROOM - AFCI
11			6 KW	12	15	1	BEDROOM 2 - AFCI
13	30	2	DRYER	14	15	1	LIVING RM - AFCI
15				16	15	1	GENERAL - AFCI
17	40	2	RANGE	18	15	1	BEDROOM 3 - AFCI
19				20	15	1	GENERAL - AFCI
21	20	1	DISPOSAL	22	20	1	BATHROOM 3 GFI RECEPT
23	20	1	SMALL APPLIANCE	24			SPACE
25	20	1	REFRIGERATOR	26			SPACE
27	20	1	DISHWASHER	28			SPACE
29	20	1	SMALL APPLIANCE	30			SPACE
31	20	1	SMALL APPLIANCE	32			SPACE
33	20	1	LAUNDRY	34			SPACE
35			SPACE	36			SPACE
37			SPACE	38	15	1	LANAI
39			SPACE	40	15	1	GARAGE

							i
		E	QUIPM	ENT SC	HEDULE		2.5
TAG	VOLTAGE	PHASE	PHASE	NUETRAL	GROUND	DISCONNECT MEANS	
CU-1 & 3	240	1	(2) # 10	N/A	# 10	30A/2P/NF/N-3R	
AHU-1,2,3 & 4	240	1	(2) # 6	N/A	# 10	60A/2P/NF/N-1	
CU-2 & 4	240	1	(2) # 8	N/A	#10	60A/2P/NF/N-3R	
WH	240	1	(2) # 10	N/A	# 10	30A/2P/NF/N-1	
DRYER	240	1	(2) # 10	#10	#10	RECEPTACLE	
RANGE	240	1	(2) # 8	#10	#10	RECEPTACLE	



Unit D 1st Floor Electrical Plan

This set of plans must be kept on the job site of work at all times per Sarasota County Ordinance Sarasota County Planning & Unit D Development Services 2nd Floor Electrical Plan

JOB SITE PLANS

D-10 **©**/\$

A/C AHU-4

KEYED DRAWING NOTES

- 1. PROVIDE COMBINATION CARBON MONOXIDE AND SMOKE DETECTORS PER ALL APPLICABLE CODES. DETECTORS SHALL BE 120V. WITH BATTERY BACK-UP AND INTERCONNECTED SO THAT THE INITIATION OF ANY GIVEN DETECTOR SHALL SOUND ALL DETECTORS.
- 2. SEE EQUIPMENT SCHEDULE THIS SHEET FOR DISCONNECT SIZES, FUSING (WHERE REQUIRED) AND CONDUCTOR SIZES. CONDENSING UNIT DISCONNECT SWITCHES SHALL BE PROVIDED WITH BUILT-IN GFI/WP RECEPTACLES.
- 3. PROVIDE FAN RATED J-BOX TO SUPPORT THE WEIGHT OF THE FIXTURE/FAN SELECTED AT ALL FAN AND FUTURE FAN LOCATIONS. ALL FANS SHALL BE PRE-WIRED FOR SEPARATE LIGHTING CONTROL REGARDLESS IF LIGHT KIT IS BEING PROVIDED. WHERE SWITCHING IS NOT REQUIRED AT THIS TIME PROVIDE BLANK COVER PLATE AND TAG CONDUCTORS FOR FUTURE IDENTIFICATION.
- 4. PROVIDE DEDICATED 120V CIRCUIT AND 20A RECEPTACLE FOR UNDER COUNTER DISHWASHER. COORDINATE EXACT LOCATION AND RECEPTACLE CONFIGURATION WITH MANUFACTURER SPECIFICATIONS PRIOR TO ROUGH—IN AND PROVIDE AS REQUIRED.
- 5. PROVIDE DEDICATED 120V CIRCUIT AND 20A RECEPTACLE FOR REFRIGERATOR/FREEZER. COORDINATE EXACT LOCATION AND RECEPTACLE CONFIGURATION WITH MANUFACTURER SPECIFICATIONS PRIOR TO ROUGH-IN AND PROVIDE AS REQUIRED.
- 6. PROVIDE DEDICATED 120V CIRCUIT AND 20A RECEPTACLE FOR GARBAGE DISPOSAL. COORDINATE EXACT LOCATION AND RECEPTACLE CONFIGURATION WITH MANUFACTURER SPECIFICATIONS PRIOR TO ROUGH—IN AND PROVIDE AS REQUIRED.
- 7. PROVIDE 120V CIRCUIT AS INDICATED FOR LOW VOLTAGE PANEL. TOP OF PANEL MOUNTED AT 12" BELOW CEILING. COORDINATE EXACT LOCATION AND MOUNTING REQUIREMENTS FOR RECEPTACLE PRIOR TO ROUGH-IN AND PROVIDE AS REQUIRED. LOW VOLTAGE PANEL SHALL BE UTILIZED FOR CATV/DATA/COMM DISTRIBUTION ONLY AND SHALL NOT CONTAIN OVERCURRENT DEVICES.
- 8. CONTRACTOR SHALL INSTALL PANEL AS INDICATED AND MAINTAIN ALL WORKING SPACES PER NEC ART. 110.26. CONTRACTOR SHALL FIELD COORDINATE WITH OTHER TRADES AS REQUIRED TO MAINTAIN REQUIRED DEDICATED ELECTRICAL SPACE.

www.bsbdesign.com 0 11512 Lake Mead Ave., #301 Jacksonville, Florida 32256

> CHECKED: UNITS C AND D ELECTRICAL

> > E3.2

8.5

8.5

SEER

146

30

35

MOCP POWER

240/1

60

60

18.1

22.1

242

257

REMARKS

0234

0234

REMARKS

1234

0234

056

REMARKS

023

023

023

023

023

023

023

023

023

JOB SITE PLANS

This set of plans must be kept

on the job site of work at all times

REMARKS

1234

1234

Ave, orida

age Buildir Street Villa Condominium E East rey, I

Say Unit 160 Ospi

www.bsbdesign.com 11512 Lake Mead Ave., #301 Jacksonville, Florida 32256

904 732 7335 JOB NO: 02T11002 PROJ MGR: JPS RAWN: JPS CHECKED: MDL

MECHANICAL NOTES AND SCHEDULES

MECHANICAL NOTES

GENERAL: ALL WORK SHALL BE IN ACCORDANCE WITH THE FLORIDA BUILDING CODE (ed 2014), AND LOCAL CODES AND ORDINANCES. INSTALLATION SHALL COMPLY WITH THE STANDARDS SET BY NFPA, ASHRAE, SMACNA, NEC AND UL.

THE CONTRACTOR SHALL EXAMINE THE DRAWINGS AND SPECIFICATIONS BEFORE SUBMITTING A PROPOSAL. THE INFORMATION GIVEN HEREIN AND ON THE DRAWINGS IS AS EXACT AS COULD BE SECURED, BUT ITS EXTREME ACCURACY IS NOT GUARANTEED. CONTRACTOR SHALL FIELD VERIFY ALL INFORMATION GIVEN AS EXISTING CONDITIONS.

THE DRAWINGS ARE DIAGRAMMATIC, INTENDED TO SHOW GENERAL ARRANGEMENT, CAPACITY AND LOCATION OF VARIOUS COMPONENTS, EQUIPMENT, AND DEVICES.

THE SYSTEMS, EQUIPMENT, DEVICES AND ACCESSORIES SHALL BE INSTALLED, FINISHED, TESTED AND ADJUSTED FOR CONTINUOUS AND PROPER OPERATION.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR HIS WORK FITTING IN PLACE AND SHALL COORDINATE WITH OTHER TRADES TO AVOID INTERFERENCE WITH THEIR WORK.

IF WORK IS REQUIRED IN A MANNER TO MAKE IT IMPOSSIBLE TO PRODUCE FIRST CLASS WORK, OR SHOULD DISCREPANCIES APPEAR AMONG THE CONTRACT DOCUMENTS, OR BETWEEN THE CONTRACT DOCUMENTS AND THE MANUFACTURER'S RECOMMENDATIONS, OR DISCREPANCIES OCCUR BETWEEN ACTURAL CONDITIONS AND CONTRACT DOCUMENTS, THE CONTRACTOR SHALL REQUEST INTERPRETATION BEFORE PROCEEDING WITH WORK.

CONTRACTOR SHALL FURNISH AND INSTALL ALL MINOR ITEMS WHICH ARE OBVIOUSLY AND REASONABLY NECESSARY TO COMPLETE THE INSTALLATION WHETHER OR NOT SPECIFIED IN THE DOCUMENTS.

REFER TO ARCHITECTURAL EXTERIOR BUILDING ELEVATIONS FOR LOCATION OF LOUVERS AND WALL CAPS ON EXTERIOR FACADES.

CONTRACTOR SHALL CLEAN COILS AND REPLACE FILTERS AT SUBSTANTIAL COMPLETION. OPERATING AND MAINTENANCE DATA: SUBMIT THREE COPIES OF MANUFACTURER'S OPERATING AND MAINTENANCE INSTRUCTIONS AND SPARE PARTS LIST FOR EACH PIECE

GUARANTEE: THE ONE-YEAR GUARANTEE PERIOD SHALL NOT START UNTIL THE PROJECT IS FULLY COMPLETED AND THE CONTRACTOR HAS RECEIVED THE FINAL PAYMENT AND CERTIFICATION OF COMPLETION. ALL EQUIPMENT AND ALL WORK SHALL BE FULLY GUARANTEED, PARTS AND LABOR, FOR ONE YEAR FROM THE DATE OF THE CERTIFICATE OF COMPLETION. REPAIRS MADE DURING THIS PERIOD MUST BE FULLY GUARANTEED FOR AN ADDITIONAL ONE YEAR PERIOD FROM THE DATE OF REPAIRS. IN ADDITION, THE CONTRACTOR SHALL ASSUME FULL RESPONSIBILITY FOR ANY DAMAGE TO THE BUILDING, AND ITS CONTENTS OR OTHER EQUIPMENT, CAUSED BY DEFECTS OR IMPROPER INSTALLATION OF EQUIPMENT OR MATERIAL INSTALLED. ALL HAVE UNITS SHALL HAVE A FIVE (5) YEAR WARRANTY ON COMPRESSORS.

SHOP DRAWINGS: THE CONTRACTOR SHALL PREPARE AND SUBMIT SHOP DRAWINGS IN ACCORDANCE WITH PROCEDURES OUTLINED IN DIVISION 1. RESPONSIBILITY FOR ERRORS OR OMISSIONS IN THE SUBMITTALS SHALL NOT BE RELIEVED BY THE ARCHITECT'S OR ENGINEER'S REVIEW. ENGINEER'S PROCESSING WILL NOT CONSTITUTE A COMPLETE CHECK BUT WILL INDICATE ONLY THAT A GENERAL METHOD OF CONSTRUCTION AND DETAILING IS SATISFACTORY.

AS-BUILT DRAWINGS: THE CONTRACTOR SHALL KEEP A RUNNING SET OF DRAWINGS SHOWING ALL FIELD MODIFICATIONS FROM THE PERMIT SET IN A CLEAR, CONCISE MANNOR. THESE DRAWINGS SHALL BE MARKED AS "AS BUILT DRAWINGS" AND HANDED OVER TO THE OWNER AT THE COMPLETION OF THE PROJECT.

EQUIPMENT LABELS: ALL MECHANICAL EQUIPMENT SHALL BE LABELED WITH EQUIPMENT TAG AS DESIGNATED ON THE DRAWINGS.

SUBSTITUTIONS: EQUIPMENT AND MATERIALS SPECIFIED SHALL ESTABLISH QUALITY. CAPACITY, TYPE AND DIMENSIONS TO BE INCLUDED IN BASE BID. SUBSTITUTIONS MAY BE CONSIDERED. APPROVAL OF SUCH SUBSTITUTIONS WILL BE BASED ON ABILITY AND CAPACITY TO PERFORM FUNCTION SERVED, QUALITY AND AVAILABILITY OF PARTS AND SERVICE, QUALITY OF EQUIPMENT, MANUFACTURER WARRANTY AND HISTORY OF SERVICE, ETC. THE ENGINEER SHALL REVIEW ALL REQUESTS BUT RESERVES THE RIGHT OF JUDGMENT TO APPROVE OR REJECT ALL PROPOSED SUBSTITUTIONS. IF A SUBSTITUTED PRODUCT OR EQUIPMENT IS REJECTED, PROVIDE THE SPECIFIED PRODUCT

ACCESS: CONTRACTOR SHALL ENSURE THAT ACCESS IS PROVIDED FOR ALL ITEMS REQUIRING ACCESS FOR ADJUSTING OR MAINTENANCE. PROVIDE ACCESS PANELS AND DUCT ACCESS DOORS AS NECESSARY WITH NO ADDITIONAL COST TO THE OWNER. CONTRACTOR SHALL REVIEW MANUFACTURER'S RECOMMENDED CLEARANCES FOR ALL EQUIPMENT AND ENSURE THAT MINIMUM CLEARANCES ARE PROVIDED.

DUCT ACCESS DOORS SHALL BE HINGED TYPE. PROVIDE INSULATED ACCESS DOORS FOR INSULATED DUCTWORK. CONSTRUCT OF SAME OR THICKER GAUGE SHEETMETAL AS DUCT IN WHICH IT IS INSTALLED. PROVIDE FLUSH FRAMES FOR UNINSULATED DUCTS. PROVIDE CONTINUOUS HINGE ON ONE SIDE, WITH ONE HANDLE-TYPE LATCH FOR ACCESS DOORS 12" HIGH AND SMALLER AND TWO HANDLE-TYPE LATCHES FOR LARGER ACCSS DOORS.

TEST AND BALANCE: THE CONTRACTOR SHALL ENSURE THAT ALL HVAC DEVICES AND SYSTEMS ARE COMPLETE, TESTED AND BALANCED, AND READY FOR OPERATION WHEN THE FACILITY IS HANDED OVER TO THE OWNER. THE HVAC SYSTEM SHALL BE TESTED IN ACCORDANCE WITH AABC OR NEBB. ELIMINATE OBJECTIONABLE NOISE AND VIBRATION, AND ASSURE PROPER FUNCTION OF CONTROLS. SUBMIT REPORT FOR ENGINEER'S REVIEW. CORRECT ALL DISCREPANCIES.

WIND RESISTANCE: ALL EQUIPMENT, APPLIANCE, AND SUPPORTS LOCATED EXTERIOR OF THE FACILITY SHALL BE INSTALLED TO RESIST WIND LOADS AS DETAILED IN THE FLORIDA BUILDING CODE-CHAPTER 16.

CUTTING AND PATCHING: ALL OPENINGS AROUND DUCT OR PIPE PENETRATIONS THROUGH SMOKE OR FIRE RATED FLOORS, CEILINGS OR WALLS SHALL BE SEALED AIRTIGHT WITH MATERIAL HAVING A RATING EQUAL TO THE MATERIAL OF THE WALL, CEILING OR FLOOR PENETRATED.

DUCTWORK (GENERAL): DUCTWORK DIMENSIONS SHOWN ON DRAWINGS ARE CLEAR INSIDE DIMENSIONS. FABRICATE AND INSTALL IN ACCORDANCE WITH LOW VELOCITY DUCT CONSTRUCTION STANDARDS PUBLISHED BY SHEET METAL AND AIR-CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA). PROVIDE TURNING VANES AT ALL ELBOWS. MAXIMUM ALLOWABLE LEAKAGE IS 2%.

FLEXIBLE DUCT CONNECTORS: PROVIDE UL LISTED 30 OUNCE NEOPRENE COATED FIBERGLASS FABRIC DUCT CONNECTORS AT INTAKE AND DISCHARGE OF ALL HVAC

FIBROUS GLASS DUCTWORK: SUPPLY AND RETURNS SHALL BE FIBERGLASS DUCTBOARD. DUCTBOARD SHALL HAVE WITH AN INTERIOR SURFACE WHICH INHIBITS MOLD AND MILDEW GROWTH. DUCTS SHALL BE CONSTRUCTED AND INSTALLED IN ACCORDANCE WITH "FIBROUS GLASS DUCT CONSTRUCTION STANDARDS" BY SMANCA. DUCTWORK SHALL HAVE AN OPERATING RANGE OF POSITIVE OR NEGATIVE 2 INCHES W.G. PRESSURE, 1200 FPM VELOCITY AND 250°F AIR TEMPERATURE. DUCTS SHALL BE CONSTRUCTED OF 1-1/2" THICK (R-6) DUCTBOARD WITH A CLASS 1 UL-181 LISTING.

GALVANIZED SHEET METAL DUCTWORK: EXHAUST DUCTS SHALL BE GALVANIZED SHEET METAL DUCTWORK. SEAL ALL JOINTS WITH FLEXIBLE MASTIC SEALANT RECOMMENDED BY SMACNA. 'T-FLEX' MAY BE USED FOR THE FINAL CONNECTION TO THE EXHAUST FANS, AND NOT EXCEED 4 FEET.

FLEXIBLE DUCTWORK: PROVIDE FACTORY ASSEMBLED CLASS 1 AIR DUCT (UL-181) WITH 1" THICK 1 PCF FIBERGLASS INSULATION (R-6) AND REINFORCED OUTER PROTECTIVE COVER/VAPOR BARRIER, WITH A ENCAPSULATED HELIX COIL. FLEXIBLE DUCT SHALL MEET NFPA 90A WITH FLAME SPREAD UNDER 25, SMOKE DEVELOPED UNDER 50 AND SHALL BE RATED FOR MINIMUM 2" W.G. PRESSURE AND 0 TO 250°F TEMPERATURE.

CARE IS TO BE TAKEN THAT ALL RUNOUTS OF FLEXIBLE DUCT ARE INSTALLED AS STRAIGHT AS PRACTICAL AND FASTENED SO AS TO ELIMINATE AIR LEAKAGE. THE INSTALLATION SHALL CONFORM TO THE TECHNIQUES SHOWN IN THE UL APPROVED AND FACTORY-SUPPLIED INSTRUCTIONS SPECIFIED FOR THE PRODUCT.

DRYER VENTS: FURNISH AND INSTALL VENTS FOR EACH DRYER. INSTALL, SIZE AND LENGTH ACCORDING TO MANUFACTURER'S RECOMMENDATIONS WHICH WILL SUPERSEDE SIZES LISTED ON THE DRAWINGS IF DISCREPANCIES OCCUR. DUCT JOINTS SHALL NOT BE ASSEMBLED WITH SHEET METAL SCREWS OR OTHER FASTENING MEANS WHICH WILL EXTEND INTO THE DUCT. MINIMUM SIZE SHALL BE 4 INCHES. PROVIDE WEATHER CAP AND BACKDRAFT DAMPER. PROVIDE DRYER-BOX WALL PAN.

AIR DEVICES: PROVIDE GRILLES AND DIFFUSERS WITH THE CHARACTERISTICS SHOWN ON THE AIR-DEVICE SCHEDULE. REFER TO ARCHITECTURAL REFLECTIVE CEILING PLAN FOR FINAL AIR-DEVICE LOCATIONS.

REFRIGERANT PIPING: PROVIDE REFRIGERANT SUCTION AND LIQUID LINES AS NEEDED FROM EACH CONDENSING UNIT TO ITS RESPECTIVE DX COOLING COIL. PIPING SHALL BE ACR DRIED AND SEALED, SOFT COPPER WITH WROUGHT COPPER BRAZED JOINTS. COORDINATE ALL REFRIGERANT PIPING AND CHARGE WITH EQUIPMENT MANUFACTURER. UNDERGROUND REFRIGERANT LINES SHALL BE RUN IN PVC SLEEVE WITH BOTH ENDS

HEAT PUMP UNITS: PROVIDE PACKAGED COMPRESSOR/CONDENSER HEAT PUMP UNIT WITH CAPACITIES SCHEDULED AND ARE MATCHED WITH AHU. PROVIDE TIME DELAY RESTART RELAY, LOW VOLTAGE CONTROLS TRANSFORMER, CONTROLS FOR START AND OPERATION DOWN TO 36 DEGREES F., FAN RELAY, LIQUID LINE FILTER DRIER, CONTINUOUS PUMPDOWN CONTROLS.

AIR HANDLING UNITS: PROVIDE FACTORY ASSEMBLED AND TESTED PACKAGED AIR HANDLING UNIT MATCHED TO CONDENSING UNIT, WITH THE CAPACITIES SCHEDULED. UNITS SHALL USE R-410 A REFRIGERANT. UNITS SHALL BE UL AND AHRI CERTIFIED. UNITS SHALL HAVE FILTER RACK, ELECTRIC HEATERS, DUAL VOLTAGE, DIRECT DIRIVE BLOWER.

UNITS SHALL HAVE PRIMARY AND SECONDARY CONDENSATE DRAINS. PRIMARY DRAIN SHALL BE RUN TO THE EXTERIOR. SECONDARY DRAIN SHALL HAVE A FLOAT SWITCH TO SHUT DOWN UNIT IF PRIMARY DRAIN IS CLOGGED.

UNITS SHALL HAVE UNIT STAND/PLENUM BOX AND BE PROVIDED VIBRATION ISOLATOR SUPPORTS.

CONDENSATE DRAINS: CONDENSATE DRAIN LINES SHALL BE PROVIDED BY PLUMBING CONTRACTOR. COORDINATE WITH PLUMBING CONTRACTOR.

CEILING FANS: PROVIDE STANDARD PREFABRICATED CEILING EXHAUST FAN OF THE TYPE AND SIZE SCHEDULED. UNITS SHALL BE INSTALLED AT CEILING WITH MANUFACTURER'S GRILLE, PLUG-IN DISCONNECTS AND BACKDRAFT DAMPER. UNITS SHALL BE INSTALLED LEVEL AND THE INSTALLATION SHALL BE AS VIBRATION FREE AS POSSIBLE.

DRYER BOOSTER FAN: WHEN DRYER VENTS EXCEED ALLOWABLE LENGTH, A UL LISTED DRYER FAN SHALL BE INSTALLED AS SHOWN. FANS SHALL BE DESIGNED TO OPERATE IN HIGH MOISTURE, LINT AND DUCT LADEN AIR. FANS SHALL BE INSTALLED IN STRICT ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. FANS SHALL BE CONTROLLED BY PRESSURE SENSOR SWITCH FOR DRYER BOOSTING APPLICATION. FANS SHALL HAVE THE CHARACTERISTICS AND CAPACITIES SCHEDULE. FANS SHALL BE FANTEC OR APPROVED

PROVIDE INDICATOR LIGHT IN LAUNDRY ROOM THAT WILL ILLUMINATE WHEN FAN IS RUNNING. PROVIDE SIGN WHICH READS "BOOSTER FAN INDICATOR".

WINDLOADS: ALL EQUIPMENT INSTALLED EXTERIOR SHALL BE MECHANICALLY FASTENED PER MANUFACTURER'S SPECIFICATIONS TO WITHSTAND LOCAL WIND LOADS AND MEET THE FLORIDA BUILDING CODE REQUIREMENTS OF HURRICANE LOADS.

CONTROLS: ALL WALL MOUNTED THERMOSTATS SHALL BE INSTALLED AT AN ELEVATION OF 44" ABOVE FINISHED FLOOR. LOCATION OF THE THERMOSTATS SHALL BE COORDINATED WITH OTHER TRADES FOR A NEAT APPEARANCE. FINAL LOCATION OF THERMOSTAT SHALL BE SUBJECT TO THE APPROVAL OF THE ENGINEER OR HIS REPRESENTATIVE IN THE FIELD. TEMPERATURE CONTROLS SHALL BE COMPLETE WITH ALL COMPONENTS REQUIRED TO ACCOMPLISH THE CONTROL SEQUENCE SPECIFIED. MECHANICAL CONTRACTOR SHALL FURNISH, INSTALL AND WIRE ALL TEMPERATURE AND CONTROL INTERLOCKS.

CONTROL SEQUENCE: COOLING MODE: WHEN THE TEMPERATURE SENSOR SENSES THE SPACE TEMPERATURE IS ABOVE THE OCCUPIED SETPOINT, IT WILL PLACE THE UNIT IN SPEED COOLING MODE AND CYCLE THE COMPRESSOR TO MAINTAIN SPACE CONDITIONS.

OCCUPIED HEATING MODE: WHEN THE TEMPERATURE SENSES THE SPACE TEMPERATURE IS BELOW THE OCCUPIED SETPOINT, IT WILL PLACE THE UNIT IN HEAT PUMP MODE, AS CONDITIONS CHANGE AND SUPPLEMENTAL HEAT NEEDED. THE UNIT WILL ENERGIZE THE ELECTRICAL HEATER TO MAINTAIN SPACE CONDITIONS.

DEHUMIDIFICATION MODE: WHEN THE HUMIDISTAT SENSOR SENSES THE SPACE HUMIDITY IS ABOVE THE OCCUPIED SETPOINT, IT WILL PLACE THE UNIT IN COOLING MODE AND CYCLE THE COMPRESSOR TO MAINTAIN SPACE CONDITIONS.


MECHANICAL LEGEND						
MEGIAN						
	SUPPLY AIR DIFFUSER					
	RETURN AIR GRILLE					
	SIDEWALL SUPPLY GRILLE					
→	SIDEWALL RETURN GRILLE					
	RIGID DUCTWORK					
	FLEXIBLE DUCTWORK					
	DUCT TRANSITION					
	SUPPLY DUCT SECTION					
	RETURN DUCT SECTION					
	EXHAUST DUCT SECTION					
	CEILING EXHAUST FAN					
(T)	THERMOSTAT CONTROL HUMIDISTAT					
CFD ►	CEILING FIRE DAMPER					
	MANUAL VOLUME DAMPER					
- ₩	DOOR UNDERCUT					
Ø	ROUND, DIAMETER					

ABBREVIATIONS

	IDE DIGITAL HEAT PU IDE HUMIDSTAT	IMP PROGRAMMABL	E THERMOSTAT	WITH SUPPLE	MENTAL HE	CAT	·	3 DISCONNEC		
				FAN	SCHE	DULE				
MARK	MFG.	MODEL	CFM	POWER	ESP	AMP	RPM	SONES	WEIGH LBS	T
EF-1	GREENHECK	SP-B70	50	115/1	0.2	0.7	700	2.5	10	0
EF-2	GREENHECK	SP-B90	75	115/1	0.2	0.7	700	2.5	10	0
EF-3	FANTECH	DBF110	150	115/1	0.2	0.72				1
_	TIPLE FANS IN DISCONNECT		PROVIDE WITH			•		SURE SWITCH		
				ID DEV	ICE C	CUEDUIT	_			
						CHEDULI				
MARK	MFG.	MODEL	FUNCTIO		PE PE	MATERIAL	FINIS	н тн	ROW	REMARI
MARK A	MFG.	MODEL 404-M		N TY				= 4-	-WAY	00
			FUNCTIO	N TY	PΕ	MATERIAL	FINIS	E 4-	-WAY WAY	①②(①②(
А	AIRMATE	404-M	FUNCTIO SUPPLY	N TY CEII	PE	MATERIAL ALUMINUM	FINIS	= 4-	-WAY	00
A B	AIRMATE AIRMATE	404-M 401-HM	FUNCTIO SUPPLY SUPPLY	N TY CEII CEII	PE LING LING	MATERIAL ALUMINUM ALUMINUM	FINIS WHITE	E 4- E 1- E 2-	-WAY WAY	①②(①②(
A B C	AIRMATE AIRMATE AIRMATE	404-M 401-HM 401-HM	FUNCTIO SUPPLY SUPPLY SUPPLY	N TY CEII CEII CEII	PE LING LING LING	MATERIAL ALUMINUM ALUMINUM STEEL	FINIS WHITE WHITE	E 4- E 2- E 4-	WAY WAY	100 100 100
A B C D	AIRMATE AIRMATE AIRMATE AIRMATE	404-M 401-HM 401-HM 404-M	FUNCTIO SUPPLY SUPPLY SUPPLY SUPPLY	N TY CEII CEII CEII CEII	PE LING LING LING LING	MATERIAL ALUMINUM ALUMINUM STEEL STEEL	FINIS WHITE WHITE WHITE	E 4- E 2- E 4- E 1-	WAY WAY WAY	100 100 100 100
A B C D	AIRMATE AIRMATE AIRMATE AIRMATE AIRMATE AIRMATE	404-M 401-HM 401-HM 404-M 401-HM	FUNCTIO SUPPLY SUPPLY SUPPLY SUPPLY	N TY CEII CEII CEII CEII CEII	PE LING LING LING LING LING	MATERIAL ALUMINUM ALUMINUM STEEL STEEL STEEL	FINIS WHITE WHITE WHITE WHITE	E 4- E 2- E 1- E 2- E 2- E 2-	-WAY -WAY -WAY -WAY	100 100 100 100 100
A B C D E	AIRMATE AIRMATE AIRMATE AIRMATE AIRMATE AIRMATE AIRMATE	404-M 401-HM 401-HM 404-M 401-HM 163-M	FUNCTIO SUPPLY SUPPLY SUPPLY SUPPLY SUPPLY	N TY CEII CEII CEII CEII CEII CEII	PE LING LING LING LING LING LING LING	MATERIAL ALUMINUM ALUMINUM STEEL STEEL STEEL ALUMINUM	FINIS WHITE WHITE WHITE WHITE	= 4- = 1- = 2- = 4- = 1- = 2-	WAY WAY WAY WAY WAY	1020 1020 1020 1020 1020
A B C D E F R	AIRMATE AIRMATE AIRMATE AIRMATE AIRMATE AIRMATE AIRMATE AIRMATE AIRMATE	404-M 401-HM 401-HM 404-M 401-HM 163-M 280	FUNCTIO SUPPLY SUPPLY SUPPLY SUPPLY SUPPLY TRANSFE	N TY CEII CEII CEII CEII CEII CEII CEII CEI	PE LING LING LING LING LING WALL LING	MATERIAL ALUMINUM ALUMINUM STEEL STEEL STEEL ALUMINUM ALUMINUM	FINIS WHITE WHITE WHITE WHITE WHITE	E 4- E 2- E 1- E 2- E 2	-WAY -WAY -WAY -WAY	100 100 100 100 100 100 100

AIR HANDLER UNIT	AHU
BRITISH THERMAL UNITS	BTU
CEILING FIRE DAMPER	CD
CONDENSATE DRAIN	CU
CONDENSING UNIT	CFM
CUBIC FEET PER MINUTE	• F
DEGREE FAHRENHEIT	db
DRY BULB TEMPERATURE	EAT
ENTERING AIR TEMPERATURE	EA
EXHAUST AIR	EF
EXHAUST FAN	ESP
EXTERNAL STATIC PRESSURE	HP
HORSEPOWER	LAT
LEAVING AIR TEMPERATURE	NTS
NOT TO SCALE	OA
OUTSIDE AIR	OAT
OUTSIDE AIR TEMPERATURE	RA
RETURN AIR	SA
SUPPLY AIR	SD
SMOKE DETECTOR	TSP
TOTAL STATIC PRESSURE	TYP
TYPICAL	WG
WATER GAUGE	W/
WITH	wb
WET BULB TEMPERATURE	
EQUIPMENT TAG (AHU-1)	

		· W/	
		wb	
MPERATURE			,-,-
(AHU-1)			
MARK - 100 6 Ø	– CFM - NECK	SIZE	
	MARK 100	(AHU-1) MARK A)100 6ø	MPERATURE AHU—1) MARK————————————————————————————————————



HEAT PUMP UNIT SCHEDULE

LRA | FLA

AIR HANDLER UNIT SCHEDULE

HP

1/3

1/2

0.50

1.2

KW

10

10

73

79

240/1

240/1

58.5

58.5

CAPACITY BTU COMPRESSOR FAN

35,000 | 16.7

14.1

ESP

.5

.5

COOLING | HEATING | RLA |

3 ANTI-SHORT CYCLE TIMER

4 INDOOR FAN DELAY KIT

NOMINAL

2.5

35,000

CFM

1000

MODEL

215BNA036

MODEL

FX4DNF031L0

FX4DNF037L0

(2) PROVIDE MULTI-SHUTTER DAMPER

CU-1, 3 | BRYANT | 215BNA030

(1) DISCONNECT BY DIVISION 16

MFG.

BRYANT

BRYANT


BRYANT

(2) CRANKCASE HEATER

MARK

CONDENSER LOCATION PLAN 1/16" = 1'-0"

30



No. 56189

MATTHEWD, EWS. RE
MATTHEWD, EWS. RE
MS FL REGISTRATION No. 56189

REVISIONS

REVISIONS

MATTHEV

THESE PLANS AND SPECIFICATIONS ARE PROTECTED UNDER FEDERAL COPPRIGHT LAWS. © 858 DESIGN MANTANNS FL REGIS

H.R.H.O.R.T.O.N. BELLINGS 13880 Treeline Ave, Suite 3 Fort Myers, Florida 33913

Bay Street Village
7 Unit Condominium Building

160 East Bay Street Osprey, Florida 34229

EII BCR

DESIGN

www.bsbdesign.com

11512 Lake Mead Ave., #30

Jacksonville, Florida 32256

11512 Lake Mead Ave., #301 Jacksonville, Florida 32256 904 732 7335 JOB NO: 02T11002 PROJ MGR: JPS DRAWN: JPS CHECKED: MDL

M2.1

UNIT-A AND UNIT-B MECHANICAL PLANS

CEILING REGISTER DETAIL-2

SHALL BE GALVANIZED STEEL.
SPACING PER SMACNA STANDARDS.

FLEXIBLE DUCT HANGER DETAIL

Village nium Building Street Villa Condominium E t Bay Street Florida 3422 160 East Osprey, F Say Unit

BSB DESIGN

www.bsbdesign.com 11512 Lake Mead Ave., #301 Jacksonville, Florida 32256 904 732 7335 JOB NO: 02T11002 PROJ MGR: JPS

DRAWN: JPS CHECKED: MDL

UNIT-C AND UNIT-D MECHANICAL PLANS

-30

3. INSTALL CEILING FIRE DAMPER IN STRICT ACCORDANCE WITH

CEILING REGISTER DETAIL-1
NTS

MANUFACTURER'S WRITTEN INSTRUCTIONS.

SCOPE: THE CONTRACTOR SHALL EXAMINE THE DRAWINGS AND SPECIFICATIONS BEFORE SUBMITTING A PROPOSAL. THE INFORMATION GIVEN HEREIN AND ON THE DRAWINGS IS AS EXACT AS COULD BE SECURED, BUT ITS EXTREME ACCURACY IS NOT GUARANTEED. CONTRACTOR SHALL FIELD VERIFY ALL INFORMATION GIVEN AS EXISTING CONDITIONS.

THE DRAWINGS ARE DIAGRAMMATIC, INTENDED TO SHOW GENERAL ARRANGEMENT. CAPACITY AND LOCATION OF VARIOUS COMPONENTS, EQUIPMENTS, AND DEVICES.

ALL WORK SHALL BE IN ACCORDANCE WITH THE FLORIDA BUILDING CODE (ed 2014), AND LOCAL CODES AND ORDINANCES. INSTALLATION SHALL COMPLY WITH THE STANDARDS SET BY NFPA, ASPE, NEC AND UL.

THE SYSTEMS, EQUIPMENT, DEVICES AND ACCESSORIES SHALL BE INSTALLED, FINISHED, TESTED AND ADJUSTED FOR CONTINUOUS AND PROPER OPERATION.

IF WORK IS REQUIRED IN A MANNER TO MAKE IT IMPOSSIBLE TO PRODUCE FIRST CLASS WORK, OR SHOULD DISCREPANCIES APPEAR AMOUNG THE CONTRACT DOCUMENTS, OR BETWEEN THE CONTRACT DOCUMENTS AND THE MANUFACTURER'S RECOMMENDATIONS, OR BETWEEN CONTRACT DOCUMENTS AND ACTUAL FIELD CONDITIONS, THE CONTRACTOR SHALL REQUEST INTERPRETATION BEFORE PROCEDING WITH WORK.

CONTRACTOR SHALL FURNISH AND INSTALL ALL MINOR ITEMS WHICH ARE OBVIOUSLY AND REASONABLY NECESSARY TO COMPLETE THE INSTALLATION WHETHER OR NOT SPECIFIED IN THE DOCUMENTS.

EXACT LOCATIONS AND MOUNTING HEIGHTS OF PLUMBING FIXTURES SHALL BE OBTAINED FROM ARCHITECTURAL DRAWINGS.

COORDINATION: THE CONTRACTOR SHALL BE RESPONSIBLE FOR HIS WORK FITTING IN PLACE AND SHALL COORDINATE WITH OTHER TRADES TO AVOID INTERFERENCE WITH THIER WORK.

INSTALL ALL PLUMBING TO AVOID INTERFENCE WITH ELECTRICAL AND MECHANICAL EQUIPMENT AND STRUCTURAL FRAMING. NO WATER OR DRAIN LINES PERMITTED OVER OR UNDER ELECTRICAL PANELS.

SHOP DRAWINGS: EACH TRADE SHALL PREPARE AND SUBMIT SHOP DRAWINGS IN ACCORDANCE WITH PROCEDURS OUTLINED IN DIVISION 1. RESPONSIBILITY FOR ERRORS OR OMISSIONS IN THE SUBMITTALS SHALL NOT BE RELIEVED BY THE ARCHITECT'S OR ENGINEER'S REVIEW. ENGINEER'S PROCESSING WILL NOT CONSTITUTE A COMPLETE CHECK BUT WILL INDICATE ONLY THAT A GENERAL METHOD OF CONSTRUCTION AND DETAILING IS SATISFACTORY.

AS-BUILT DRAWINGS: DURING THE PROGRESS OF THE WORK, MAINTAIN AN ACCURATE RECORD SHALL SHOW CHANGES IN MANUFACTURER (WITH NUMBERS AND TRADE NAMES). MATERAILS, SIZES, LOCATIONS AND HOOK-UP POINTS. AS-BUILTS SHALL BE GIVEN TO OWNER'S CONSTRUCTION MANAGER AT COMPLETION OF JOB.

REQUIRED ACCESS: CONTRACTOR SHALL ENSURE THAT ALL EQUIPMENT AND DEVICES THAT REQUIRE REPLACEMENT, SERVICING, ADJUSTING OR MAINTENANCE SHALL BE LOCATED TO ALLOW EASY ACCESS AND SPACE FOR REMOVAL OF INTERNAL ASSMBLIES, IF REQUIRED. CONTRACTOR SHALL PROVIDE ACCESS PANELS WHERE REQUIRED TO ALLOW ACCESS, EVEN IF NOT INDICATED ON THE DRAWINGS AT NO ADDITIONAL COST TO OWNER.

OPERATING AND MAINTENANCE DATA: SUBMIT THREE COPIES OF MANUFACTURER'S OPERATING AND MAINTENANCE INSTRUCTIONS AND SPARE PARTS LIST FOR EACH PIECE OF EQUIPMENT.

VALVES: ALL VALVES SHALL HAVE A MINIMUM OF 125 PSIG WORKING PRESSURE. VALVES AND COCKS MAY NOT BE INDICATED IN EVERY INSTANCE ON THE DRAWINGS, BUT WHETHER OR NOT SHOWN, ALL VALVES, COCKS AND CHECK VALVES NECESSARY FOR THE PROPER OPERATION OF THE SYSTEM SHALL BE FURNISHED AND INSTALLED.

INSTALL ISOLATION/SHUT-OFF VALVES ON EACH INLET AND OUTLET OF EACH PIECE OF EQUIPMENT. PROVIDE A FLANGE OR UNION BETWEEN THE VAVLE AND THE EQUIPMENT TO PERMIT DISCONNECTION, REMOVAL AND SERVICE.

PROVIDE ANGLE STOPS ON ALL WATER SERVICE LINE TO INDIVIDUAL FIXTURES FOR

<u>DIELECTRIC UNIONS:</u> PROVIDE DIELECTRIC UNIONS OR FLANGES AT CONNECTIONS OR CONTACT BETWEEN PIPES OF DISSIMILAR METALS.

PLUMBING FIXTURES AND TRIM: PLUMBING FIXTURES SHALL BE FURNISHED AND INSTALLED IN A NEAT AND WORKMANLIKE MANNER WITH PROPER CONNECTIONS TO SUPPLY AND DRAINAGE PIPING. ALL FIXTURES SHALL BE FREE OF FLAWS AND DEFECTS OF ANY SORT IN MATERIAL AND WORKMANSHIP AND SHALL OPERATE PERFECTLY WHEN INSTALLED IN ACCORDANCE WITH MANUFACTURER'S DIRECTIONS. CONTRACTOR SHALL PROVIDE ROUGH-IN, AND SHALL CONNECT ALL FIXTURES TO THE PLUMBING SYSTEMS. PROVIDE CONCEALED ARM CARRIERS AND SUPPORTS FOR ALL FIXTURES REQUIRING SAME.

PIPE PENETRATION: PROVIDE SLEEVES THROUGH ALL PENETRATIONS THROUGH CONCRETE AND MASONARY FLOORS AND WALLS. SEAL ALL PENETRATIONS WATER

> ALL FIRE RATED FLOOR AND WALL PENETRATIONS SHALL BE PROPERLY PROTECTED FROM FIRE, SMOKE AND WATER PENETRATION BY FILLING VOIDS BETWEEN PIPE ANDE WALL/FLOOR SLEEVES WITH FIRE RATED FOAM TO ACHIEVE THE SAME RATING AS WALLS OR FLOOR.

WATER PIPING: CPVC TUBING WITH THE FOLLOWING CHARACTERISTICS. TUBING, FITTINGS AND CEMENT SHALL MEET ASTM D-2846, 100 PSI @ 180°F CONTINUOUS RATING. CPVC TUBING AND FITTINGS SHALL MEET 25/50 FLAME SPREAD/SMOKE DEVELOPED REQUIREMENTS FOR PLENUMS. CONTRACTOR SHALL INSTALL CPVC IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. CONTRACTOR SHALL PROVIDE FOR EXPANSION AND CONTRACTION OF TUBING. TUBING SHALL BE SLEEVED AT PENETRATION OF CONCRETE SLABS OR WALLS. CPVC TUBING SHALL BE FLOWGUARD GOLD OR APPROVED EQUAL.

PROVIDE BID ALTERNATE FOR PEX TUBING WITH THE FOLLOWING CHARACTERISTICS. TUBING AND FITTINGS SHALL MEET ASTM F876, ASTM 877, AND ASTM F1807. PEX TUBING AND FITTINGS SHALL MEET 25/50 FLAME SPREAD/SMOKE DEVELOPED REQUIREMENTS FOR PLENUMS. CONTRACTOR SHALL INSTALL PEX IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. TUBING SHALL BE SLEEVED AT PENETRATION OF CONCRETE SLABS OR WALLS. PEX TUBING SHALL BE ZURN-PEX OR APPROVED EQUAL.

SANITARY, STORM, DRAIN AND VENT PIPING: ALL BURIED AND UNBURIED PIPING AND FITTINGS SHALL BE SCHEDULE 40 PVC-DWV.

SLOPE OF SANITARY OR DRAINAGE PIPING 2-1/2" AND SMALLER SHALL BE A MINIMUM OF 1/4" PER FOOT; PIPING 3" AND LARGER SHALL BE SLOPED A MINIMUM OF 1/8" PER FOOT.

<u>VENTING</u>: THE STACKS SHALL BE EXTENDED THROUGH ROOF OF BUILDING TO POINTS NOT LESS THAN 12" ABOVE ROOF. VENTS SHALL BE OFFSET AS REQUIRED TO PENETRATE ROOFS AT LEAST 3 FEET EDGE OF BUILDING AND 10 FEET FROM ANY FRESH AIR INTAKE OR OPERABLE WINDOW OR DOOR.

DOMESTIC HOT WATER HEATERS (ELECTRIC): HOT WATER HEATER SHALL BE UL CERTIFIED. UNITS SHALL BE EQUIPPED WITH CODE-APPROVED TEMPERATURE AND PRESSURE RELIEF VALVES. TANKS SHALL BE GLASS-LINED AND SHALL HAVE MANUFACTURER'S STANDARD WARRANTY.

EQUIPMENT FURNISHED BY OTHERS: THE CONTRACTOR SHALL MAKE ALL PIPING CONNECTIONS TO EQUIPMENT FURNISHED BY OTHERS. THIS WORK SHALL INCLUDE FURNISHING AND INSTALLATION OF ALL WATER AND DRAIN PIPING. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH RECOMMENDATIONS OF EQUIPMENT MANUFACTURER.

CLEANOUTS: PROVIDE CLEANOUT WHERE SANITARY LINE LEAVES BUILDING. PROVIDE CLEANOUTS AT BASE OF EACH STACK. CONCEALED CLEANOUTS SHALL HAVE CAST BRASS CHROMIUM PLATED FLAT ACCESS COVER PLATE.

CONDENSATE DRAINS: COORDINATE WITH MECHINCAL CONTRACTOR. RUN CONDENSATE DRAIN LINES FOR MECHANICAL AIR HANDLER. CONDENSATE DRAIN SHALL BE MINIMUM OF 1" SCHEDULE 40 PVC. DRAINS SHALL BE PITCHED NOT LESS THAN 1" IN 10'. PROVIDE P-TRAP AND CLEANOUT AT DRAIN PAN CONNECTIONS. INSULATE CONDENSATE DRAINS WITH 1/2" ARMAFLEX. DRAINS SHALL BE ROUTED TO DRYWELL OR AN APPROVED LOCATION.

STERILIZATION OF DOMESTIC WATER SYSTEM: THE DOMESTIC WATER DISTRIBUTION SYSTEM SHALL BE PURGED OF DELETERIOUS MATTER AND WHERE REQUIRED REQUIRED BY THE ADMINISTRATIVE AUTHORITY, DISINFECTED PRIOR TO UTILIZATION. THE METHOD TO BE FOLLOWED SHALL BE PERSCRIBED BY THE HEALTH AUTHORITY OR WATER PURVEYOR HAVING JURISDICTION, OR THE ABSENCE OF A PRESCRIBED METHOD, THE PROCEDURE DESCRIBED IN EITHER AWWA C651 OR AWWA C652. OR AS DESCRIBED IN SECTION 610 FBC-P.

TESTING: TEST ALL WASTE AND VENT PIPING IN THE MANNOR REQUIRED BY LOCAL AUTHORITY HAVING JURISDICTION.

REPAIR ANY LEAKS FOUND BY REMAKING JOINT. DO NOT USE CAULKING OR SIMILIAR METHODS TO CORRECT LEAKS. UPON REPAIRING ANY LEAKS FOUND. AGAIN TEST THAT PORTION OF THE SYSTEM AS DESCRIBED ABOVE.

				FIX	XTUF	RE CONNECTION SCHED	ULE
		BF	RANCH	SIZE			
MARK	FIXTURE	DRAII	NAGE	WA	TER	MANUFACTURER/MODEL	REMARKS
		WASTE	VENT	COLD	HOT		
WC-D	WATER CLOSET	3"	2"	1/2"		AMERICAN STANDARD CADET 2852.000 OR EQUAL	VITREOUS CHINA, ROUND BOWL, FLOOR MOUNTED TANK TYPE WITH WHITE SOLID PLASTIC SEAT WITH LID. PROVIDE 3/8" SUPPLY AND STOP.
(- -)	LAVATORY	2"	2"	1/2"	1/2"	AMERICAN STANDARD AQUALYN 0476.028 AMERICAN STANDARD RELIANT 2385.006 OR EQUAL	20x17, SELF-RIMMING, VITREOUS CHINA, WITH FAUCET LEDGE AND INTERNAL OVERFLOW. PROVIDE SINGLE LEVER FAUCET, 4" CENTER, POP-UP DRAIN ASSEMBLY. PROVIDE TAILPEICE, P-TRAP, SUPPLY AND STOP.
S-1)	SINK	2"	2"	1/2"	1/2"	PROFLO PFT332264 SINK PROFLO PF2001M FAUCET BADGER 5 DISPOSAL OR EQUAL	33x22, DOUBLE BOWL, STAINLESS STEEL SINK UNDERSIDE FULLY SOUND DEADENED. PROVIDE DUO STRAINER, TAIL—PEICE, P—TRAP, SUPPLY AND STOP. CHROME FINISH, SINGLE HANDLE, KITCHEN SPOUT.
					+ 1		DISPOSAL: 1/2 HP, 6.9 AMPS, 120/1,
SH-1	SHOWER	2"	2"	1/2"	1/2"	CONTRACTOR BUILT SHOWER UNIT ZURN TEMP-GARD III Z27301-SS-MT OR EQUAL	REFER TO ARCHITECTURAL DRAWINGS FOR SHOWER UNIT. PROVIDE CHROME FINISHED PRESSURE—BALANCING MIXING VALVE WITH INTEGRAL SERVICE STOPS, SINGLE LEVER HANDLE AND SHOWER HEAD.
S 1− 1	SHOWER-TUB	2"	2"	1/2"	1/2"	PROFLO PFB6112 RIGHT—HAND TUB PROFLO PFB6113 LEFT—HAND TUB AURN TEMP—GARD III Z7302—SS—MT OR EQUAL	CONTRACTOR SHALL FIELD VERIFY QUANTITY OF LEFT HAND AND RIGHT HAND TUBS. TUBS SHALL BE CONSTRUCTED WITH ENAMILED STEEL WITH SLOPING BACK SUPPORT. TUBS SHALL HAVE INTEGRAL OVERFLOW, LIFT AND TURN STOPPER. PROVIDE CHROME FINISHED PRESSURE—BALANCING MIXING VALVE WITH INTEGRAL SERVICE STOPS, SINGLE LEVER HANDLE, SHOWER HEAD AND TUB SPOUT.
CB-1	ICE-MAKER CONNECTION BOX			1/2"		OATEY 38614 OR EQUAL	1/4 TURN BRASS BALL VALVE, PCVC RECESSED VALVE BOX.
CB-2	LAUNDRY CONNECTION BOX	2"	2"	1/2"	1/2"	OATEY 38747 OR EQUAL	1/4 TURN BRASS BALL VALVE, 2" DRAIN OPENING, PCVC RECESSED VALVE BOX.
HB-1)	HOSE BIBB			1/2"		WOODFORD MODEL 24 OR EQUAL	ANTI-SIPHON PROTECTION
(AAV-1)	AIR ADMITTANCE VALVE		2"	<u>-</u> -		STUDOR MINI-VENT OR EQUAL	
(HWH-)	HOT WATER HEATER			3/4"	3/4"	AO SMITH CONSERVATIONIST PXHT-40 OR EQUAL	40 GALLON, ELECTRIC, 240/1, 4.5 KW UPPER. PROVIDE EXPANSION TANK, SAFETY PAN, T&P VALVE AND ISOLATION VALVES. 0.95 ENERGY EFFICIENCY RATING
P-1)	RECIRCULATING PUMP				1/2"	TACO 003	HOT WATER RECIRCULATION PUMP. 115 V, 0.43 AMP, 1/40 HP, 1/2" CONNECTIONS, 5 FT HEAD. PROVIDE AQUASTAT.

PLUMBING LEGEND SYMBOL **DESCRIPTION** SANITARY DRAIN ______ COLD WATER SUPPLY HOT WATER SUPPLY PLUMBING VALVE CHECK VALVE PIPE DOWN PIPE UP ___ PLUMBING FIXTURE NUMBER RECIRCULATION PUMP PLUMBING ABBREVIATION DESCRIPTION **ABREVIATION** ABOVE FINISHED FLOOR CO CLEANOUT CV CHECK VALVE CWS COLD WATER SUPPLY GALLONS PER MINUTE HOT WATER HEATER HWS HOT WATER SUPPLY HOT WATER RETURN HWR PRV PRESSURE REDUCING VALVE TEMPERATURE AND PRESSURE VTR VENT THRU ROOF WALL CLEAN OUT NOT ALL SYMBOLS AND ABBREVIATION MAY BE USED ON THIS PROJECT

STEPANEK-LEWIS AND ASSOCIATES

fax (813) 991-5566


john@stepaneklewis.com

22557 Twelve Oaks Way


Wesley Chapel, Florida 33544


Suite 103

MAKE AND MODEL FOR BID PURPOSES ONLY. PROVIDE FIXTURE SUBMITTAL TO OWNER FOR APPROVAL



GRADE CLEANOUT DETAIL N.T.S





VENT THROUGH ROOF DETAIL

30

PLUMBING NOTES **DETAILS AND** SCHEDULES

Street Village Condominium Building 342

Suite (33913

elii 'S,

160 Fe Ospre

DESIGN

www.bsbdesign.com 11512 Lake Mead Ave., #301 Jacksonville, Florida 32256 904 732 7335

JOB NO: 02T11002 PROJ MGR: JPS DRAWN: JPS CHECKED: MDL

DJD DESIGN www.bsbdesign.com 11512 Lake Mead Ave., #301 Jacksonville, Florida 32256 904 732 7335

JOB NO: 02T11002 PROJ MGR: JPS CHECKED: MDL


SANITARY PLANS

REFER TO UNIT-B
FOR CONTINUATION
37(13 IRV)

SEFER TO UNIT
ONNECT DISHMASHER
TO KITCHEN SINK

SEFER TO UNIT
A

SEFER TO UNIT





SI-1) ¹

CONNECT DISHWASHER TO KITCHEN SINK


UNIT-C


REFER TO CIVIL FOR CONTINUATION





SECOND FLOOR SANITARY PLAN
1/8" = 1'-0"





D.R.HORTON 题 Merica's Swinder

Bay Street Village 6 Unit Condominium Building

Osprey, Florida 34229


11512 Lake Mead Ave., #301 Jacksonville, Florida 32256 904 732 7335

JOB NO: 02T11002 PROJ MGR: JPS DRAWN: JPS CHECKED: MDL

WATER PLAN UNIT A & UNIT B

N.T.S.





H.R. H. O. R. B. B. H. Americas Buite 3 Fort Myers, Florida 33913


Bay Street Village 6 Unit Condominium Building Osprey, Florida



www.bsbdesign.com 11512 Lake Mead Ave., #301 Jacksonville, Florida 32256 904 732 7335

JOB NO: 02T11002 PROJ MGR: JPS DRAWN: JPS CHECKED: MDL

WATER PLAN UNIT C & UNIT D



FOUNDATION NOTES

FOOTING EXCAVATIONS AND SLAB SUBGRADE SHALL BE COMPACTED TO AT LEAST 95% OF

ALL INTERIOR SLAB-ON-GRADE SHALL BE A MIN. OF 4" AND REINFORCED WITH WUF 6x6 WL4 x L4 OVER A 6 mil (10 mil. recommended) POLY VAPOR BARRIER W 6" LAP AND MIN. PERM RATING OF 05

THE DESIGN SOIL PRESSURE USED FOR ALL CALCULATIONS WAS 2000 PSF IN ACCORDANCE WITH STRUCTURAL NOTES

TOP OF FINISHED SLAB SHALL BE 0'-0", SEE SURVEY PLOT FOR NGVD.

COORDINATE SLAB AND FOOTING PENETRATIONS WITH PLUMBING, ELECTRICAL AND MECHANICAL DRAWINGS.

COLUMN AND FOOTING CENTERLINES, SHALL COINCIDE UNLESS DIMENSIONED OTHERWISE. PROVIDE A COMPLETE TREATMENT FOR THE PREVENTION OF SUBTERRANEAN TERMITES. TREATMENT SHOULD BE IN ACCORDANCE WITH THE RILES AND LAWS AS ESTABLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUMER SERVICES.

COORDINATE DIMENSIONS, SLAB ELEVATIONS, STEPS, AND SLOPES WITH ARCHITECTURAL


WINDOWS, DOORS AND ROUGH OPENINGS ARE TO BE COORDINATED WITH THE WINDOW/DOOR TYPES AND LOCATIONS NOTED ON THE ARCHITECTURAL DRAWINGS AND WITH THE MANUFACTURERS SPECIFICATIONS.

RATIONAL ANALYSIS WAS PERFORMED TO DETERMINE THE STEEL REINFORCING FOR THE FOUNDATION, DESIGNED WAS BASED ON AN ALLOWABLE SOIL BEARING CAPACITY OF 2,000 (1) (2) 4 × 4'-0" LONG DIAGONAL REBAR IN SLAB


F2 1" DOOR RECESS

WALL DOWELS


(1) #5 @ 48" O.C. MAXIMUM U.ON., MIN 25" LAP SPLICE	
INDICATES "5 DOWELS FOR FIRST FLOOR WALLS ONLY	
INDICATED®S DOWELS FOR FIRST FLOOR CONTINUOUS TO SECOND FLOOR WALLS	




SECTION AT EXTERIOR WALLS NOT TO SCALE



SECTION AT STEP DOWN NOT TO SCALE



SECTION AT INTERIOR BEARING WALLS NOT TO SCALE



THICKENED EDGE AS PER TABLE -

(1) 0 0 Street Village
Condominium Building

DESIGN

www.bsbdesign.com

100 Main St. Suite 209

Safety Harbor, Florida 34695

813 265 4808

JOB NO: 02T12034 PROJ MGR: LCC


FOUNDATION PLAN


S1.0

DRAWN: LCC CHECKED:

160 East Bay Street Osprey, Florida 34229

SECTION AT THICKENED EDGE NOT TO SCALE






KEY NOTES

- 2.1 8" DEEP PRE-CAST PRE-ENGINEERED CONCRETE QUAD TEE FLOOR SYSTEM - SEE SHOP DRAWINGS - TOP AT 10'-0" AFF.
- 4" DEEP PRE-CAST PRE-ENGINEERED CONCRETE QUAD TEE FLOOR SYSTEM - SEE DETAILS - TOP AT 9'-8" AFF.
- CMU WALL ABOVE SUPPORTED BY LINTEL NOT BEARING ON QUAD TEE SLAB BOTTOM AT 9'-4" AFF., SEE SHEET S20
- 2.4) 12"x24" PENETRATION IN CONCRETE QUAD TEE FLOOR SLAB FOR CMU WALL SUPPORTING UPSET LINTELS TOP AT 10'-4".
- 2.5 CMU WALL ABOVE SUPPORTED BY LINTEL WITH BOTTOM ELEV AT 8'-8". SEE SHEET S2.0.
- CMU WALL ABOVE SUPPORTED BY LINTEL WITH BOTTOM ELEV AT 9'-4". SEE SHEET 520.
- 2.7) PRE-MANUFACTURED WOOD FLOOR TRUSSES. SEE SHOP DRAWINGS.

 (2.6) PRE-MANUFACTURED ROOD ROOF TRUSSES. SEE SHOP DRAWINGS.
- (2) 2XI2 P.T. LEDGER ATTACHED TO CMU TIE BEAM AS PER WALL SECTIONS.
- (1) 2×8 P.T LEDGER ATTACHED TO CMU WALL W/ 1/4"×3" TAPCONS 6" O.C. STAGGERED.
- SEE PC-5 ON SHEET 52.0 FOR BEARING OF PRECAST SLAB OVER COLUMN



WALL REINFORCEMENT DOWELS

(1) #5 @ 48" O.C. MAXIMUM U.O.N., 25" MIN LAP SPLICE	
INDICATES #5 DOWELS FOR SECOND FLOOR WALLS ONLY	. 🖸
INDICATED CONTINUOUS #5 REINFORCEMENT FROM FIRST FLOOR TO SECOND FLOOR WALLS	· •

4-2015 Permit Se

07

www.bsbdesign.com


100 Main St. Suite 209
Safety Harbor, Florida 34695
813 265 4808

JOB NO: 02T12034 PROJ MGR: LCC
DRAWN: LCC CHECKED:

160 East Bay Street Osprey, Florida 342

LOWER ROOF AND SECOND FLOOR FRAMING PLAN

S3.0



Village ium Building Condominium

160 East Bay Street Osprey, Florida 342


BSB DESIGN

www.bsbdesign.com 100 Main St. Suite 209

Safety Harbor, Florida 34695 813 265 4808 JOB NO: 02T12034 PROJ MGR: LCC DRAWN: LCC CHECKED:

SECOND FLOOR PLAN STRUCTURAL

S4.0



Street Village
Condominium Building 160 East Bay Street Osprey, Florida 34229 Bay 7 Unit

DESIGN

www.bsbdesign.com 100 Main St. Suite 209 Safety Harbor, Florida 34695 813 265 4808

JOB NO: 02T12034 PROJ MGR: LCC DRAWN: LCC CHECKED:


UPPER ROOF FRAMING

20

S


PLAN - STRUCTURAL

S5.0






. .



5	seeure (PSF)	Design Pro	4554 (05)	E (FT)	SIZI	- A
Remarks	Negative	Positive	AREA (SF)	HEIGHT	MIDTH	MARK
	-32.9	29.9	42.5	5'-0"	8'-6"	wei
	-32.9	29.9	28.2	4'-10"	5'-10"	WØ2
	-34.0	31.3	3.4	1'-10"	1'-10"	WØ3
	-32.9	28.0	43.3	5'-0"	8'-8"	WØ4
	-340	313	15.0	5'-0"	3'-@"	WØ5
	-340	313	15.0	5'-0"	3'-0"	W06
	-340	31.3	100	5'-0"	2'-@"	WOT .
	-32.9	29.9	21.7	5'-@"	4'-4"	wes
	-32.9	29.9	30.0	5'-0"	6'-0"	WØ9
	-32.9	29.9	480	8'-0"	6'-0"	DØI
ARAGE DOOR	-312	27.6				DØ2
	-32.9	29.9	24.0	8'-Ø"	3'-0"	DØ3
	-32.9	29.9	24 <i>D</i>	8'-Ø"	3'-@"	DØ4
	-30.7	28.0	640	8'-0"	8'-0"	DØ5

JOB SITE PLANS

This set of plans must be kept
on the job site of work at all times
per Sarasota County Ordinance
Sarasota County Planning &
Development Services



07-24-20

JOB NO: 02T12034 PROJ MGR: LCC CHECKED:

Street Village
Condominium Building

3ay Unit

160 East Bay Street Osprey, Florida 34229

PRESSURES **S7.0**

WIND DESIGN

Jili BSB

DESIGN

www.bsbdesign.com

100 Main St. Suite 209 Safety Harbor, Florida 34695 813 265 4808

Suite 3 33913

STRUCTURAL SPECIFICATIONS

I. GENERAL 1. SUBCONTRACTOR IS RESPONSIBLE FOR MEANS AND METHODS OF CONSTRUCTION TO ENSURE TH SAFETY OF THE BUILDING UNTIL STRUCTURAL SYSTEM IS COMPLETED. THIS INCLUDES, BUT IS NOT LIMITED TO, THE ADDITION OF WHATEVER TEMPORARY BRACING, SHORING, GUYS TO TIE-DOWNS THAT 2. 6UBCONTRACTOR IS SOLELY RESPONSIBLE FOR THE SAFETY OF HIS WORK DURING CONSTRUCTION. 3. APPLICABLE BUILDING CODES: - FLORIDA BUILDING CODE (2014), DRAWINGS ARE CERTIFIED FOR STRUCTURAL PORTION ONLY THAT INCLUDES FOUNDATION SYSTEMS, BEAMS, POSTS, SHEARWALLS, STRUCTURAL CONNECTORS, REQUIRED WIND DESIGN PRESSURES, FASTENERS, SHEATHING MATERIAL AND THICKNESS, WALL STRUCTURAL ELEMENTS, HEADERS OVER WINDOWS, REINFORCED CONCRETE, STEEL FRAMING, WOOD FRAMING, MASONRY SIZES AND REINFORCEMENT, AND SPECIFICATIONS DESCRIBED HEREIN. 4. DESIGN LOADS: A. ROOF: 20 PSF 10 PSF (SHINGLES & METAL) DEAD LOAD B. UNINHABITABLE ATTICS WITH LIMITED STORAGE 10 PSF BALCONIES LIVE LOAD 60 PSF ALL OTHER ROOMS LIVE LOAD 40 PSF 10 PSF DEAD LOAD D. SNOW AND SEISMIC LOAD: NONE 5. STRUCTURAL MEMBER ALLOWABLE DEFLECTION Rafters having slopes greater than 3:12 with no finished ceiling attached to rafters interior walls and partitions Floors and plastered ceiling All other structural members Lintels supporting masonry veneer walls 6. ALL CONTRACTORS, SUBCONTRACTORS, SUPPLIERS AND FABRICATORS SHALL BE RESPONSIBLE FOR THE CONTENT OF DRAWINGS, AND FOR THE SUPPLY AND DESIGN OF APPROPRIATE MATERIALS AND WORK 7. ALL MANUFACTURED ARTICLES, MATERIALS AND EQUIPMENT SHALL BE APPLIED, INSTALLED, ERECTED, USED, CLEANED, AND CONDITIONED IN STRICT ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. 8. ALL STUCCO FINISH SHALL BE APPLIED AS PER ASTM C926 AND CONTROL JOINTS PROVIDED AS PER ASTM C1063. CURING TIME AS PER SECTION R10463 OF THE FLORIDA BUILDING CODE 5TH EDITION (2014). II. SITE WORK I. FOUNDATION DESIGN IS BASED ON A MINIMUM SOIL PRESSURE INDICATED ON THE FOUNDATION PLAN. THE CONTRACTOR IS RESPONSIBLE TO FOLLOW RECOMMENDATIONS NCLUDED IN THE RESPECTIVE GEOTECHNICAL REPORT AND SHALL CONFIRM THE SOIL EXIST, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY ENGINEER OF RECORD. 2. THE SUBGRADE UNDER THE NEW CONCRETE FOUNDATIONS SHALL BE COMPACTED TO 95% OPTIMUM DENSITY. SOIL COMPACTION TESTS TO BE TAKEN BY A GUALIFIED SOILS LAB PRIOR TO POURING ANY CONCRETE. 3. FOOTINGS SHALL BE NEAT EXCAVATED WHERE POSSIBLE WITH SIDES AND TOP EDGES FREE OF LOOSE OR WET MATERIALS. WHERE NEAT EXCAVATION IS NOT POSSIBLE, FOOTINGS EXCAVATION SHALL BE OPEN CUT WITH EDGES FORMED AND BRACED. ALL FOOTINGS WITH FORMED EDGES SHALL BE BACKFILLED FROM BOTTOM TO TOP OF FOOTING WITH SELECT FILL. THE BOTTOM EXCAVATION SHALL BE CLEAN AND DRY WITH ALL LOOSE MATERIAL REMOVED FOR AN ESSENTIALLY FLAT BEARING SURFACE. III. CAST IN PLACE CONCRETE 1. CONCRETE TO BE NORMAL WEIGHT WITH THE FOLLOWING MINIMUM COMPRESSIVE STRENGTHS AT 28 DAYS: a.) FOOTINGS, SLAB-ON-GRADE, SLAB FILL: b.) MASONRY WALL TIE BEAMS, TIE COLUMNS: 2500 PSi 2500 PSi 3000 PSi C.) REINFORCED CONCRETE BEAMS AND COLUMNS 2. CONCRETE SHALL BE READYMIX PER ASTM C94: a.) PORTLAND CEMENT - A6TM CI50 b.) AGGREGATE6 - A6TM C33 (3/4" MAX.) a) NO CALCIUM CHLORIDE e.) WATER REDUCING - ASTM C494 F) FLYASH - ASTM C618-78 CLASS F (20 % MAX) a) WATER - CLEAN AND POTABLE 3. REINFORCING STEEL: ASTM A615 GRADE 40, DEFORMED BARS. 4. REQUIRED SLUMP RANGE = 3" TO 5". 5. WELDED WIRE FABRIC: ASTM A185 6. MOISTURE BARRIER: 6 MIL POLYETHYLENE. a.) ACI 301 "SPEC FOR STRUCTURAL CONCRETE FOR BUILDINGS. b.) ACI 305 "RECOMMENDED PRACTICE FOR HOT WEATHER CONCRETING." a.) ACI 318 "BLDG. CODE REQUIREMENTS FOR REINF. CONCRETE." d.) ACT 315 "DETAILS AND DETAILING OF CONCRETE REINFORCEMENT." 8. MINIMUM LAP SPLICE . 40 BAR DIAMETERS UNLESS NOTED OTHERWISE 9. CONCRETE FINISHES SHALL BE PER CONTRACTOR'S SPEC'S. 10. SUBCONTRACTOR 16 RESPONSIBLE FOR THE PROPER DESIGN AND CONSTRUCTION OF ALL FORMWORK, SHORING, AND RESHORING. II. REINFORCING BAR COVER: b) COLUMNS 1 1/2" C.) BEAMS AND WALLS I 1/2" d.) 8LABS 3/4" (INTERIOR), 1 1/2" (EXTERIOR) 12. CONCRETE SHALL BE PLACED WITHIN 90 MINUTES OF BATCH TIME. 13. PROVIDE CORNER BARS AT ALL WALL FOOTING AND BEAM CORNERS TO MATCH HORIZONTAL BARG. (25" MINIMUM LAP FOR "5 BARG, OTHERS AS PER ACI 318). 14. ALL BUILDING SLABS-ON-GRADE SHALL BE NOMINAL 4" THICK, REINFORCED WITH 6X6-WIA WWF. ON 6 MIL VAPOR BARRIER SEE PLANS FOR OTHER CONDITIONS AND SIZES. NO FIBERMESH ALLOWED UNLESS OTHERWISE NOTED ON THE FOUNDATION PLAN. B. ANCHOR BOLTS FOR WOOD LEDGERS AND PLATES TO CONCRETE OR MASONRY (OPTIONS). a. J BOLTS - USE 1/2" X 8" "J" BOLTS WITH 6" EMBEDMENT AND 2" PROJECTION WHEN INSTALLED PRIOR TO PLACING CONCRETE, AS SHOWN ON DRAWINGS. b. EXPANSION ANCHORS - USE 1/2" \times 4" EMBED, HILTI KIJIK BOLT II, OR EQUAL, AT LOCATIONS (OTHER THAN EDGE CONDITIONS) IN LIEU OF 1/2" X 8" "J" BOLTS. C. EPOXY ANCHORS IN CONCRETE - USE 1/2" X 4-1/4" IMBED, WITH HILTI CIDD), OR ANCHOR BOND BY CELTITE, INC., AT EDGE OF SLAB CONDITION WHERE BOLT IS LESS THAN 6" TO A CONCRETE EDGE. d. EPOXY ANCHORS IN TOP OF BLOCK WALLS - USE THREADED ROD (3/4" \times A6-5/8" IMBED) ON TOP OF 8" MASONRY WALLS WITH HILTI HIT C-100 ADHESIVE OR ANCHOR BOND, WHEN 1/2" \times 8" 16. FOOTING SIZES SHOUN ARE TYPICAL ONLY FOR STATED SOIL BEARING PRESSURE AND CONSISTED COMPACTION. CONTRACTOR SHALL BE RESPONSIBLE FOR FOOTINGS COMPLYING WITH THE DESIGN REQUIREMENTS OF SPECIFIC SOIL CONDITIONS 17. PROVIDE 1/2" EXPANSION JOINT MATERIAL BETWEEN ALL CONCRETE SLABS AND

ABUTTING CONCRETE OR MASONRY WALLS OCCURRING IN EXTERIOR OR UNHEATED AREAS.

16. PROVIDE 1/4" SAW CUT EXPANSION JOINTS ON SLABS SPACED AT NO MORE THAN IS FEET ON

1. HOLLOW LOAD BEARING UNITS (CMU) SHALL CONFORM TO ASTM CSØ, NORMAL WEIGHT, TYPE I, GRADE N. MINIMUM NET COMPRESSIVE STRENGTH = 1900 PSI.

4. BARS SHALL HAVE MINIMUM CLEARANCE OF 1/2" FROM MASONRY. THE CLEAR DISTANCE

5. VERTICAL REINFORCING SHALL BE AT ALL CORNERS, EACH JAMB OF OPENINGS, UNDER ALL

6. REINFORCING BARS SHALL BE STRAIGHT EXCEPT FOR BENDS AROUND CORNERS AND WHERE

8. WHEN A FOUNDATION DOWEL DOES NOT LINE UP WITH A VERTICAL CORE, IT SHALL NOT BE SLOPED MORE THAN ONE HORIZONTAL IN SIX VERTICAL. DOWELS SHALL BE GROUTED INTO A CORE IN VERTICAL ALIGNMENT, EVEN THOUGH IT IS IN AN ADJACENT CELL TO THE VERTICAL WILL BE VERTICAL.

T. REINFORCING BARS SHALL BE LAPPED 40 BAR DIAMETERS WHERE SPLICED AND SHALL

9. CLEANOUTS SHALL BE PROVIDED IN THE BOTTOM COURSE OF MASONRY IN EACH GROUT POUR WHEN THE POUR HEIGHT EXCEEDS 5'. PROVIDE 4" X 4" OBSERVATION HOLE TO VERIFY CONCRETE GROUT PLACEMENT.

II. PROVIDE 8" X 8" PRECAST REINFORCED CONCRETE LINTELS OVER ALL MASONRY OPENINGS NOT SHOWN TO HAVE A STRUCTURAL BEAM. MINIMUM END BEARING. = 4"

13. PROVIDE HORIZONTAL REINFORCEMENT AT EVERY OTHER COURSE USING 120 TRUSS-MESH BY

10. PLACE ALL MASONRY IN RUNNING BOND WITH 3/8" MORTAR JOINTS. PROVIDE COMPLETE COVERAGE FACE SHELL MORTAR BEDDING, HORIZONTAL AND VERTICAL. FULLY

MORTAR WEBS IN ALL COURSES OF PIERS, COLUMNS, AND PILASTERS AND AND ADJACENT TO GROUTED CELLS.

REFER TO LINTEL SCHEDULE (MINIMUM CAPACITY OF 1000 PLF). 12. PROVIDE METAL CAVITY CAPS, 6" WIRE MESH, OR EQUAL PRODUCTS, INC., WHERE

REQUIRED TO RETAIN GROUT IN VERTICAL CELLS.

GIRDER LOADS, AND NOT TO EXCEED 6'0" O/C FOR STRAIGHT WALLS, OR AS SHOWN ON THE DRAWINGS. FILL CELLS WITH CONCRETE GROUT AS SPECIFIED. PROVIDE ACI 318 90 DEGREE

BETWEEN BARS SHALL NOT BE LESS THAN ONE BAR DIAMETER, NOR LESS THAN I".

CENTER EACH WAY AND AS SHOWN ON PLANS

3. CONCRETE GROUT SHALL CONFORM TO ASTM C476:

STANDARD HOOKS INTO FOOTING, AND TIE BEAMS.

BENDS OR HOOKS ARE DETAILED ON THE PLANS.

a.) 2500 PSI AT 28 DAYS.

BE WIRED TOGETHER

HOHMANN 4 BARNARD.

2. MORTAR SHALL BE TYPE M OR 6 AND CONFORM TO ASTM C270.

1. DIMENSIONED LUMBER SHALL BE DRESSED \$45, AND SHALL BEAR THE GRADE STAMP OF THE MANUFACTURER'S ASSOCIATION. 2. ALL LUMBER SHALL BE SOUND, SEASONED, AND FREE FROM WARP. 3. ALL STRUCTURAL BEAMS AND HEADERS SHALL BE SOUTHERN YELLOW PINE (SYP.) NO. 1 GRADE OR BETTER, WITH SINGLE MEMBER (UNFACTORED) STRESSES AS FOLLOWS: Fc = 975 P6 E = 1600000 PAI 19% MAXIMUM MOISTURE CONTENT A FRAMING LUMBER SHALL BE 12 SPRUCE-PINE-FIR OR BETTER B. INTERIOR NON-LOAD BEARING WALLS MAY BE UTILITY GRADE. 4. ALL LUMBER IN CONTACT WITH MASONRY OR CONCRETE SHALL BE PRESSURE TREATED. 5. PRESSURE TREATED LUMBER SHALL BE PROVIDED IN ACCORDANCE WITH THE AMERICAN WOOD PROTECTION ASSOCIATION LATEST STANDARDS. 6. SHEATHING FOR ROOFS AND WALLS SHALL BE APA RATED (EXPOSURE 1) SHEATHING WITH EXTERIOR GLUE, ALL ROOF SHEATHING TO BE INSTALLED WITH PLYCLIPS, (MAXIMUM 24" O/C). THICKNE66 TO BE MINIMUM 15/32" FOR SHINGLE ROOF AND 1/2" FOR TILE ROOF 1. NAILING FOR PLYWOOD ROOFS AND WALL SHEATHING SHALL BE SD RING SHANK . 4" O.C. . PANEL EDGES, AND 6" O.C. INTERMEDIATE, FOR 1/2" SHEATHING OR LEGO. NAILING FOR STRUCTURALLY APPROVED ARCHITECTURAL WALL PANELS (1/4"+) SHALL BE 6D COMMON • 4" O/C AT PANEL EDGES, AND 6" O/C INTERMEDIATE. 8. ALL FLOORING MATERIAL TO BE 3/4" T4G PLYWOOD, NAILED AND GLUED TO FLOOR JOISTS. FLOOR NAIL WITH IND NAILS AT 3" O/C AT PANEL EDGES, 6" O/C IN THE FIELD. STAGGER NAILS AT 2" O/C AT BUTT ENDS OF PLYWOOD SHEATHING. 9. INSTALL BRIDGING IN ALL (2X) FLOOR OR ROOF JOISTS AT 8'-0" MAXIMUM, INSTALL BLOCKING IN ALL BEARING WALLS AND PARTITIONS OVER 9'-0" •
MID-HEIGHT. BRACE GABLE END WALLS AT 4'0" O/C WHERE WALL FRAMING IS NOT CONTINUOUS FROM FOUNDATION TO ROOF, OR AS SHOWN ON DRAWINGS 10. ALL NAILING AND BOLTING SHALL COMPLY WITH AMERICAN INSTITUTE OF TIMBER CONSTRUCTION REGUIREMENTS. ALL NAILS EXPOSED TO THE EXTERIOR SHALL BE GALYANIZED II. ALL CONNECTION HARDWARE SHALL BE GALVANIZED AND SUPPLIED BY SIMPSON STRONGTIE CO., OR EQUIVALENT. SUBMIT CUT SHEETS FOR ALL CONNECTION HARDWARE TO CONTRACTOR FOR APPROVAL. ALL NAIL HOLES SHALL BE FILLED OR AS PRESCRIBED BY THE MANUFACTURER 12. PROVIDE A SINGLE PLATE AT THE BOTTOM AND DOUBLE PLATE AT THE TOP OF ALL LOAD BEARING STUD WALLS, STAGGER END JOINTS IN DOUBLE PLATES AT LEAST 4'-0"
PER DETAIL. 2 × 4 SILL PLATES FOR BEARING WALLS SHALL BE BOLTED TO
FOUNDATION AS PER BEARING WALL DETAIL. 13. LOAD BEARING STUDS SHALL BE DOUBLED AT ALL ANGLES AND AROUND ALL OPENING AND AT STRUCTURALLY APPROVED ARCHITECTURAL WALL PANEL JOINTS. STUDS SHALL BE TRIPLED AT ALL CORNERS. 14. WOOD LINTELS OVER OPENINGS SHALL BE DOUBLED 2XIZ HEADERS UNLESS NOTED OTHERWISE ON PLANS, WITH CONTINUOUS 1/2" PLYWOOD FILLER CUT TO FULL DEPTH OF BEAM BETWEEN 2x MEMBERS. B. RAFTER SCHEDULE FOR CONVENTIONAL FRAMED AREAS UNLESS OTHERWISE NOTED. NOTE I: RAFTERS MUST BE BRACED LATERALLY BY A CONTINUOUS NAILING OF NOTE 2: RAFTER SPACING NOT TO EXCEED 24" O/C. NOTE 3: RIDGE BOARDS TO BE ONE SIZE LARGER THAN RAFTER UNLESS NOTE 4: CONNECTOR SCHEDULE

VI. PRE-ENGINEERED WOOD TRUSSES I. THIS SECTION DEFINES PRE-ENGINEERED, PREFABRICATED, METAL PLATE CONNECTED 2. TRUSS LAYOUTS SHOWN ON PLANS ARE SCHEMATIC ONLY. TRUSS MANUFACTURER AND/OR ENGINEER SHALL BE RESPONSIBLE FOR THE DESIGN AND SPACING OF ALL TRUSSES AND SHALL SUBMIT SHOP DRAWINGS TO THE BUILDER FOR APPROVAL. 3. THE WOOD TRUSS MANUFACTURER MUST PARTICIPATE IN A CODE APPROVED THIRD PARTY QUALITY ASSURANCE PROGRAM SUCH AS THE TRUSS PLATE INSTITUTE'S "QUALITY CONTROL INSPECTION PROGRAM" OR EQUIVALENT.

A SIMPSON MT820 (OR EQUAL) BETWEEN CAT BLOCKING AND ROOF TRUSSES.

B. SIMPSON HS (OR EQUAL) BETWEEN RAFTER TAILS TO CAT BLOCKING. C. SIMPSON HS (OR EQUAL) BETWEEN THE RAFTERS AND RIDGE BOARD. D. SIMPSON CS20 AT ENDS OF RIDGE BOARD, OR SIMPSON JOIST

OTHERWISE NOTED ON PLANS.

HANGER WHERE APPLICABLE.

) YALLEY SETS FOR OVER-BUILD CONDITION

THE CONTRACT DOCUMENTS INCLUDING: LIVE, DEAD, AND CONCENTRATED LOADS, PLUS 5. REFER TO THE FLOOR PLAN AND OTHER STRUCTURAL DETAIL SHEETS FOR IMPORTANT INFORMATION NOT SPECIFICALLY ADDRESSED BY THE TRUSS FRAMING LAYOUT SUCH AS BEARING WALL HEIGHTS AND CEILING VAULT DETAILS.

6. WOOD TRUSS DESIGN SHOP DRAWINGS SHALL INCLUDE, BUT ARE NOT LIMITED TO, THE FOLLOWING INFORMATION: a.) SPAN LENGTH, OVERHANG AND EAVE DIMENSIONS, SLOPE AND SPACING OF THE WOOD TRUBBES.

b.) ALL DESIGN LOADS AND THEIR POINTS OF APPLICATION, VALLEY AND CONVENTIONAL FRAMING MUST BE CONSIDERED.

c.) ADJUSTMENTS TO ALLOWABLE VALUES.

EL REACTIVATE FORCES AND THEIR LOCATIONS D) BEARING TYPE AND MINIMUM BEARING LENGTH. g.) METAL CONNECTOR PLATE TYPE, GALIGE, SIZE, AND LOCATION.
N) LUMBER SIZE, SPECIES, GRADE AND MOISTURE CONTENT.
1.) LOCATION AND CONNECTION DESIGN OF REQUIRED CONTINUOUS LATERAL BRACING. I) NET UPLIFT LOADS BASED ON ACTUAL BUILDING DEAD LOAD. WEB REINFORCEMENT DETAILS FOR GABLE END TRUSSES.

1. LIMIT DEFLECTIONS FOR LIVE LOAD TO SPAN/360 (ROOF), SPAN/480 (FLOOR), AND LIMIT TOTAL LOAD DEFLECTIONS TO SPAN/240 (ROOF), SPAN/360 (FLOOR) UNLESS SPECIFICALLY NOTED OTHERWISE.

8. FIRE RETARDANT WOOD 16 NOT ALLOWABLE FOR USE AS TRUSS CHORDS OR WEBS. 9. WOOD TRUBSES SHALL BE DESIGNED SO THAT MINIMAL HORIZONTAL REACTIONS ARE IMPOSED ON THE SUPPORTING STRUCTURE UNDER VERTICAL LOADS. NO SLIP CONNECTIONS ARE ALLOWED UNLESS OTHERWISE NOTED. CONTACT CONTRACTOR AS REQUIRED.

10. WOOD TRUBSES MUST BE CHECKED FOR WIND. WIND VELOCITY, DESIGN VELOCITY Pressures, and mean roof height must be shown on the submitted shop drawings. IL CONTINUOUS BOTTOM CHORD LATERAL BRACING IS REQUIRED AT A MINIMUM

SPACING OF 10' OC. UNLESS NOTED OTHERWISE. BOTTOM CHORD BRACING IS CONTINUOUS FROM ONE END OF THE BUILDING TO THE OTHER END. OVERLAP CONTINUOUS BRACING AT LEAST ONE TRUSS SPACE. USE A MINIMUM OF 2×4 (ROOF), 2×6 (FLOOR) GRADE MARKED LUMBER AT LEAST 10' LONG, WITH 2-16d NAILS AT INTERMEDIATE AND 3-16d NAILS AT END CONNECTIONS.

12. CROSS BRACING IS REQUIRED AT MINIMUM 10' O.C. UNLESS NOTED OTHERWISE. LOCATE CROSS BRACING AT OR NEAR THE BOTTOM CHORD BRACING. INSTALL CROSS BRACING AT EACH END AND AT 20' O.C. ALONG THE LENGTH OF THE LATERAL BRACING. CROSS BRACING IS ACCOMPLISHED BY ATTACHING DIAGONAL WEB BRACING TO OPPOSITE SIDES OF THE SAME GROUP OF SIMILAR WEB MEMBERS. SLOPE CROSS BRACING IN OPPOSITE DIRECTIONS AT APPROXIMATELY 45 DEGREES FORMING A CROSS "X". USE A MINIMUM OF 2X4 GRADE MARKED LUMBER WITH AT LEAST 3-16d NAILS AT EACH CONNECTION.

13. TRUGG ERECTOR IS RESPONSIBLE FOR ALL TEMPORARY BRACING OF TRUGG SYSTEM DURING CONSTRUCTION

14. HANDLING, INSTALLATION, AND BRACING OF WOOD TRUSSES SHALL BE IN ACCORDANCE WITH "HIB-91", PUBLISHED BY THE TRUSS PLATE INSTITUTE. IB. ALL WOOD TRUSSES SHALL BE FASTENED TO THEIR SUPPORTS WITH APPROVED HURRICANE

ANCHORS, RATED TO CARRY LIPLIFT LOADS SPECIFIED BY TRUSS MANUFACTURER 16. ALL CONNECTION HARDWARE SHALL BE GALVANIZED AND SUPPLIED BY SIMPSON STRONG-TIE, OR APPROVED EQUIVALENT MANUFACTURER. ALL NAIL HOLES SHOULD BE FILLED, OR AS PRESCRIBED BY THE MANUFACTURER.

17. TRUSSES ARE TO BE DESIGNED TO ALLOW FOR THE PROPER ROUTING OF A/C DUCT WORK AND PLUMBING. CHASES SHALL NOT BE BLOCKED BY WOOD TRUSSES. 18. PILING OF PLYWOOD ON WOOD TRUBSES IS NOT ALLOWED.

19. INSTALLATION OF BROKEN, DAMAGED, WARPED, OR IMPROPERLY REPAIRED WOOD TRUSSES IS NOT ALLOWED. 20. IMPROPER OR UNAUTHORIZED FIELD ALTERATIONS OF WOOD TRUSSES IS NOT ALLOWED.

21. GABLE ENDUALL TRUSSES MUST TRANSFER LATERAL LOADS TO THE SHEAR WALLS AND/OR THE ROOF DIAPHRAGM. 22. WOOD TRUSSES THAT DO NOT MEET INTERIOR LOAD BEARING WALLS MUST BE SHIMMED.

DO NOT FULL WOOD TRUGGES DOWN TO INTERIOR BEARINGS. 23. SUBMITTALS: ALL SUBMITTALS SHALL BEAR THE EMBOSSED SEAL OF A LICENSED STRUCTURAL ENGINEER IN THE STATE OF FLORIDA AND SHALL BE SUBMITTED TO CONTRACTOR FOR REVIEW PRIOR TO WOOD TRUSS FABRICATION.

a) SUBMIT SEALED WOOD TRUSS DESIGN CALCULATIONS AND PROFILES FOR EACH TYPE OF TRUSS WITH PERMANENT BRIDGING REQUIREMENTS.
b) SUBMIT WOOD TRUSS ERECTION PLAN, INCLUDING CONNECTION DETAILS AND UPLIFT C.) SUBMIT WOOD TRUGG TEMPORARY ERECTION BRACING PLAN. d) Maintain copy of submittal on Jobsite.

PROTECTION AGAINST TERMITES

RSIS.I Termite Protection. Termite protection shall be provided by registered termiticides, including soil applied posticides, baiting systems and posticides applied to wood, or other approved methods of termite protection labeled for use as a preventative treatment to new construction. See Section 202, Registered termiticide. Upon completion of the application of the termite protective treatment, a Certificate of Compliance shall be issued to the building department by the licensed peet control company that contains the following statement: The building has received a complete treatment for the prevention of subterranean termitee. Treatment is in accordance with the state and laws and all the state that the state of control with rules and laws established by the Florida Department of Agriculture and Consumer Services.

R318.1.1 If soil treatment is used for subterranean termite prevention, the initial chemical soil treatment inside the foundation perimeter shall be done after all excavation, backfilling and compaction is complete.

subsequent installation of plumbing traps, drains or any other purpose shall be created by using plastic or netal permanently

R3I8.12 If soil treatment is used for subterranean termite prevention, soil area disturbed after initial chemical soil treatment shall be retreated with a chemical soil treatment, including spaces boxed or formed. R3I8.13 If soil treatment is used for subterranean termitie prevention, space in concrete floors boxed out or formed for the

placed forms of sufficient depth to eliminate any planned soil disturbance after initial chamical soil treatment. R3/8/14 If soil treatment is used for subterranean termite prevention, chemically treated soil shall be protected with a minimum 6 mil vapor retarder to protect against rainfall dilution. If rainfall occurs before vapor retarder placement, retreatment is required. Any work, including placement of reinforcing steel, done after chemical treatment until the concrete floor is poured, shall be done in such marner as to avoid penetrating or disturbing treated soil.

R3I8.15 If soil treatment is used for subterranean termits prevention, concrete overpour or mortar accumulated along the exterior foundation perimeter shall be removed prior to exterior chemical soil treatment, to enhance vertical penetration of the chemicals. R3(8).6 If soil treatment is used for subterranean termite prevention, chemical soil treatments shall also be applied under all exterior concrete or grade within 1 foot (305 mm) of the primary structure sidewalls. Also, a vertical chemical barrier shall be applied promptly after construction is completed, including initial landscaping and irrigation/sprinkler installation. Any soil disturbed after the chemical vertical barrier is applied shall be promptly retreated.

R3I8.IT If a registered termiticide formulated and registered as a balt system is used for subterranean termitic prevention, Sections RSIBLI through RSIBLE do not apply: however, a signed contract assuring the installation, maintenance and monitoring of the balting system for a minimum of 5 years from the issue of the Certificate of Occupancy shall be provided to the building official prior to the pouring of the slab, and the system must be installed prior to final building approval. If the balting system directions for use require a monitoring phase prior to installation of the pesticide active ingredient, the installation of the monitoring phase components shall be deemed to constitute installation of the system.

R3I8.18 If a registered termiticide formulated and registered as a wood treatment is used for subterranean termite prevention, Sections R3IS.LI through R3IS.16 do not apply. Application of the wood treatment termiticide shall be as required by label directions for use, and must be completed prior to final building approval.

R3182 Penetration. Protective sleeves around piping penetrating concrete slab-on-grade floors shall not be of cellulose-containing materials and, if soil treatment is used for subterranean termite protection, the sleeve shall have a maximum wall thickness of DDD inch (025 mm) and be sealed within the slab using non-corrosive clamping device to eliminate the arrular space between pipe and the sleeve. No termiticides shall be applied inside the sleeve.

R318.3 Cleaning. Cells and cavities in masonry units and air gaps between brick, stone or masonry veneers and the structure shall be cleaned of all non-preservative treated or non-naturally durable wood, or other cellulose-containing material prior to concrete

Exception: Inorganic material manufactured for closing cells in foundation concrete masonry unit construction or clean earth fill placed in concrete masonry unit voids below slab level before termite treatment is performed. R98A Concrete bearing ledge. Brick, stone or other veneer shall be supported by a concrete bearing ledge at least equal to the total thickness of the brick stone or other veneer which is poured integrally with the concrete foundation. No supplemental concrete foundation pours which will create a hidden cold joint shall be used without supplemental treatment in the foundation unless there is an approved physical barrier. An approved physical barrier shall also be installed from below the wall still plate or first block course horizontally to embed in a mortar joint. If masonry veneer extends below grade, a ternite protective treatment must be applied to the

cavity created between the veneer and the foundation, in lieu of a physical barrier.

Exception: Veneer supported by a structural member secured to the foundation sidewall in accordances with ACIB30/ASCE 5/THS 402, provided at least a 6 inch (ib2 mm) clear inspection space of the foundation sidewall exterior exist between the veneer and the top of any soil, sod, mulch or other organic landscaping component, deck, apron, porch, walk or any other work immediately

R3I85 Protection against decay and termites. Condensate lines, irrigation/sprinkler system risers for spray heads, and roof downspouts shall discharge at least 1 foot (305 mm) away from the structure sidewall, whether by underground piping, tall extensions or splash blocks. Gutters with downspouts are required on all buildings with eaves of less than 6 inches (IB2 mm) horizontal projection except for gable end rakes or on a roof above another roof. R386 Preparation of building site and removal of debris.

R318.6.1 All building sites shall be graded to provide drainage under all portions of the building not occupied by becoments. R318.6.2 The foundation and the area encompassed within 1 foot (305 mm) therein shall have all vegetation, stumps, dead roots, cardboard, trash and foreign material removed and the fill naterial shall be free of vegetation and foreign material. The fill shall be

R318.6.3. After all work is completed, loose wood and debris shall be completely removed from under the building and within 1 foot (305 mm) thereof. All wood forms and supports shall be completely removed. This includes, but is not limited to: wooden grade stakes, forms, contraction spacers, tub trap boxes, plumbing supports, bracing, shoring, forms or other cellulose-containing material placed in any location where such materials are not clearly visible and readily removable prior to completion of the work. Wood shall not be stored in contact with the ground under any building.

Set Common Set Common Set Common Set Common Cocking, face nail Set Common Cocking, face nail Set Common Common Cocking, face nail Set Set Common Cocking, face nail Set	Section Sect		YPICAL NAILING SCHEDU	
Security	portion, face nall professional parts to stud, defailed us to see plate to stud, defailed us of see plate, toe nail sed common 4. C.C. control plate, face nail publied stude, face nail sed common 44° C.C. control plates, face nail sed common 44° C.C. control plates, face sell sed common 44° C.C. control plates, face nail sed common 45° along each edge minimum shark dia. of 92929 Inch and shirtum shark cits. o	edger strip	léd comon	3 at each joist
pp of sole plate to stud, and natified common 2 and natified and to sole plate, toe natii 8d common 4 OC. 4 OC	p of sole plate to stud, disclaration and all selections on the common disclaration and all selections all selections are selections. 2 decreases and all selections are selections and all selections are se		IDOI COMBON	10 000
used to sole plates, toe nell sold common 4 outbled stude, face nell 8d common 24° OC. 18d common 16° along each edge on thouse header to 18d common 18d	displaced stude, face natii 8d common 4 cure to sole plate, toe natii 8d common 24° OC. subled stude, face natii 8d common 16° along each 16° along each 11° along each 11° along each 11° along each 12° OC. substanting or less to 12° OC. at cope and botton each 12° OC. at cope 12° OC.	COUNTY, TACE NAII		
used to sole plates, toe nell sold common 4 outbled stude, face nell 8d common 24° OC. 18d common 16° along each edge on thouse header to 18d common 18d	displaced stude, face natii 8d common 4 cure to sole plate, toe natii 8d common 24° OC. subled stude, face natii 8d common 16° along each 16° along each 11° along each 11° along each 11° along each 12° OC. substanting or less to 12° OC. at cope and botton each 12° OC. at cope 12° OC.	on of sole plate to stud	16cl common	
to do sole plate, toe nail outbied stude, face nail published stude, face nail published, face nail published face	ud to sole plate, toe nail subled stude, face nail subled stude, face nail subled stude, face nail subled stude, face nail subled top plates, face subled top plates, face subled top plates, face subled top plates, face subled common subled stude, face nail subled stude, face nail subled common dependent subled stude, face nail subled common dependent dep		PO CONNOT	1 4
coblect stude, face mall bild common 24" OC. cotabled top plates, face mall bild common is along each edge onthrous header to adult to mall and to bearing, face mall wer bild extending or less to ach bearing, face mall wer bild extending to ach bearing, face mall wer bild extending to ach bearing, face mall wer bild extending to ach bearing, face mall wild-up opener stude wild-up common 24" OC. at top and bottom and staggered 2 ends at each eptice at e	subled top plates, face nall bild common 24° OC. controlled top plates, face nall bild common 16° along each 11° active part of the plates, face nall 18° along each 18° al			
Second common Second commo	Section Sect	wa to sole plate, toe hall		
and to entition the edge of th	minutus header to adjusted to adjust the netting of less to adjusted the parting of less to adjusted the parting face nation and the parting face nation and parting and parting face nation and parting and parting face nation and parting face nation and parting and parti	CUCINCI BUICO, FACE RAIL		
ontinuous header to ud, toe natility of less to add to enting or less to ach bearing, face natility or less than thing to ach bearing, face natility of three members and lease up to three members are less than the less than	minimus header to adjoes and adjoes to adjoes and an adjoes and adjoes and an adjoes and		MPCI COMMON	
Set common 2 Set common 2 Set common 2 Set common 3 Set common 32 Set Common	and toe nettile of lease to combon to bearing, face natil sold common to bearing, face natil side of bearing side of beari			
8 sheathing or less to ach bearing, face nall very D8 sheathing to ach bearing, face nall searing, face nall wild-up comer stude wild-up comer stude wild-up griders and same up to three members seams	8 sheathing or less to chibearing, face natil chibearing, face natil ser D8 sheathing to chibearing, face natil side common 3 com		8d common	3
ach bearing, face natil ver DG sheathing to ach bearing, face natil uild-up griders and 20 common 24° CC. uild-up griders and and bottom and staggared 2 ends at each splice 1 ga -1/2"	ch bearing, face natil ach pearing, face natil ach pearing, face natil allot-up corner stude allot-up griders and allot-up and bottom and staggered 2 ends at each applica at outer bearing and bottom and staggered 2 ends at each applica and and shimman sheark cla, of epossy inch and shimman sheard intermediate supports and bottom edges and shimman sheark cla, of epossy inch and shimman sheark cla, of epossy inch and ellered and ellered and ellered and eller			
According to ach bearing, face nall wild-up common and betaring, face nall wild-up common and bottom and action and bottom and bottom and ease up to three members are seen up to three bearing are seen are see	Act Does heathing to chibearing, face natilities and better bearing. B' Gupsum Sheathing Ii ga 1-1/2" 1-3/8" head B' Gupsum Sheathing Ii ga 1-3/4" 1-3/8" head B' Gupsum Sheathing Ii ga 1-3/4" 1-3/8" chymall natil 1-3/8" c		8d comnon	2
ach bearing, face natii uild-up corner stude uild-up griders and and botton and staggared 2 ends at each splice I ga -1/2"	ch bearing, face nall all process and side common 24" O.C. at top and bottom and staggered 2 ends at each explice and staggered 2 ends at each explice and staggered 2 ends at each explice at each explication and staggered 2 ends at each each each explication and staggered 2 ends at each each each each each explicat			
Section Sect	Idd-up corner stude Idd-up griders and 20' CC. at top and bottom and staggered? ends at each epilice I'06' head 8' CC. at other bearing I'16' head		8d common	3
Section Sect	Idd-up corner stude Idd-up griders and 20' CC. at top and bottom and staggered? ends at each epilice I'06' head 8' CC. at other bearing I'16' head			<u>'</u>
20d common 32 ° O.C. at top and bottom and stagggred 2 ends at each splice 2° Gypoum Sheathing 1° Gypoum Wallboard 1° O.C. at other bearing 1	20d common 32° O.C. at top and bottom and etaggered 2 ends at each splice "Gypeum Sheathing II ga I-1/2" 4° O.C. at edges 8° o.c. at other bearing 11 ga I-3/4" 4° O.C. at edges 8° o.c. at other bearing 12° head 12° head 12° head 12° head 12° o.c. at other bearing 12° head 12° he	uild-up comer studs	libd common	24" O.C.
and bottom and staggared 2 ands at each epitice 2º Gypsum Sheathing Ii ga I-1/2º 4ºC.C. at edges 8º o.c. at other bearing 1 ga I-3/4º 4ºC.C. at edges 1 //6º head 8º o.c. at other bearing 1 ga I-3/4º 4ºC.C. at edges 1 o.c. at other bearing 1 ga I-3/4º 4ºC.C. at edges 1 o.c. at other bearing 1 ga I-3/4º 4ºC.C. at edges 1 o.c. at other bearing 1 co.c. on callings 8ºC.C. on mails 1 o.c. at other bearing 1 o.c. at	and bottom and etaggered 2 ends at each eplice "Gypeum Sheathing II ga I-1/2" 4°D.C. at edges 8° o.c. at other bearing II ga I-3/4" 4°D.C. at edges 8° o.c. at other bearing II ga I-3/4" 4°D.C. at edges 8° o.c. at other bearing II ga I-3/4" 4°D.C. on ceilings 8°D.C. on mails peum Wallboard I/2" I-3/8" drywall nati T°D.C. on ceilings 8°D.C. on walls 5/8" I-1/2" drywall nati T°D.C. on ceilings 8°D.C. on walls roboard Lap Siding, 8d corrosion resistant with minimum shark data. of 0.09990 inch and minimum head data. of 0.09990 inch and minimum head data. of 0.09990 inch and minimum head data. of 0.00990 inch and minimum head and minimum head intermediate supports	uild-up griders and	20d common	32" OC. at 100
staggered 2 ands at each epilice 2º Gypsum Sheathing II ga I-1/2º 4ºOC at edges 1/6º head 8º oc at other bearing II ga I-3/4º 4ºOC at edges 1/6º head 8º oc at other bearing 1/6º head 8º oc at other bearing 1/6º head 8º oc at other bearing 1/6º head 1/0° oc at other bearing 1/6º head 1/0° oc at other bearing 1/6º head 1/0° oc at other bearing 1/0° oc at top 1/0° oc at top 1/0° oc at top 1/0° oc at other bearing 1/0° oc at top 1/0° oc at other bearing 1/0° oc at top 1/0° oc at other bearing 1/	etaggered 2 ends at each epilics "Gypeum Sheathing II ga I-1/2" 4°D.C. at edges 7/6" head 8° o.c. at other bearing 8° o.c. at other bearing 7/6" head 8° o.c. at other bearing 8° o.c. at other bearing 8° o.c. on ceilings 8° o.c. on mails 7° o.c. on ceilings 8° o.c. on mails 9° o.c. on mails 8° o.c. on mails 8° o.c. on mails 9° o.c. on mails			
at each spilice 2" Gypeum Sheathing II ga I-1/2" 4"O.C. at edges 1" 1/6" head 8" o.c. at other bearing II ga I-3/4" 4"O.C. at edges 2" c.c. at other bearing II ga I-3/4" 4"O.C. at edges 2" c.c. at other bearing II ga I-3/6" head 8" o.c. at other bearing II ga I-3/6" head 8" o.c. at other bearing II o.c. on ceilings 8" O.C. on mails II-0.C. on ceilings 8" O.C. on mails II-0.C. on ceilings 8" O.C. on mails II-0.C. on ceilings 8" O.C. at top and bottom edges III of 0.0999 inch and minimum head clia. of 0.240 inch III of 0.0999 inch and minimum head clia. of 0.2999 inch and minimum head clia. of 0.2999 inch and minimum head clia. of 0.2990 inch and minimum head clia. of 0.240 inch III o.C. at edges III of 0.0990 inch and minimum head clia. of 0.0990 inch and bottom edges III o.C. at edges	at each epilice "Gypeum Sheathing II ga I-1/2" 4"O.C. at edges "T/6" head 8" o.c. at other bearing II ga I-3/4" 4"O.C. at edges "O.C. at edges "O.C. at other bearing Pum Wallboard I/2" I-3/8" drymall nati ITO.C. on ceilings 8"O.C. on maile I-1/2" drymall nati ITO.C. on ceilings 8"O.C. on maile I-1/2" drymall nati ITO.C. on ceilings 8"O.C. on maile I-1/2" drymall nati ITO.C. on ceilings 8"O.C. on maile II of O.C. at top and bottom edges II of O.C. at top and bottom edges II of O.C. at top and bottom edges III of O.C. at e	T	· ·	
Suppose the string II ga I-1/2" 4"O.C. at edges 1/6" head 8" o.c. at other bearing II ga I-3/4" 4"O.C. at edges 1/6" head 8" o.c. at other bearing 1 ga I-3/4" 4"O.C. at edges 1/6" head 8" o.c. at other bearing 1-3/6" crystall nati 1"O.C. on ceilings 8"O.C. on stalls 1-1/2" crystall nati 1"O.C. on ceilings 8"O.C. on stalls 1-1/2" crystall nati 1"O.C. on ceilings 8"O.C. on stalls 1-1/2" crystall nati 1"O.C. on ceilings 8"O.C. on stalls 1-1/2" crystall nati 1"O.C. on ceilings 8"O.C. on stalls 1-1/2" crystall nati 1"O.C. on ceilings 8"O.C. on stalls 1-1/2" crystall nati 1-1/2" crystall nati 1"O.C. on ceilings 8"O.C. on stalls 1-1/2" crystall nati 1-1/2" cry	# Gypsum Sheathing II ga I-1/2" 4*O.C. at edges 5* Gypsum Sheathing II ga I-3/4" 4*O.C. at edges 7/6" head 8* o.c. at other bearing 10 ga I-3/4" 4*O.C. at edges 7/6" head 8* o.c. at other bearing 1-3/8" chywall nail 7*O.C. on ceilings 8*O.C. on walls 7*O.C. on ceilings 8*O.C. on walls 7*O.C. on ceilings 8*O.C. on walls 7*O.C. on wal		· ·	
I ga -1/2" 4"O.C. at edges 8" o.c. at other bearing II ga -3/4" 4"O.C. at edges 7/6" head 8" o.c. at other bearing 1 ga -3/4" 4"O.C. at edges 7/6" head 8" o.c. at other bearing 1-3/8" drymall nati 1"O.C. on ceilings 8"O.C. on mails 1-1/2" drymall nati 1"O.C. on ceilings 8"O.C. on mails 8"O.C. on mails 1-1/2" drymall nati 1"O.C. on ceilings 8"O.C. on mails 1-1/2" drymall nati 1"O.C. on ceilings 8"O.C. on mails 1-1/2" drymall nati 1"O.C. on ceilings 8"O.C. on mails 1-1/2" drymall nati 1"O.C. on ceilings 8"O.C. on mails 1-1/2" drymall nati 1"O.C. on ceilings 8"O.C. on mails 1-1/2" drymall nati 1-1/2" drymall nati 1"O.C. on ceilings 8"O.C. on mails 1-1/2" drymall nati 1-1/2" drymall n	Gypeum Sheathing Il ga I-1/2" 4"OC. at edges 8" oc. at other bearing 1 Il ga I-3/4" 4"OC. at edges 17/6" head 8" oc. at other bearing 17/6" head 1-3/8" drymail nati 1"OC. on ceilings 8"OC. on mails 10" oc. on ceilings 8"OC. on mails 16" oc. at top 10" oc. on ceilings 10" oc. on ceilings 10" oc. on mails 10" oc. on ceilings 10" oc. on mails 10" oc. on ceilings 10" oc. on mails 10" oc. on ceilings 10" oc. on mails 10" oc. on ceilings 10" oc. on mails 10" oc. on ceilings 10" oc. on mails 10" oc. on ceilings 10" oc. o			
1/16" head 8" o.c. at other bearing 11 ga 1-3/4" 4" O.c. at edges 2" o.c. at other bearing 1/6" head 8" o.c. at other bearing 1/6" head 8" o.c. at other bearing 1/2" 1-3/8" drywall nail 7" O.C. on ceilings 8" O.C. on walls 1-1/2" drywall nail 7" O.C. on ceilings 8" O.C. on walls 1-1/2" drywall nail 7" O.C. on ceilings 8" O.C. on walls 1-1/2" drywall nail 10 O.C. at top and bottom edges 16" O.C. at top wer sheathing 16" O.C. at top with minimum shark 16" O.C. at top with minimum shark 16" O.C. at top with minimum head 16" O.C. at top with minimum head 16" O.C. at edges 17" O.C. at edges 17" O.C. at edges 17" O.C. at edges 18"	1/16" head 8" o.c. at other bearing 11 ga 3-3/4" 4"O.C. at edges 7/16" head 8" o.c. at other bearing 1-3/8" drywall nati 1"O.C. on ceilings 8"O.C. on walls 1"O.C. on ceilings 1"O.C. on ceilings 8"O.C. on walls 1"O.C. on ceilings 1"O.C. on ceilings 1"O.C. on ceilings 1"O.C. on ceilings 8"O.C. on walls 1"O.C. on ceilings 1"O.C. on ceiling	2º Gunum Sheething	11 00 1-10"	
### Bidding ### A Poc. at edges ## Oc. at other bearing ### A Poc. at edges ## Oc. at other bearing ### A Poc. on callings ## Oc. on mails ###	1 ga 1-3/4" 4"OC. at edges 2" oc. at other bearing 1 ga 1-3/4" 1-3/8" drywall nati 1"OC. on ceilings 8"OC. on walls 8"OC. at top with minimum shark 16" OC. at top 10" of 240 inch 10" o	- Area contain		
1-3/8" chywall nati 10.0. on ceilings 8'0.0. on walls 1-3/8" chywall nati 10.0. on ceilings 8'0.0. on walls 1-1/2" chywall nati 10.0. on ceilings 8'0.0. on walls 1-1/2" chywall nati 10.0. on ceilings 8'0.0. on walls 1-1/2" chywall nati 10.0. on ceilings 8'0.0. on walls 1-1/2" chywall nati 10.0. on ceilings 8'0.0. on walls 1-1/2" chywall nati 10.0. on ceilings 8'0.0. on walls 1-1/2" chywall nati 10.0. on ceilings 8'0.0. on walls 1-1/2" chywall nati 10.0. on ceilings 8'0.0. on walls 1-1/2" chywall nati 10.0. on ceilings 8'0.0. on walls 1-1/2" chywall nati 10.0. on ceilings 8'0.0. on walls 1-1/2" chywall nati 10.0. on ceilings 8'0.0. on walls 1-1/0.0. on ceilin	T/6" head 1-3/8" drywall nati 1-3/8" drywall nati 1-3/8" drywall nati 1-3/8" drywall nati 1-0C. on ceilings 8"OC. on walls 1-1/2" drywall nati 1"OC. on ceilings 8"OC. on walls 1-1/2" drywall nati 1"OC. on ceilings 8"OC. on walls 1"OC. on ceilings 8"OC. on walls 16" OC. at top and bottom edges 16" OC. at edges 17" OC. at edges 17" OC. at edges 18" OC. at edges	101 Cutoum Glossibles		
i-3/8" drywall nail T*O.C. on cellings 8"O.C. on walls I-1/2" drywall nail T*O.C. on cellings 8"O.C. on walls I*O.C. on cellings I*O.C. on walls I*O.C. o	peum Wallboard 1/2" 1-3/8" drywall nati 1-1/2" d	o album ammund		
1-3/8" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. at top and botton edges 10" O.C. at edges 12" O.C. at intermediate supports 1-1/2" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. on callings 8"O.C. on walls 1-1/2" drywall nati 1"O.C. at edges 12" O.C. at edges 12" O.C. at edges 12" O.C. at intermediate supports	i-3/8" drywall nati 10.C. on ceilings 8"O.C. on walls b/8" i-1/2" drywall nati 10.C. on ceilings 8"O.C. on walls raboard Lap 6iding, rect to 8tude 20.C. on walls and bottom edges is corrosion resistant with minimum sharik dia. of 0.240 inch and minimum head dia. of 0.240 inch raboard Lap 6iding, we sheathing 20.C. at top and bottom edges is docrrosion resistant with minimum sharik dia. of 0.240 inch and minimum head dia. of 0.240 inch and minimum sharik dia. of 0.240 inch and minimum sharik dia. of 0.220 inch and minimum head dia. of 0.225 inch raboard Panel siding, were to 8tude 20.C. at edges raboard Panel siding, were to 8tude 21. O.C. at edges aupports 8d corrosion resistant intermediate aupports 8d corrosion resistant 21. O.C. at edges aupports 10.C. at edges 21. O.C. at edges 22. O.C. at edges 22. O.C. at intermediate aupports raboard Panel siding, were to 8theathing 21. O.C. at intermediate aupports		1/16- nead	8" o.c. at other bearing.
8°O.C. on mails 1-1/2" drymail nail 1°O.C. on ceilings 8°O.C. on mails 1°O.C. at top and bottom edges 1°O.C. at edges	8°OC. on walls 1-1/2" drywall nati 1°OC. on ceilings 8°OC. on walls 1°OC. at top and bottom edges 1°OC. at top and bottom edges 1°OC. at top and bottom edges 1°OC. at edges 1		1000	
I-I/2" drywall nail T*OC. on ceilings 8°OC. on walls 8°OC. on walls 8°OC. on walls 9°OC. on walls 9°OC. on walls 9°OC. on walls 9°OC. at top with minimum shank dia. of 00990 inch and minimum head dia. of 00990 inch 9000 inch 90000 inch 9000 inch	1-1/2" drywall nail TOC. on ceilings 8"OC. on walls rect to Stude Sel corrosion resistant with minimum shark dia. of 00090 inch and minimum shark dia. of 00090 inch and minimum shark dia. of 00090 inch and minimum shark dia. of 00000 inch and minimum shark dia. of 000000 inch and minimum shark dia. of 0000000 inch and minimum shark dia. of 0000000 inch and minimum shark dia. of 0000000 inch and minimum shark dia. of 00000000000000000000000000000000000	V2-	1-3/8" cirywall nail	
8"OC. on walls andboard Lap Siding, Bet corrosion resistant With minimum shark dia. of 02990 inch and minimum head dia. of 0240 inch Broboard Lap Siding, Wer sheathing Bet corrosion resistant With minimum shark dia. of 02900 inch and minimum head dia. of 0240 inch Broboard Panel siding, Bet corrosion resistant With minimum shark dia. of 0240 inch Broboard Panel siding, Bet corrosion resistant With minimum shark dia. of 02920 inch and minimum head dia. of 02920 inch Broboard Panel siding, Bet corrosion resistant With minimum shark dia. of 02920 inch Broboard Panel siding, Wer to Sheathing Bet corrosion resistant With minimum shark dia. of 02920 inch Broboard Panel siding, Wer to Sheathing Bet corrosion resistant With minimum shark dia. of 02920 inch Broboard Panel siding, Wer to Sheathing Bet corrosion resistant With minimum shark dia. of 02920 inch Broboard Panel siding, Wer to Sheathing Bet corrosion resistant With minimum shark dia. of 02920 inch Bet corrosion resistant Bet OC. at edges With minimum shark dia. of 02920 inch Bet occurred inch Be	### Strain ### S			8"O.C. on malls
8"OC. on walls andboard Lap Siding, Bet corrosion resistant With minimum shark dia. of 02990 inch and minimum head dia. of 0240 inch Broboard Lap Siding, Wer sheathing Bet corrosion resistant With minimum shark dia. of 02900 inch and minimum head dia. of 0240 inch Broboard Panel siding, Bet corrosion resistant With minimum shark dia. of 0240 inch Broboard Panel siding, Bet corrosion resistant With minimum shark dia. of 02920 inch and minimum head dia. of 02920 inch Broboard Panel siding, Bet corrosion resistant With minimum shark dia. of 02920 inch Broboard Panel siding, Wer to Sheathing Bet corrosion resistant With minimum shark dia. of 02920 inch Broboard Panel siding, Wer to Sheathing Bet corrosion resistant With minimum shark dia. of 02920 inch Broboard Panel siding, Wer to Sheathing Bet corrosion resistant With minimum shark dia. of 02920 inch Broboard Panel siding, Wer to Sheathing Bet corrosion resistant With minimum shark dia. of 02920 inch Bet corrosion resistant Bet OC. at edges With minimum shark dia. of 02920 inch Bet occurred inch Be	### Strain ### S			
8"OC. on walls andboard Lap Siding, Bet corrosion resistant With minimum shark dia. of 02990 inch and minimum head dia. of 0240 inch Broboard Lap Siding, Wer sheathing Bet corrosion resistant With minimum shark dia. of 02900 inch and minimum head dia. of 0240 inch Broboard Panel siding, Bet corrosion resistant With minimum shark dia. of 0240 inch Broboard Panel siding, Bet corrosion resistant With minimum shark dia. of 02920 inch and minimum head dia. of 02920 inch Broboard Panel siding, Bet corrosion resistant With minimum shark dia. of 02920 inch Broboard Panel siding, Wer to Sheathing Bet corrosion resistant With minimum shark dia. of 02920 inch Broboard Panel siding, Wer to Sheathing Bet corrosion resistant With minimum shark dia. of 02920 inch Broboard Panel siding, Wer to Sheathing Bet corrosion resistant With minimum shark dia. of 02920 inch Broboard Panel siding, Wer to Sheathing Bet corrosion resistant With minimum shark dia. of 02920 inch Bet corrosion resistant Bet OC. at edges With minimum shark dia. of 02920 inch Bet occurred inch Be	### Strain ### S	5/8"	1-1/2" cirywall nail	TOC. on ceilings
with minimum sharik dia. of 00990 inch and minimum head dia. of 0240 inch and bottom edges life oc. at top wer sheathing life corrosion resistant with minimum sharik dia. of 00990 inch and minimum head dia. of 00990 inch and minimum sharik dia. of 00900 inch and minimum sharik dia. of 00000 inch and minimum sharik dia. of 00000 inch and minimum sharik dia. of 00000 inch and minimum head dia. of 00000 inch and minimum sharik dia. of 000000 inch and bottom edges descriptions descripti	with minimum sharik dia. of 00990 inch and minimum head dia. of 0240 inch redboard Lap Siding, were sheathing IDE corrector resistant with minimum sharik dia. of 0240 inch and minimum sharik dia. of 0240 inch redboard Panel eiding, sect to Studie IDE OC. at top and bottom edges IDE OC. at top and bottom edges IDE OC. at edges IDE OC. at edges IDE OC. at edges IDE OC. at intermediate and minimum head dia. of 0220 inch and minimum sharik dia. of 0225 inch IDE OC. at edges			8"O.C. on walls
with minimum sharik dia. of 00990 inch and minimum head dia. of 0240 inch and bottom edges life oc. at top wer sheathing life corrosion resistant with minimum sharik dia. of 00990 inch and minimum head dia. of 00990 inch and minimum sharik dia. of 00900 inch and minimum sharik dia. of 00000 inch and minimum sharik dia. of 00000 inch and minimum sharik dia. of 00000 inch and minimum head dia. of 00000 inch and minimum sharik dia. of 000000 inch and bottom edges descriptions descripti	with minimum sharik dia. of 00990 inch and minimum head dia. of 0240 inch redboard Lap Siding, were sheathing IDE corrector resistant with minimum sharik dia. of 0240 inch and minimum sharik dia. of 0240 inch redboard Panel eiding, sect to Studie IDE OC. at top and bottom edges IDE OC. at top and bottom edges IDE OC. at edges IDE OC. at edges IDE OC. at edges IDE OC. at intermediate and minimum head dia. of 0220 inch and minimum sharik dia. of 0225 inch IDE OC. at edges	ardboard Lap Biding,	8d corrosion resistant	16" O.C. at top
dia. of 00990 inch and minimum head dia. of 0240 inch ardboard Lap Siding, wer sheathing iiiiiiiiiiiiiiiiiiiiiiiiiiiiiiiiii	dia. of 00990 inch and minimum head dia. of 0240 inch relocated Lap Siding, with minimum sharik dia. of 02990 inch and minimum head dia. of 0240 inch relocated Panel siding, rect to Studie dia. of 02900 inch and minimum sharik dia. of 02000 inch and minimum sharik dia. of 02000 inch and minimum sharik dia. of 02900 inch and minimum sharik and minimum sharik dia. of 02900 inch and minimum sharik	irect to Stude	with minimum shank	
and minimum head dia. of 0240 inch ardboard Lap Siding, wer sheathing ibd corrosion resistant with minimum shark dia. of 02990 inch and minimum head dia. of 0240 inch ardboard Panel siding, irect to Studis ardboard minimum shark dia. of 02920 inch and minimum shark dia. of 02920 inch and minimum shark dia. of 02920 inch and minimum head dia. of 02920 inch and minimum shark dia. of 02920 inch ardboard Panel siding, wer to Sheathing ard corrosion resistant be of oc. at edges uith minimum shark dia. of 02920 inch lintermediate and minimum shark dia. of 02920 inch and bottom edges dia. of 02920 inch and minimum shark dia. of 02920 inch and minimum shark dia. of 02920 inch and dia. of 02920 inch	and minimum head dia. of 0240 inch 10d corrosion resistant with minimum shark dia. of 02990 inch and minimum head dia. of 0240 inch and minimum shark dia. of 0240 inch and minimum shark dia. of 0290 inch and minimum shark dia. of 02920 inch and minimum shark and minimum shark dia. of 02920 inch and minimum shark		dia. of 00990 inch	1
dia. of @24@ inch ardiocard Lap Siding, wer sheathing	dia. of @24@ inch Idd corrosion resistant with minimum shark dia. of @299@ inch and minimum shark dia. of @24@ inch and minimum shark dia. of @24@ inch and minimum shark dia. of @24@ inch and minimum shark dia. of @292@ inch and minimum shark dia. of @22@ inch and minimum shark dia. of @22% inch Intermediate aupports Id Corrosion resistant supports			
indipoard Lap Siding, wer sheathing iiiii corrosion resistant with minimum shark cita. of \$29990 inch and bottom edges dia. of \$240 inch inct to Studis iiiiiiiiiiiiiiiiiiiiiiiiiiiiiiiiii	rdboard Lap Siding, er sheathing Indicated Corrosion resistant Indicated Corrosion resis			·
wer sheathing with minimum sharik dia. of 00090 inch and minimum head dia. of 00000 inch and minimum head dia. of 00000 inch and minimum sharik intermediate and minimum sharik intermediate and minimum head dia. of 00000 inch and minimum sharik intermediate supports inch and minimum sharik intermediate supports	with minimum sharik dia. of 00990 inch and minimum head dia. of 00990 inch rect to 8tude 6" O.C. at edges with minimum sharik 12" O.C. at dia. of 00920 inch intermediate supports rect to 8tude 8 d corrosion resistant 2" O.C. at intermediate supports rectooard Panel siding, 8 d corrosion resistant with minimum sharik 12" O.C. at edges with minimum sharik 12" O.C. at edges 12" O.C. at dia. of 00920 inch intermediate supports		THE CLEAN THE REAL	1
wer sheathing with minimum sharik dia. of 00990 inch and minimum head dia. of 0040 inch archoard Panel siding, frect to Stude with minimum sharik dia. of 00920 inch and minimum head dia. of 00920 inch archoard Panel siding, archoard Panel siding, wer to Sheathing Sd corrosion resistant with minimum sharik dia. of 00920 inch archoard Panel siding, wer to Sheathing with minimum sharik dia. of 00920 inch and minimum head supports	with minimum sharik dia. of 00990 inch and minimum head dia. of 00990 inch rect to 8tude 6" O.C. at edges with minimum sharik 12" O.C. at dia. of 00920 inch intermediate supports rect to 8tude 8 d corrosion resistant 2" O.C. at intermediate supports rectooard Panel siding, 8 d corrosion resistant with minimum sharik 12" O.C. at edges with minimum sharik 12" O.C. at edges 12" O.C. at dia. of 00920 inch intermediate supports	ardooard Lap Siding	10d corresion resistant	I6" OC # top
dia. of 00990 inch and minimum head dia. of 0240 inch archoard Panel siding, frect to Stude 6" OC. at edges with minimum shark dia. of 00920 inch and minimum head dia. of 00225 inch archoard Panel siding, wer to Sheathing 8d corrosion resistant with minimum shark dia. of 00225 inch 2" OC. at edges wer to Sheathing 6" OC. at edges linth minimum shark dia. of 00020 inch and minimum head supports	dia. of 00990 inch and minimum head dia. of 0240 inch rect to 8tude 6" O.C. at edges with minimum shank 12" O.C. at dia. of 00920 inch and minimum head dia. of 00225 inch rect to 8heathing 8d corresion resistant with minimum shank 12" O.C. at intermediate supports 6" O.C. at edges 12" O.C. at dia. of 00220 inch with minimum shank 12" O.C. at dia. of 00020 inch and minimum head supports			
and minimum head dia. of 0240 inch archoard Panel eiding, irect to Stude 6° O.C. at edges uith minimum shark dia. of 02920 inch and minimum head dia. of 0225 inch archoard Panel eiding, ver to Sheathing 8d corrosion resistant uith minimum shark dia. of 0225 inch 8d corrosion resistant uith minimum shark dia. of 02920 inch and minimum head eupports	and minimum head dia. of 0240 inch and minimum head dia. of 0240 inch and corrosion resistant dia. of 00220 inch and minimum head dia. of 00225 inch and minimum head dia. of 00225 inch and minimum head dia. of 00225 inch and minimum head dia. of 00220 inch and minimum head dia. of 00220 inch and minimum head dia. of 00220 inch and minimum head supports	Am albanud		and cottom adder
dia. of 0240 inch ardboard Panel siding, irect to Studie bd corrosion resistant with minimum shank dia. of 0020 inch and minimum head dia. of 0225 inch ardboard Panel siding, wer to Sheathing bd corrosion resistant with minimum shank dia. of 00220 inch with minimum shank dia. of 00220 inch and minimum head supports	dia. of \$240 inch rdboard Panel eiding, sect to Stude bd corrosion resistant with minimum shank dia. of \$2920 inch and minimum head dia. of \$225 inch rdboard Panel eiding, ser to Sheathing bd corrosion resistant with minimum shank dia. of \$225 inch corrosion resistant with minimum shank dia. of \$220 inch and minimum head supports			
ardboard Panel siding, irect to Stude 6" O.C. at edges with minimum shank dia. of 0.0920 inch and minimum head dia. of 0.225 inch ardboard Panel siding, wer to Sheathing 8d corrosion resistant with minimum shank dia. of 0.0920 inch lintermediate and minimum shank dia. of 0.0920 inch and minimum head eupports	rdboard Panel siding, sect to Stude ### Control on resistant ### Contr			
with minimum shank dia. of 00020 inch and minimum head dia. of 00220 inch and minimum head dia. of 00225 inch ardboard Panel siding, wer to Sheathing Bd corrosion resistant with minimum shank dia. of 00020 inch and minimum head and minimum head 12" OC. at intermediate and minimum head	with minimum shank dia. of 0020 inch and minimum head dia. of 0225 inch redboard Panel siding, ret to Sheathing Bel corresion resistant with minimum shank dia. of 0020 inch and minimum head supports Bel corresion resistant with minimum shank and minimum head Bel corresion resistant supports Bel corresion resistant supports Bel corresion resistant supports Bel corresion resistant supports		dia. of 102410 inch	1
with minimum shank dia. of 00020 inch and minimum head dia. of 00220 inch and minimum head dia. of 00225 inch ardboard Panel siding, wer to Sheathing Bd corrosion resistant with minimum shank dia. of 00020 inch and minimum head and minimum head 12" OC. at intermediate and minimum head	with minimum shank dia. of 0020 inch and minimum head dia. of 0225 inch redboard Panel siding, ret to Sheathing Bel corresion resistant with minimum shank dia. of 0020 inch and minimum head supports Bel corresion resistant with minimum shank and minimum head Bel corresion resistant supports Bel corresion resistant supports Bel corresion resistant supports Bel corresion resistant supports			
dia. of 00920 inch and minimum head dia. of 0225 inch irdboard Panel siding, wer to Sheathing dia. of 00920 inch with minimum shank dia. of 00920 inch and minimum head exports	dia. of 00920 inch and minimum head dia. of 0225 inch rdboard Panel siding, ser to Sheathing with minimum shank dia. of 00920 inch and minimum head supports	_		
and minimum head dia. of 0225 inch ardboard Panel siding, ver to Sheathing with minimum shank dia. of 00220 inch and minimum head and minimum head and minimum head and minimum head	and minimum head dia. of 0225 inch and minimum head dia. of 0225 inch and correction restetant and minimum sharik dia. of 00220 inch and minimum head and minimum head and minimum head and minimum head and minimum head	irect to Stude	with minimum shank	12" O.C. at
and minimum head dia. of 0225 inch ardboard Panel siding, ver to Sheathing with minimum shank dia. of 00220 inch and minimum head supports	and minimum head dia. of 0225 inch and board Panel siding, but corresion resistant with minimum shank dia. of 00220 inch and minimum head supports			internecliate
dia. of @225 inch ardboard Panel siding, ver to Sheathing with minimum sharik dia. of @226 inch and minimum head dia. of @225 inch intermediate supports	dia. of @225 inch rdboard Panel siding, ser to Sheathing with minimum shark dia. of @220 inch and minimum head dia. of @225 inch supports		and minimum head	
ver to Sheathing with minimum shank 12" O.C. at dia. of 0.0920 inch intermediate and minimum head supports	ver to Sheathing with minimum shank 12° O.C. at dia. of 0.0920 inch intermediate and minimum head supports		dia. of @225 inch	
ver to Sheathing with minimum shank 12" O.C. at dia. of 0.0920 inch intermediate and minimum head supports	ver to Sheathing with minimum shank 12° O.C. at dia. of 0.0920 inch intermediate and minimum head supports			
ver to Sheathing with minimum shank 12° O.C. at dia. of 0.0920 inch intermediate and minimum head supports	ver to Sheathing with minimum shank 12° O.C. at dia. of 0.0920 inch intermediate and minimum head supports	irdboard Panel siding.	8d corrosion resistant	6" OC at edges
dia. of 0.0920 inch intermediate and minimum head supports	dia. of 0.0920 inch intermediate and minimum head supports			
and minimum head supports	and minimum head supports			
	GIB. 01 9225 NOT			supports .


ALL MANUFACTURED PRODUCTS SUCH AS ROOFING, WINDOWS, DOORS, ETC. ARE SHOWN HEREIN FOR ILLUSTRATION PURPOSES ONLY. THE INFORMATION SHOWN IS THE RESPONSIBILITY OF THE MANUFACTURER. THE MANUFACTURER IS RESPONSIBLE FOR THE VALIDITY OF THE COMPONENTS PROVIDED. ATTACHMENT INFORMATION GIVEN BY THE MANUFACTURER IS PROVIDED HEREIN. CONTRACTOR AS PROJECT COORDINATOR, SHALL BE RESPONSIBLE FOR INSURING THAT THE APPROPRIATE PRODUCT/COMPONENT IS USED AND THAT IT HAS BEEN INSTALLED PER MANUFACTURER'S SPECIFICATIONS SUCH THAT IT WILL WITHSTAND THE COMPONENTS AND CLADDING PRESSURES REQUIRED BY THE SEALED PLANS.

PRE-CAST AND PRE-STRESSED CONCRETE COMPONENTS SHALL BE USED. AND INSTALLED PER MANUFACTURER'S SPECIFICATIONS. PRE-CAST LINTELS HAVE BEEN REVIEWED AND PLACED BASED ON DESIGN ALLOWABLE LOAD NFORMATION PROVIDED BY CAST CRETE. THEREFORE, CAST CRETE IS A DELEGATED ENGINEER FOR THIS PROJECT. ENGINEER OF RECORD MUST APPROVE IN WRITING ANY CHANGE IN LINTEL MANUFACTURER. ALL OTHER STRUCTURAL PRE-CAST COMPONENT MANUFACTURERS MUST SUBMIT DESIGN LOAD INFORMATION TO ENGINEER OF RECORD FOR APPROVAL. ENGINEER OF RECORD RESERVES THE RIGHT TO MAKE ANY CHANGES AFTER SUCH INFORMATION HAS BEEN PROVIDED FOR REVIEW. CONTRACTOR, AS PROJECT COORDINATOR, SHALL BE RESPONSIBLE FOR INSURING INFORMATION REQUESTED ABOVE HAS BEEN SUBMITTED TO ENGINEER OF RECORD IN A TIMELY MANNER WHEN


UPON REVIEW, ENGINEER OF RECORD WILL PROVIDE A REVIEW LETTER INDICATING ANY CHANGE IN STRAPPING OR SUPPORT BASED ON THAT REVIEW CONSTRUCTION COMMENCING PRIOR TO ENGINEER'S REVIEW IS SUBJECT TO MODIFICATION BASED ON REVIEW LETTER.

CEMENTITIOUS FINISH OVER FRAME TO BE A MINIMUM 1/8" IN THICKNESS CEMENTITIOUS FINISH OVER CMU TO BE A TINIMUM 5/8" IN THICKNESS TO MEET ASTM C926

CONNEC	TOR PRODUCT APPRO	VALS
APPLICATION	SIMPSON CONNECTOR	FL APPROVAL No.
CAPS AND BASES	CC, ECC, PC, EPC	FL 10860
CAPS AND BASES	ABU	FL 10849
	HU, HUC	FL 10655
	HGT, MBHA	FL 10866
	HD, HDQB, HHDQ	FL 10441
CONCRETE / MASONRY CONNECTORS	DETAL, FGTR, HETA, HHETA, HM, HTSM, HGAM, HGUM, LGUM, LTA, META, MSTAM, MSTCM, MTSM	FL 11473
	HGAIO, LGT, MGT, MSTC, VGT	FL 11470
	нтт, Стт	FL 11496
	LRU, LSGU, LSU, THA	FL 10447
	HHUS, HSUL., HSUR, HU, HUC, IUS,IUT, LU, LUS, MU,SUL, SUR, U	FL 10531 / FL 10655
HANGERS	HEU, HEUQ, HEUS, HHEU, HHUS, HUCQ, HUS, LCU, LUS, MEU, MSCPT, THA, THEB, THEQ, THEW, THJU	FL 10531 / FL 11468
	B, BA, HB, LBV	FL 10667
	EG, GB, GLS, GLST, GLT, GLTV, HGB, HGLS, HGLT, HGLTV, HHB, HHBD, HIT, HW, HWI, HWU, ITS,ITT, MEG, MIT, MSC, W, WI, WNP, WNPU, WP, WPI, WPU,	FL 10661
	A, FC, 6A, H, H6A, HH, L, L5, LPT, Z	FL 10446
STRAPS AND TIES	DSP, FTA, H, HGT, HTS, LFTA, LTS, MTS, RSP, RST, SP, SPH, SSP	FL 10456
	CMST, CS, FHA, HST, LSTA, LSTI, MST, MSTA, MSTC, MSTI, ST	FL 10852



EXTERIOR WINDOW BUCK DETAIL



EXTERIOR DOOR BUCK DETAIL NOT TO SCALE

NOINEEL

D

Bay

www.bsbdesian.com 100 Main St. Suite 209

Safety Harbor, Florida 34695 813 265 4808 JOB NO: 02T12034 PROJ MGR: LC DRAWN: LCC CHECKED:

STRUCTURAL NOTES

AND DETAILS

SD1

JOB SITE PLANS


This set of plans must be kept

on the job site of work at all times

per Sarasota County Ordinance

Sarasota County Planning &

Development Services




DETAILING DIMENSION DETAILING DIMENSION


SD2

BAR	-	180° HO	90° H00K		
SIZE	A or G	L	D	A or G	D
#3	5"	3"	2 1/4"	6"	2 1/4"
#4	6"	4"	3"	8"	3"
#5	7"	5"	3 3/4"	10"	3 3/4"
#6	8"	6"	4 1/2"	12"	4 1/2"
#7	10"	7"	5 1/4"	14"	5 1/4"
#8	11"	8"	6"	16"	6"
#9	15"	II 3/4"	9 1/2"	19"	9 1/2"
#10	17"	13 1/4"	10 3/4"	22"	10 3/4"

STANDARD HOOK SD2



DOOR JAMB DETAIL - MASONRY NOT TO SCALE



STEPPED MASONRY TIE BEAM


SD2

VERTICAL REBAR CENTERED IN CELL SEE PLAN FOR LOCATIONS. FILL CELL -WITH CONCRETE OR GROUT. PROVIDE DOWEL TO MATCH VERTICAL REINF.


> - REMOVE ALL PROTRUSIONS EXTENDING 1/2" OR MORE INTO CELLS OR CAVITIESTO BE GROUTED. - SPACES TO BE GROUTED SHALL BE FREE OF MORTAR DROPPINGS, DEBRIS, LOOSE AGGREGATES, & ANY MATERIAL DELETERIOUS TO MASONRY GROUT.

TYP. VERT. FILLED CELL MASONRY REINF. DETAIL

SD2








I. EACH JAMB OPENING TO BE REINFORCED W (1) #5 BAR VERT. IN CONC. FILLED CELL 2. PRECAST LINTEL FOR OPENING GREATER THAN OR EQUAL TO 6'-O" TO HAVE #5 BENT BARS INTO JAMBS AS SHOWN 3. PRECAST LINTELS SHALL BE "CAST CRETE" OR EQUAL.

TYPICAL PRECAST LINTEL SD2


BOND BEAM "U-BLOCK" (TYP) LAP VERT. FILLED CELL REINF. DOWEL W/ BOND BEAM REINF. BOND BEAM REINF. BOND BEAM FILLED CELL AT CORNER 45 CORNER BAR TYPICAL FOR KNOCK-OUT BLK. # FORM AND POUR TIE BEAMS

CONTINUITY OF THE BEAM REINF. AT CORNERS DETAILS

SD2



CONTINUITY OF REINF. IN FOOTINGS



2"x 4" COLUMNS W (I) ROW OF STAGGERED 16d COMMON WIRE NAILS (D = 0.162", L = 3 1/2") 2"x 6" OR 2"x 8" COLUMNS W (2) ROWS OF STAGGERED 16d COMMON WIRE NAILS (D = 0.162", L = 3 1/2")

TYPICAL STUD COLUMN AND JACK NAILING

I. ADJACENT NAILS ARE DRIVEN FROM OPPOSITE SIDES OF THE COLUMN

2. ALL NAILS PENETRATE AT LEAST 3/4 OF THE THICKNESS OF THE LAST LAMINATION


3. FOR 3-PLY, COLUMN SHALL BE NAILED AS SHOWN FROM EACH SIDE (ONE INTO EACH OUTSIDE FACE OF B.U.C., SAME NUMBER OF ROWS, SAME SPACING)

SD2 NOT TO SCALE


4. FOR 4-PLY, PROVIDE 1/4" DIA. x 5 1/2" LAG SCREWS OR EQUAL (SPACE AS SHOWN FOR

5. FOR 5-PLY, PROVIDE 1/4" DIA. x 7" LAG SCREWS OR EQUAL (SPACE AS SHOWN FOR 3-PLY)


6. REFER TO NDS SECTION 15.3 FOR ADDITIONAL INFORMATION



GARAGE DOOR DETAIL SD2



BRG. FRAME WALL SECT (NO UPLIFT)



TOP PLATE FASTENERS



07

DESIGN www.bsbdesign.com 100 Main St. Suite 209

Safety Harbor, Florida 34695 813 265 4808 JOB NO: 02T12034 PROJ MGR: LCC CHECKED: STRUCTURAL NOTES AND DETAILS


160 East Bay Street Osprey, Florida 34229

Bay Street Village
All Condominium Buildings


JOB SITE PLANS

This set of plans must be kept on the job site of work at all times per Sarasota County Ordinance Sarasota County Planning & Development Services









NOT TO SCALE

C 36.

ENGINEERING, INC.
16704 Tobacco Road, Lutz, Fl. 33558
Phone: (813) 846-0412 | Faz: (813) 896-0210 | EB # 8233
AT HAVE REVIEWED THIS DESIGN AND FOUND IT TO BE IN
HE FLORIDA BUILDING CODE STH EDITION (2014).

Village Buildings 160 East Bay Street Osprey, Florida 342 ondominium Street Bay All Col

DESIGN

www.bsbdesign.com 100 Main St. Suite 209 Safety Harbor, Florida 34695 813 265 4808 JOB NO: 02T12034 PROJ MGR: LCC DRAWN: LCC CHECKED:

S

2

0

STRUCTURAL NOTES

AND DETAILS

SD3